



1 PLUMBING SEWER RISERS

SCALE: NTS

PLUMBING FIXTURE SCHEDULE

MARK	DESCRIPTION	TYPE	ROUGH-IN-SIZES				NOTES
			WASTE	VENT	CW	H.W.	
WC	WATER CLOSET	VALVE	4"	3"	1"	-	3
LAV	LAVATORY IN COUNTER	COUNTER	2"	2"	1/2"	1/2"	1, 2, 3
LAV-WH	LAVATORY ON WALL	WALL HUNG	2"	2"	1/2"	1/2"	1, 2, 3
FD	FLOOR DRAIN	-	2"	2"	-	-	4
SINK	DOUBLE KITCHEN SINK	-	2"	2"	-	-	
SHWR	SHOWER DRAIN	-	3"	2"	1/2"	1/2"	
TUB	TUB W/SHOWER HEAD	-	3"	2"	1/2"	1/2"	
WH	WATER HEATER	-	-	-	3/4"	3/4"	
W/D	WASHER/DRYER COMBO	FLOOR MNT	2"	1-1/2"	3/4"	3/4"	
AHU	AIR HANDLING UNIT	-	2"	2"	-	-	

- NOTES:
- INSULATE PIPING FOR HANDICAP FIXTURE.
 - PROVIDE CHAIR CARRIER FOR WALL HUNG FIXTURE.
 - H.C. - HANDICAP FIXTURE
 - INSTALL CONTINUOUS DRIP VALVE ON ALL FLOOR DRAINS.

PLUMBING LEGEND

SYMBOL	DESCRIPTION
— S — S — S —	SANITARY SEWER
CO	CLEAN OUT
WCO	WALL CLEAN OUT
VTR	VENT THRU ROOF
HB	HOSE BIB

NOTE: ALL PLUMBING LINES ARE SHOWN DIAGRAMATIC.

- FIXTURE NOTES:
- PROVIDE CHAIR CARRIER FOR WALL HUNG FIXTURES.
 - INSTALL CONTINUOUS DRIP VALVE ON ALL FLOOR DRAINS.
 - FIXTURES SELECTED BY OWNER.

DAMMON ENGINEERING, INC.

LOUISIANA & MISSISSIPPI
 8140 LAMAR BLVD SUITE 100 NEW ORLEANS, LA 70118
 PH: 504-885-9832 FAX: 504-885-9833 WWW.DAMMONENGINEERING.COM

RESIDENCE JOSEPHINE CONDOMINIUMS
 2100 St. Thomas St.
 New Orleans, Louisiana 70130

SCALE: AS SHOWN FILE NAME: 15014/Elev02.A
 DATE: 27 Oct. 2015

STEVEN J. FINEGAN ARCHITECTS, LTD.
 A PROFESSIONAL CORPORATION
 123 S. Pierce St. - New Orleans, LA 70119
 (504)486-5744 www.stevfineganarchitect.com
 E-mail: stevfinegan@noxxmail.com

NO.	DATE	REVISIONS

This drawing is the property of STEVEN J. FINEGAN ARCHITECTS, LTD. It is not to be reproduced, copied or altered in whole or in part. It is not to be used for any purpose without the approval of STEVEN J. FINEGAN ARCHITECTS, LTD. and is to be returned on request.