



**HVAC UNIT SCHEDULE**

NO.	TOTAL BTU	CFM	O.A.	HEAT ELEC.		ELECTRICAL		COMMENTS
				kW	VOLTAGE	MCA	CKT BRKR	
1	120,000	4,000	-	15 kW	240V, 3Ø	-	-	1ST FLOOR
2	96,000	3,200	-	15 kW	240V, 3Ø	-	-	2ND FLOOR
3	120,000	4,000	-	15 kW	240V, 3Ø	-	-	SANCTUARY
4	120,000	4,000	-	15 kW	240V, 3Ø	-	-	SANCTUARY

- MECHANICAL NOTES**
1. CONCEALED DUCTWORK TO BE UL-181, CLASS 1, FIBERGLASS DUCTBOARD. DUCTS SHALL BE SIZED TO LIMIT MAIN DUCTS TO 1000 CFM & SECONDARY DUCTS TO 800 CFM. TO BE INSTALLED PER SMACNA STANDARDS.
  2. EXPOSED DUCTWORK TO BE GALVANIZED SHEET METAL PER SMACNA STANDARDS. LINE WITH NEOPRENE COATED 1.0" x 1.5 POUNDS PER CUBIC FOOT DUCT INSULATION.
  3. ROUND FLEXIBLE DUCT TO BE UL-181, CLASS 1, AIR DUCT MATERIALS.
  4. DUCT SIZES SHOWN ARE CLEAR INSIDE DIMENSIONS.
  5. IN ALL SYSTEMS OVER 2000 CFM AND LESS THAN 15,000 CFM, SMOKE DETECTORS SHALL BE INSTALLED IN ACCORDANCE WITH NFPA 72E IN THE RETURN DUCT DOWNSTREAM OF THE AIR HANDLING UNIT AND ALL FILTERS TO AUTOMATICALLY STOP THE FAN.
  6. PROVIDE UL, LISTED 125° F. FIRE-RATED IN RETURN AIR OF EACH SYSTEM UNDER 2000 CFM TO SHUT DOWN THE FAN IN THE EVENT OF FIRE.
  7. PROVIDE UL, LISTED FIRE DAMPERS WHERE REQUIRED AT ALL DUCT PENETRATIONS OF FIRE-RATED ASSEMBLIES AND WHERE REQUIRED BY CODE, INCLUDING OUTSIDE AIR INTAKES.
  8. CONDENSATE DRAINS TO BE PVC PIPE RUN TO PLUMBERS P-TRAP WITHIN FIVE FEET OF AIR HANDLING UNITS.
  9. ALL AIR HANDLING SYSTEMS TO BE BALANCED TO ASSURE PROPER AIR FLOWS PER PLANS.
  10. ALL THERMOSTATS TO BE AUTOMATIC CHANGEOVER WITH HEAT SWITCH.
  11. EXHAUST FAN EQUAL TO BROAN MODEL NO. 100 CF OR EQUAL. FAN SHALL BE CONTROLLED BY A SWITCH ON THE WALL IN THE SAME LOCATION AS LIGHT SWITCHES). PROVIDE BACK DRAFT PREVENTER AND INSTALL WATER PROOF GABLE VENT IN PROPER ROOF LOCATION FOR PLUMBING FIXTURE EXHAUST.
  12. PROVIDE AND INSTALL WATER PROOF GABLE VENT IN PROPER ROOF LOCATION FOR PLUMBING FIXTURE EXHAUST.
  13. ALL SUPPLY AIR VENTS SHALL BE EQUIPPED WITH AIR CONTROL DAMPERS.
  14. LOCATE OUTDOOR UNITS AS SHOWN ON ARCH. DWGS.
  15. REFRIGERANT LINES SHALL BE SIZED BY UNIT MANUFACTURER AND INSTALLED ACCORDING TO MANUFACTURER'S INSTRUCTIONS.
  16. FRESH AIR SHALL BE SUPPLIED TO EACH AIR HANDLER THROUGH EXTERIOR WALL DUCT SUPPLIED WITH A CONTROL DAMPER.
  17. INSTALL FIRE DAMPER WHERE S.A. & R.A. DUCTS PENETRATE 1 HOUR RATED CEILING.
  18. ALL ELECTRICAL, MECHANICAL, AND PLUMBING PENETRATING FIRE WALLS SHALL BE FIRE CALKED. (PENETRATIONS THROUGH RATED CONSTRUCTION SHALL BE SEALED WITH A MATERIAL CAPABLE OF PREVENTING THE PASSAGE OF FLAMES AND HOT GASES WHEN TESTED IN ACCORDANCE WITH ASTM E-151).

<p>EL-BETHEL PENTECOSTAL CHURCH</p> <p><b>DAMMON ENGINEERING. INC.</b></p> <p>1095 FLORIDA AVENUE 985-649-5892 SLIDELL, LA. 70458</p> <p>DAMMONENGINEERING.COM</p>	<p>1st FLOOR MECHANICAL PLAN</p> <p>EUGENE WELLINGTON ALLEN ROAD SLIDELL, LOUISIANA</p>	<p>SCALE: AS NOTED</p> <p>FILE:</p> <p>JOB NO. 1819</p> <p>DATE: 3-29-07</p> <p>SHEET 19</p> <p style="font-size: 2em; font-weight: bold;">M-1</p> <p>OF 22</p>
--	---	---