


PARKING REQUIREMENTS:
 7500 TOTAL SQ. FT.
 TOTAL REQUIRED = 25
 TOTAL PROVIDED = 23 + 2 (KSP) = 25

SITE PLAN
 SCALE: 1"=20'



LEGEND

- PROPERTY LINE
- - - NEW BUILDING
- ▣ LITTER RECEPTACLE
- ▣ CATCH BASIN
- 6"-0" WOODEN FENCE
- WHEEL STOP

LANDSCAPING LEGEND

- GRAPE VITIFLORA OR WAX MYRTLE 1" CALIBER, SIX FOOT HIGH @ 20' O.C.
- AZALEAS
- OAK, ELM OR MAPLE - MINIMUM OF 10' HIGH, CALIBER OF 3"
- CYPRESS OR PINE TREE - MINIMUM OF 12' HIGH, CALIBER OF 4"

NOTE: NATURAL BUFFER AREA MUST BE RESTORED TO ORIGINAL CONDITION. USE A MIXTURE OF OAK, CYPRESS, PINE, ELM, AND MAPLE TREES PLACED UNEVENLY TO CREATE A HEAVILY WOODED, NATURAL APPEARANCE. NO TREE TO HAVE MORE THAN A 10' RADIUS OF BARE GROUND SURROUNDING IT.

SITE LIGHTING

EXTERIOR LIGHTING SHALL BE SHARED OR UNIMPAIRED DIRECTED IN SUCH A MANNER SO THAT NO LIGHTING GLARE OCCURS AND THE PROPERTY LINE ATTENTION OF SUCH LIGHTING SHALL NOT EXCEED ONE FOOT CANDLE AS MEASURED AT THE ADJACENT PROPERTY LINE.

LITTER RECEPTACLES

THE STATES LITTER LAW REQUIRES THAT EVERY PROPERTY WITH FIFTEEN OR MORE PARKING SPACES ARE RESPONSIBLE FOR THE PROCUREMENT, PLACEMENT, AND MAINTENANCE OF LITTER RECEPTACLES. THE LAW ALSO REQUIRES A LITTER RECEPTACLE BE PROVIDED FOR EVERY LOT CONSISTING OF THIRTY OR MORE PARKING SPACES OPERATED FOR PUBLIC USE.

REVISION: 03-01-08

SITE PLAN
 REINE CONSTRUCTION CORP.
 HOWZE BEACH ROAD
 SLIDELL, LOUISIANA

DAMMON ENGINEERING, INC.
 NEW OFFICE BUILDING
 1095 FLORIDA AVENUE 985-649-5882 SLIDELL, LA. 70468
 DAMMONENGINEERING.COM

SCALE(S) NOTED
 FILE:
 JOB NO. 1689
 DATE: 06-17-05
 SHEET 2
 C-1
 OF 13