

S. Leibel Harsney Outbursty

~~addendum #1~~

To: All Plan Holders for the project
to: Revante

Add the following work to the Contract.

1. Remove and replace all Fascia at roof & replace drip edge.

2. Where window unit is ~~installed~~ ^{to be removed} from west wall of building, ~~replace~~ brick with brick that is removed to install new window. ~~Remove~~ ~~brick~~ part brick and reinstall using ~~total~~ original size bricks.

3. ~~or~~ where rough spots in the floor exist,

3. Where walls are to be removed, use acrylic floor patch to fill any ~~voids~~ voids. Chip out and install cap on any pipes prior to patching.

4. Demolish cabinets in ^{and on} wall of offices ~~and~~ and remove far down ~~to~~ to ceiling. Patch as required.

5. Remove all borders on walls and patch as required.

6. Clean and paint existing ~~door~~ metal door frames where being reused.

2

70. The housing authority will, prior to contract award, ~~make~~^{perform} any mold remediation required.