

## SPIRAL STAIRS GENERAL NOTES:

1. RISER HEIGHTS SHALL NOT EXCEED 7".
2. THE STAIRWAY SHALL HAVE A TREAD DEPTH OF NOT LESS THAN 11" FOR A PORTION OF THE STAIRWAY WIDTH SUFFICIENT TO PROVIDE EGRESS CAPACITY FOR THE OCCUPANT LOAD SERVED.
3. AT THE OUTER SIDE OF THE STAIRWAY, AN ADD. 10-1/2" OF WIDTH SHALL BE PROVIDED CLEAR TO THE OTHER HANDRAIL, AND THIS WIDTH SHALL NOT BE INCLUDED AS PART OF THE REQUIRED EGRESS CAPACITY.
4. THE INNER HANDRAIL SHALL BE PROVIDED ON BOTH SIDES OF THE SPIRAL STAIRWAY.
4. THE INNER HANDRAIL SHALL BE LOCATED WITHIN 24", MEASURED HORIZ., OF THE POINT WHERE A TREAD DEPTH NOT LESS THAN 11" IS PROVIDED.
5. THE TURN OF THE STAIRWAY SHALL BE SUCH THAT DESCENDING USERS HAVE THE OUTER HANDRAIL AT THEIR RIGHT SIDE.

39'-10"

4'-9 1/2"