



DAMMON ENGINEERING, INC.

CHIEF ENGINEER
EMMETT
DAMMON, P.E.

CHIEF ARCHITECT
ROBERT
WILTSE

1095 FLORIDA AVENUE
SLIDELL, LA. 70458
OFFICE: 985-649-5832
FAX: 985-641-5950

WEBSITE:
WWW.DAMMONENGINEERING.COM

EMAIL:
DAMMONENG@BELLSOUTH.NET

ARCHITECTURE
ENGINEERING
STUDIES
PLANNING
INVESTIGATION
EXPERT WITNESS

CECIL BOYD'S
CAR WASH
LOT 5A
EAST HALL ST.
SLIDELL, LA

ELECTRICAL
POWER PLAN,
NOTES, &
SCHEDULES

REV:

SCALE: AS NOTED

JOB#: 2074

DATE: 09-13-10

SHEET 16

E-1

OF 18

PANEL: P-1		LOCATION: CARWASH EQUIPMENT ROOM		VOLTAGE: 208/120V, 600A 3Ø, 4W		ENCLOSURE: SURFACE MOUNTED W/EQUIPMENT GND BAR		W-SHUNT TRIP BRK. 22000 AIC	
CCT. NO.	THIN WIRE SIZE	LOAD DESCRIPTION	BREAKER	LOAD (VA)	CCT. NO.	THIN WIRE SIZE	LOAD DESCRIPTION	BREAKER	LOAD (VA)
1	#12	ENTRY UNIT (110V)	20 1	1780	1	#12	ENTRY UNIT (110V)	20 1	1780
3	3/0	WASH BAY #1 JUNCTION BOX	200 3	20775	3	3/0	WASH BAY #2 JUNCTION BOX	200 3	20775
7				20775					20775
9	#6	VACUUM SYSTEM	60 3	5784	9	#6	EXTERIOR SIGN JUNCTION BOX	30 2	1864
11				5784	11				1864
13				5784	13				1864
15	#12	RESTROOM 102 RECEPTACLES	20 1	640	15	#12	WASH BAY #1 LIGHTS	20 1	1536
17	#12	VACUUM SYSTEM AREA-EXIT WEATHERPROOF GFI RECEPTACLE	20 1	180	17	#12	WASH BAY #2 LIGHTS	20 1	1536
19	#12	EQUIPMENT & RESTROOM 101 & 102 LIGHTS	20 1	480	19	#12	AIR COMPRESSOR DEDICATED RECEPTACLE IN EQUIP. ROOM	20 1	180
21	#8	SITE LIGHTING	30 2	800	21	#8	EXIT/EMERGENCY LIGHTS	20 1	24
23				800	23				2407
25	#12	VACUUM SYSTEM AREA-EXIT WEATHERPROOF GFI RECEPTACLE	20 1	1842	25	#12	AIR COMPRESSOR IN EQUIPMENT ROOM (16.7A)	20 1	2405
27	#12	REPRESSURIZATION UNIT IN EQUIPMENT ROOM (5.7A)	20 1	1642	27	#12	REPRESSURIZATION UNIT IN EQUIPMENT ROOM (5.7A)	20 1	1642
29	#6	WHEEL BLASTER-GATLING PUMP UNIT IN EQUIPMENT ROOM (46A)	50 3	4419	29	#6	WHEEL BLASTER-GATLING PUMP UNIT IN EQUIPMENT ROOM (46A)	50 3	4419
31				4420	31				4420
33				4419	33				4419
35	#12	TIRE SHINE PANEL DEDICATED RECEPTACLE IN EQUIP. ROOM	20 1	180	35	#12	VACUUM CANOPY LIGHTS	20 1	1024
37	#12	SPARE	20 1	-	37	#12	SPARE	20 1	-
39	#12	TIRE SHINE PANEL DEDICATED RECEPTACLE IN EQUIP. ROOM	20 1	180	39	#12	SPARE	20 1	-
41	#12	SPARE	20 1	-	41	#12	EF-2 EXHAUST FAN IN EQUIPMENT ROOM	20 1	1200
TOTAL CONNECTED LOAD (VA)=195,142				A=85,781 B=64,280 C=85,101		GROUND BUS GROUND WIRE (G)			

POWER LEGEND

- ⊖ - RECEPTACLE 20A 115V
- ⊖ (with WPT/GFI) - GFI WEATHERPROOF RECEPTACLE
- ⊖ (with J) - JUNCTION BOX
- ⊖ (with P) - POWER PANEL
- ⊖ (with D) - DEDICATED RECEPTACLE 20A 110V

ELECTRICAL NOTES

1. ALL WORK SHALL CONFORM TO THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE, THE GOVERNING ELECTRICAL CODE AND ALL OTHER INSPECTION DEPARTMENTS HAVING JURISDICTION. OBTAIN CERTIFICATES OR APPROVAL WHERE REQUIRED.
2. ALL MATERIALS FURNISHED SHALL BE NEW AND SHALL BE U.L. LISTED.
3. THE DRAWINGS INDICATE SIZE AND GENERAL LOCATION OF WORK. SCALE DIMENSIONS SHALL NOT BE USED. THE EXACT LOCATION AND LOCATION OF ALL LIGHTING FIXTURES, RECEPTACLES AND TELEPHONE OUTLETS, ETC. SHALL BE DETERMINED BY ACTUAL CONDITIONS IN THE FIELD.
4. PRIOR TO BIDDING, CONTRACTOR SHALL VISIT THE JOB SITE AND FAMILIARIZE THEMSELVES WITH THE EXISTING CONDITIONS.
5. ELECTRICAL CONTRACTOR SHALL COORDINATE HIS WORK WITH OTHER TRADES AND WITH OTHER CONTRACTORS WHOSE WORK MAY AFFECT THIS INSTALLATION.
6. ELECTRICAL CONTRACTOR SHALL COORDINATE INCOMING ELECTRICAL SERVICE WITH UTILITY COMPANY AND INCLUDE IN HIS BID ALL CHARGES AND FEES INCURRED IN MODIFICATIONS.
7. WHERE MORE THAN ONE SWITCH OCCURS IN THE SAME LOCATION, THEY SHALL BE INSTALLED IN A GANG TYPE BOX UNDER ONE COVER PLATE.
8. ELECTRICAL CONTRACTOR, BEFORE INSTALLING ANY OF THE WORK, SHALL SEE THAT IT DOES NOT INTERFERE WITH CLEARANCES REQUIRED FOR FINISHED COLUMNS, HUNG CEILINGS, PLASTER, PARTITIONS, WALLS, ETC. AS SHOWN IN THE ARCHITECTURAL DRAWINGS AND DETAILS. IF ANY WORK IS INSTALLED AND IT LATER DEVELOPS THAT SUCH DETAILS OR DESIGN CANNOT BE FOLLOWED, THE CONTRACTOR, AT HIS OWN EXPENSE, SHALL MAKE SUCH CHANGES IN THE WORK AS DIRECTED BY THE ARCHITECT. AS WELL AS TO PERMIT THE INSTALLATION OF THE ARCHITECTURAL WORK AS SHOWN ON THE PLANS AND DETAILS.
9. PERFORM TEST REQUIRED BY THE OWNER OR THE ENGINEER IN CONNECTION WITH THE OPERATION OF THE ELECTRICAL SYSTEM IN THE BUILDING.
10. ALL TESTS SHALL BE MADE IN ACCORDANCE WITH THE LATEST STANDARD OF THE IEEE AND THE NATIONAL ELECTRICAL CODE.
11. MINIMUM CONDUCTOR SIZE SHALL BE #12, 600V INSULATION. MINIMUM SIZE CONDUIT SHALL BE 3/4" EMT FOR INTERIOR USE, AND 3/4" RIGID ALUMINUM FOR EXTERIOR USE. USE CONDUIT # WIRE OR TYPE MC CABLE COPPER, FOR LIGHTS AND RECEPTACLE CIRCUITS. EXTERIOR FITTINGS SHALL BE CAST BOXES AND COVERS. INTERIOR FITTINGS SHALL BE CAST WHERE EXPOSED ON WALLS. STAMPED BOXES MAY BE USED ABOVE CEILINGS IN AIR CONDITIONED SPACES. WHERE LAY IN FIXTURES ARE IN USE, USE 1/4" 2 IS ALLOWED FOR 6" WIPES.
12. ALL ELECTRICAL SWITCHES AND RECEPTACLES SHALL BE RATED AT NOT LESS THAN 20 AMPS.
13. CONTRACTOR SHALL INSTALL WIRING AND OTHER CIRCUIT COMPONENTS TO MATCH EQUIPMENT ACTUALLY INSTALLED.
14. BONDING AND GROUNDING SHALL BE IN ACCORDANCE WITH NFPA 70:230-63, NFPA 250-23, 250-71 & 250-72.
15. GROUND NEUTRAL IN ACCORDANCE WITH NFPA 70:250-23b.
16. FUSES SHALL BE ITT CLASS K5, 250 VOLT, 200,000 AMP INTERRUPTING CAP.
17. EXTERIOR LIGHTING SHALL BE SHADED OR INWARDLY DIRECTED IN SUCH A MANNER SO THAT NO DIRECT LIGHTING OR GLARE IS CAST BEYOND THE PROPERTY LINE. THE INTENSITY OF SUCH LIGHTING SHALL NOT EXCEED ONE FOOT CANDLE AS MEASURED AT THE BUTTING PROPERTY LINE.
18. ALL ELECTRICAL, MECHANICAL AND PLUMBING PENETRATING FIRE PARTITIONS SHALL BE FIRE CAULKED. (PENETRATIONS THROUGH RATED CONSTRUCTION SHALL BE SEALED WITH A MATERIAL CAPABLE OF PREVENTING THE PASSAGE OF FLAMES AND HOT GASES WHEN TESTED IN ACCORDANCE WITH ASTM-E814.)
19. ALL ABOVE GROUND PVC TO BE SCHEDULE 80.
20. SCOTTSDALE LIGHT FIXTURES ARE MULTI-TAPPED AND MUST BE SET AT 120 VOLT SINGLE PHASE.

