


DOOR & HARDWARE SCHEDULE						
MARK	SIZE	DOOR TYPE	FRAME	HDWR. NO.	STC	REMARKS
EXTERIOR DOORS						
①	PR. 1 3/4" x 3/0 x 7/0	1/2 GLASS SOLID WOOD	WOOD	N/A	N/A	
②	1 3/4" x 3/0 x 7/0	1/2 GLASS HOLLOW CORE	WOOD	N/A	N/A	
③	1 3/4" x 3/0 x 7/0	THREE PANEL HOLLOW CORE	WOOD	N/A	N/A	
INTERIOR DOORS						
④	PR. 1 3/4" x 2/6 x 7/0	6 PANEL HOLLOW CORE	WOOD	N/A	N/A	
⑤	1 3/4" x 3/0 x 6/8	6 PANEL HOLLOW CORE	WOOD	N/A	N/A	

WINDOW SCHEDULE						
MARK	SIZE	WINDOW TYPE	FRAME	GLASS	LITES	REMARKS
Ⓐ	NOM. 3'-0" x 5'-0"	EXTERIOR	ALUM.	TINTED	SIX	
Ⓑ	NOM. 3'-0" x 3'-0"	EXTERIOR	ALUM.	TINTED	FOUR	

FINISH SCHEDULE						
ROOM NAME	WALLS	FLOOR	WALL BASE	CEILING	CLG. HT.	COMMENTS
BEDROOM #1	5/8" GYP. PTD.	VCT	RB	GWB	9'-0"	
BEDROOM #2	5/8" GYP. PTD.	VCT	RB	GWB	9'-0"	
BEDROOM #3	5/8" GYP. PTD.	VCT	RB	GWB	9'-0"	
BEDROOM #4	5/8" GYP. PTD.	VCT	RB	GWB	9'-0"	
BEDROOM #5	5/8" GYP. PTD.	VCT	RB	GWB	9'-0"	
BEDROOM #6	5/8" GYP. PTD.	VCT	RB	GWB	9'-0"	
BATH #1	5/8" GYP. PTD.	VCT	RB	GWB	9'-0"	
BATH #2	5/8" GYP. PTD.	VCT	RB	GWB	9'-0"	
BATH #3	5/8" GYP. PTD.	VCT	RB	GWB	9'-0"	
HALF BATH	5/8" GYP. PTD.	VCT	RB	GWB	9'-0"	
OFFICE	5/8" GYP. PTD.	VCT	RB	GWB	9'-0"	
ENTRANCE	5/8" GYP. PTD.	VCT	RB	GWB	9'-0"	
CORRIDOR	5/8" GYP. PTD.	VCT	RB	GWB	9'-0"	
REC ROOM	5/8" GYP. PTD.	VCT	RB	GWB	9'-0"	
KITCHEN	5/8" GYP. PTD.	VCT	RB	GWB	9'-0"	
PANTRY	5/8" GYP. PTD.	VCT	RB	GWB	9'-0"	
WASH ROOM	5/8" GYP. PTD.	VCT	RB	GWB	9'-0"	
ELECTRICAL	5/8" GYP. PTD.	VCT	RB	GWB	9'-0"	
SCREENED PORCH	5/8" GYP. PTD.	VCT	RB	GWB	9'-0"	
CARPORT	5/8" GYP. PTD.	VCT	RB	GWB	9'-0"	

LEGEND:
 GWB GYPSUM WALL BOARD
 RB RUBBER BASE 6" HIGH
 VCT VINYL COMPOSITION TILE

GENERAL NOTES
<p>1. INSULATION AND INSULATION ASSEMBLIES SHALL MEET THE REQUIREMENTS OF SECTION 719. A. CONCEALED INSULATION SHALL HAVE A FLAME SPREAD OF 0-25 AND SMOKE DEVELOPED INDEX OF 0-450. EXCEPT THAT IN COMBUSTIBLE (WOOD FRAME) CONSTRUCTION. B. FACING SHALL COMPLY WITH IBC 2006.</p> <p>2. PROVIDE 5'x5' LANDINGS, LEVEL WITH FINISHED FLOOR, OUTSIDE EXTERIOR DOORS OF BUILDING. THRESHOLDS SHALL BE NOT MORE THAN 1/2" IN HEIGHT AND SHALL BE BEVELED IF MORE THAN 1/4".</p> <p>3. CONTRACTOR TO VERIFY ALL SITE CONDITIONS, BUILDING LOCATIONS, AND DIMENSIONS PRIOR TO CONSTRUCTION.</p> <p>4. MATERIALS SHALL BE NEW AND U.L. LISTED.</p> <p>5. NO WORK SHALL BE CONCEALED UNTIL APPROVED BY LOCAL INSPECTORS.</p> <p>6. CONSTRUCTION SHALL COMPLY WITH ALL PARISH, STATE, AND LOCAL CODES.</p> <p>7. CONTRACTOR TO GUARANTEE WORK FOR ONE YEAR.</p> <p>8. CONTRACTOR SHALL FURNISH WATER AND POWER FROM EXISTING SOURCES.</p> <p>9. EXTERIOR CAULKING SHALL BE THIOKAL CAULK.</p> <p>10. PAINT GRADE TO SHALL BE SHERWIN WILLIAMS OR EQUIVALENT. ALL WORK TO RECEIVE 3 COATS. COLOR SELECTION BY OWNER.</p> <p>11. PROVIDE CLEANUP ON A REGULAR BASIS. NO TRASH STORED IN BUILDING.</p> <p>12. ALL BATT INSULATION SHALL HAVE A CLASS "A" (0-25) FLAME SPREAD IN COMPLIANCE WITH APPLICABLE CODE.</p> <p>13. USE 6" STUDS, OR 4" STAGGERED STUDS AT ALL PLUMBING WALLS.</p> <p>14. PROVIDE GALVANIZED METAL PAN WITH DRAIN AT WATER HEATER LOCATION.</p> <p>15. ALL CORNERS SHALL BE PROPERLY BRACED FOR WIND LOADS. A 48" SHEATHING SHALL BE PROVIDED EVERY 20 FEET OF WALL LENGTH.</p> <p>16. INTERIOR LOCKS ON DOORS IN MEANS OF EGRESS SHALL NOT REQUIRE THE USE OF A KEY, SPECIAL KNOWLEDGE, OR SPECIAL DEVICE TO OPEN IN THE DIRECTION OF EGRESS. ALL DOORS SHALL HAVE LEVER TYPE HANDLES.</p> <p>17. INTERIOR WALLS AND CEILINGS SHALL HAVE A FLAME SPREAD OF 0-200 AND A SMOKE DEVELOPMENT RATING OF 0-450.</p> <p>18. ALL WORK SHALL COMPLY WITH THE LATEST EDITION OF ALL LOCAL, STATE, AND NATIONAL CODES COVERING THE TYPE OF WORK BEING PERFORMED.</p> <p>19. PROVIDE PORTABLE FIRE EXTINGUISHERS IN ACCORDANCE WITH NFPA 101. SEE APPENDIX "E" OF NFPA 101 FOR DISTRIBUTION OF EXTINGUISHERS.</p>



DAMMON
ENGINEERING, INC.

CHIEF ENGINEER
EMMETT
DAMMON, P.E.

CHIEF ARCHITECT
ROBERT
WILTSE

1095 FLORIDA AVENUE
SLIDELL, LA. 70458
OFFICE: 985-649-5832
FAX: 985-641-5950

WEBSITE:
WWW.DAMMONENGINEERING.COM

EMAIL:
DAMMONENG@BELLSOUTH.NET

ARCHITECTURE

ENGINEERING

STUDIES

PLANNING

INVESTIGATION

EXPERT WITNESS

NEW
LIVING
FACILITY

STARC WEST
1705 VIOLA ST
MANDEVILLE, LA

SCHEDULES
AND NOTES

REV:

SCALE: AS NOTED

JOB#: 2081

DATE: 11-4-10

SHEET 10

A-6

OF 17