



**Ordering Information**

Catalog No.	Finishes	Track Mountings	Ballast Module	Lamp	Reflectors
8314WH 8314BK 8314AL	Matte White Matte Black Metallic Aluminum	All Lytespan® Track systems and Multipoint. All PowerArc™ Modular canopies, extension wands, mounting brackets or pipe clamps. Not compatible with ProSpec® or ATOM®. See ballast for details.	Use one of: <b>83B20E</b> <b>83B39E</b> <b>83B70SE</b> <b>83CY39E</b> <b>83CY70E</b> <b>83B39LE</b> <b>83B70E</b>	T4 or T4.5 Single-Ended, G8.5 Base, Clear Ceramic Metal Halide 70W Max.	<b>MHT4RS</b> <b>MHT4RNF</b> <b>MHT4RF</b>

**Features**

1. **Housing:** Die cast aluminum body.
2. **Vertical Pivot:** 0-90° vertical adjustment.
3. **Horizontal Pivot:** Die cast track adapter with infinite rotation.
4. **Track Attachment Fitting:** Molded polycarbonate, rotates into track.
5. **Power Connector:** 5kv rated with insulated pins. Connects to ballast module. Keyed for polarity.
6. **Safety Lens:** Tempered 1/8" glass. Meets or exceeds U.L. safety requirement for metal halide lamps.
7. **Reflector:** (not shown) Interchangeable reflectors available to allow for desired precise beam spread without the need of additional lenses.
8. **Shade:** Die cast aluminum. Accepts Accessory Holder. Reflectors sold separately. See MHT4R S/NF/F specification sheets.

**Accessories**

- 83T4AH** Accessory Holder. Accepts 2 Accessories Max.
  - 83T4S** Snoot Accessory Holder. Accepts 2 Accessories Max.
  - ADF3 (3 3/4" dia.)** Color Filters
  - AF3 (3 3/4" dia.)** Diffusion Filters
  - AL3HC** Hex Cell Louver (For use with 39W Max.)
  - 83EW18WH, BK, AL** 18" Extension Wand
  - 83EW48WH, BK, AL** 48" Extension Wand
  - 83EC72WH, BK** 6' Extension Cord
  - 83PCWH, BK** Pipe Clamp
  - 83MPTWH, BK** Mounting Bracket
- } Compatible with 83B39LE, 83B70E

**Finish**

All painted finishes are baked enamel.

**Electrical**

See ballast module spec sheet.

**Labels**

UL, cUL

Job Information	Type:
<b>Job Name:</b>	
<b>Cat. No.:</b>	
<b>Lamp(s):</b>	
<b>Notes:</b>	