


FLOOR PLAN  
SCALE: 3/8"=1'

WINDOW SCHEDULE									
MARK	DESCRIPTION	TYPE	FRAME	GLASS	LITES	ACCESSORIES	REMARKS		
		SINGLE HUNG						ALL WINDOWS TO BE SELECTED BY OWNER	
A	3'-4"x5'-4"	FIXED	ALUMINUM HOLLOW METAL	TINTED LOW E	PLAIN	TEMPERED-SAFETY	6/6	9/9	SILL HT. = 2'-8" A.F.F.
B	3'-4"x1'-1"								SILL HT. = 6'-11" A.F.F.
C	2'-8"x7'-0"								SILL HT. = 8" A.F.F.

DOOR & HARDWARE SCHEDULE									
MARK	DESCRIPTION	TYPE	FRAME	HINGE	LOCK	ACCESSORIES	REMARKS		
								ALL DOORS TO BE SELECTED BY OWNER	
1	3/0x7/0	ALUM. & GLASS	ALUMINUM HOLLOW METAL	BUILT 1-1/2 PR	KEYED HANDLE	WEATHERSTRIP	ALUM. S.F. W/TRANSOM		
2	3/0x7/0	S. C. WOOD	HOLLOW METAL		DEADBOLT	DOOR STOP			
3	3/0x7/0	H. C. WOOD	HOLLOW METAL		KEYED HANDLE	DOOR STOP			
4	3/0x7/0	ALUMINUM HOLLOW METAL	WOOD		KEYED HANDLE	DOOR STOP			
5	PR 2/6x7/0								
6	3/0x7/0								

- DOOR & HARDWARE NOTES:
- ANY GLAZING TO BE LAMINATED SAFETY GLASS.
  - COORDINATE KEYING SCHEDULE WITH OWNER
  - DOOR STOPS TO BE SELECTED BY OWNER
  - WEATHER-STRIP & THRESHOLD FINISH TO COMPLEMENT OTHER HARDWARE.
  - ALL NEW EXTERIOR DOORS RATED FOR 130 MPH.



**DAMMON**  
ENGINEERING, INC.

CHIEF ENGINEER  
EMMETT  
DAMMON, P.E.

CHIEF ARCHITECT  
ROBERT  
WILTSE

554 OLD SPANISH TRAIL  
SLIDELL, LA. 70458  
OFFICE: 985-649-5832  
FAX: 985-641-5950

WEBSITE:  
WWW.DAMMONENGINEERING.COM

EMAIL:  
DAMMONENG@BELLSOUTH.NET

- ARCHITECTURE
- ENGINEERING
- STUDIES
- PLANNING
- INVESTIGATION
- EXPERT WITNESS

PAUL REES  
OFFICE  
BUILDING  
MANDEVILLE,  
LOUISIANA

FLOOR  
PLAN

REV:

SCALE: AS NOTED

JOB#: 2104

DATE: 03-31-11

SHEET

**A-1**

OF

PRELIMINARY (NOT FOR CONSTRUCTION)