



1 EXISTING 200 LEVEL DEMOLITION PLAN
1/8"=1'-0"

PLAN NOTES - UNLESS NOTED OTHERWISE:
 1. TOP OF EXISTING SLAB EL. 137'-0 1/2"
 2. EXISTING CONCRETE WAFFLE JOIST FLOOR SYSTEM (14"x3" & 3"x3") CONCRETE SLAB = 17"± TOTAL THICKNESS.
 3. (E) - INDICATES EXISTING CONSTRUCTION.
 4. (X) - INDICATES DEMOLITION OF EXISTING FRAMING. DEMOLITION SHALL NOT PROCEED UNTIL ALL PERMANENT AND/OR TEMPORARY SHORING HAS BEEN INSTALLED. SEE STRUCTURAL DRAWINGS FOR PERMANENT SHORING. CONTRACTOR TO PROVIDE TEMPORARY SHORING AS REQUIRED TO FACILITATE THE DEMOLITION WORK. SEQUENCE OF DEMOLITION SHALL BE DETERMINED BY CONTRACTOR. SEE D1, D2, ETC., REFER ALSO TO SECTIONS AND DETAILS FOR DEMOLITION REQUIREMENTS NOT SHOWN ON THIS PLAN.
 5. SEE 3/DS2-6 AND 4/DS2-6 FOR EXISTING TOILET ROOM DEMOLITION PLAN PLANS.
 6. COORDINATE ALL OTHER DEMOLITION, SITE, UTILITY, INTERIOR, ETC., WITH RESPECTIVE DISCIPLINES.
 7. S1, S2, ETC. INDICATES NEW PERMANENT SUPPORT FRAMING TO BE INSTALLED PRIOR TO DEMOLITION. SEE NEW CONSTRUCTION FRAMING PLANS SHEETS S2-2, S2-1, ETC.

2 DEMOLITION NOTES (200 LEVEL)

- (D01) - INDICATES EXISTING 9"x9" CONC. STAR LANDING TO BE REMOVED.
- (D02) - INDICATES EXISTING CONC. STAR TO BE REMOVED.
- (D03) - INDICATES REMOVAL OF EXISTING 12"± CONC. WALLS TO BE REMOVED FROM TOP OF FLOOR TO TOP OF EXISTING DOOR OPENING (+) 8'-4 1/2"±. SECTION OF WALL BETWEEN TOP OF EXISTING OPENING & FLOOR ABOVE TO REMAIN.
- (D04) - INDICATES REMOVAL OF EXISTING 12"± CONC. WALL FOR NEW ELEVATOR DOOR OPENING.
- (D05) - INDICATES EXISTING 16"x16" CONC. CANOPY COLUMN TO BE REMOVED.
- (D06) - INDICATES EXISTING 16"x24" CONC. STAR COLUMN TO BE REMOVED.
- (D07) - INDICATES EXISTING CONC. STAR TO BE REMOVED.
- (D08) - INDICATES EXISTING CONC. FLOOR LANDING TO BE REMOVED.
- (D09) - INDICATES EXISTING 12"± U-SHAPED CONC. STAR COLUMN TO BE REMOVED.
- (D10) - INDICATES EXISTING 12"± CONC. WALL TO BE REMOVED FROM TOP OF FLOOR TO UNDERSIDE OF FLOOR FRAMING ABOVE.
- (D11) - INDICATES EXISTING CONC. WAFFLE SLAB CANOPY TO BE REMOVED.
- (D12) - INDICATES EXISTING CONC. WAFFLE SLAB CANOPY TO BE REMOVED. SEE ALSO S2 FOR NEW PERMANENT COLUMN SUPPORT.
- (D13) - INDICATES EXISTING 14WF43 CRANE BEAM TO BE REMOVED.

3 SHORING NOTES (200 LEVEL)

- (S1) - INDICATES NEW PERMANENT HSS-x-x TO BE INSTALLED FROM LEVEL 100 TO LEVEL 200. NEW COLUMN TO BE INSTALLED PRIOR TO DEMOLITION OF CANOPY D05.
- (S2) - INDICATES EXISTING CONC. STAR TO BE REMOVED.

PRELIMINARY
NOT FOR CONSTRUCTION

No.	Date	Issue	No.	Date	Issue
1	12.23.10	SD PRICING SET			
2	01.18.11	100% SD SET			
3	05.18.11	LNO Meeting			
4	09.15.11	100% DD/ PRICING			

MORPHY CONSULTING ENGINEERS
336 N. Jeff Davis Pkwy.
New Orleans, LA 70119
TEL: (504) 488-1317
FAX: (504) 488-9924
WEB: www.mmi-eng.com
INCORPORATED JOB NO. 10128

HOLABIRD & ROOT | **HOLLY & SMITH LLC**
140 South Dearborn Avenue Suite 500 Chicago, IL 60660
312.357.1771 (tel) 312.357.1909 (fax) www.holabird.com
541 Julia Street Suite 201 New Orleans, LA 70130
504.585.1315 (tel) 504.585.1316 (fax) www.hollyandsmith.com

Project Number	15248.00
Drawn	RAB
Checked	JAS
Proj. Arch./Eng.	JAS

LOYOLA UNIVERSITY NEW ORLEANS
Monroe Hall Renovation

EXISTING 200 LEVEL DEMOLITION PLAN
Sheet Name
Drawing No. **DS2-2**