



PLAN NOTES - UNLESS NOTED OTHERWISE:  
 1. TOP OF SLAB EL. (-)11'-9 1/2". WITH TOPPING SLAB EL. (-)11'-7 1/2".  
 2. EXISTING 12" CONCRETE SLAB WITH 2" TOPPING SLAB THROUGHOUT.  
 3. (E) - INDICATES EXISTING.  
 4. (N) - INDICATES NEW CONSTRUCTION.  
 5. (E) - INDICATES EXISTING 4 PILECAP WITH TOP OF CAP AT EL. (-)5'-0".  
 6. (E) - INDICATES NEW 4 PILECAP WITH TOP OF CAP AT EL. (-)5'-0". PILE TYPE PER GEN. NOTE 8A.  
 7. (E) - INDICATES EXISTING PILES WITH NEW CONSTRUCTION.  
 8. (N) - INDICATES SINGLE 14"x14" PRECAST PILE. SEE SECTIONS FOR CUT-OFF.  
 9. (E) - INDICATES OUTLINE OF BASEMENT, EXIST. BASEMENT.  
 10. (N) - INDICATES NEW 2 PILE CAP TOP OF CAP AT EL. (-)7'-7 1/2". NEW PILE TYPE PER GEN. NOTE 8B.  
 11. (E) - INDICATES EXISTING PILES WITH NEW CONSTRUCTION.  
 12. (N) - INDICATES NEW PILES WITH NEW CONSTRUCTION.

1 FOUNDATION/000 LEVEL  
 S2-0 FRAMING PLAN 1/8"=1'-0"

2 ELEVATOR PIT  
 S2-0 FRAMING PLAN 1/8"=1'-0"

PRELIMINARY  
 NOT FOR CONSTRUCTION

No.	Date	Issue	No.	Date	Issue
1	12.23.10	SD PRICING SET			
2	01.18.11	100% SD SET			
3	05.18.11	LNO Meeting			
4	09.15.11	100% DD/ PRICING			

**MORPHY CONSULTING ENGINEERS**  
 336 N. Jeff Davis Pkwy.  
 New Orleans, LA 70119  
 TEL: (504) 488-1317  
 FAX: (504) 488-9224  
 WEB: www.mmi-eng.com  
 INCORPORATED JOB NO. 10128

**HOLABIRD & ROOT**  
 140 South Dearborn Avenue  
 Suite 500  
 Chicago, IL 60660  
 312.357.1771 (toll)  
 312.357.1909 (fax)  
 www.holabird.com

**HOLLY & SMITH LLC**  
 541 Julia Street  
 Suite 201  
 New Orleans, LA 70130  
 504.585.1315 (toll)  
 504.585.1316 (fax)  
 www.hollyandsmith.com

Project Number	15248.00
Drawn	RAB
Checked	JAS
Proj. Arch./Eng.	JAS

**LOYOLA UNIVERSITY NEW ORLEANS**  
**Monroe Hall**  
 Renovation

Project Name	FOUNDATION/000 LEVEL FRAMING PLAN
Sheet Name	
Drawing No.	<b>S2-0</b>