



8'x24' Unit Specifications

Serial Number DBI04137

Qty	Description/Memo	Color/Location
<u>FRAMES</u>		
1	Detachable Hitch	
1	10 in I-Beam	
1	Outrigger Frame	
<u>FLOORS</u>		
160	Woven Nylon Impregnated Vinyl Bottom Board	
1	2x6 Floor Joists 16" O.C.	
160	3/4 sturdfloor plywood	
160	Covering - Block Tile 1/8	
<u>WALLS & PARTITIONS</u>		
1	Wall Ht - 8'	
5	2x4 Studs, 16" OC	
1	Standard Trim	
56	Double Top Plate	
1	1/2in VCG (Factory Std.)	
<u>INTERIOR DOORS</u>		
2	36X80 Std. Door	
1	Keyed Levers FOR CLOSET	
1	Lever-Privacy	
<u>ROOF</u>		
1	Truss Type - Cottage	
1	IBC Code	
1	20 # Live Load	
56	Overhang sides and ends 4"	
1	Truss Spacing - 24" OC	
1	Roof Sheathing - 7/16" OSB	
160	29 Ga. Hi-Rib Steel Roof Cover	



8'x24' Unit Specifications

Serial Number DBI04137

Qty	Description/Memo	Color/Location
<u>ROOF</u>		
1	Roof Sheathing - 7/16" OSB	
160	29 Ga. Hi-Rib Steel Roof Cover	
1	Roof Ventilation	
1	Hurricane Straps	
<u>CEILING</u>		
160	C-Spray	
<u>PLUMBING</u>		
1	1/2 Bath, Handicap Accessible	
1	Lavatory, wall mount w/ mirror W/ BOOT UNDER SINK	
1	Supply Lines - CPVC	
1	Mirror- Standard	
1	Toilet Paper Holders	
1	EEmax/ Chromomite	
1	Handicap Commode with grab bars-STD.	
1	Floor Drain w/ Trap Primer	
<u>ELECTRICAL</u>		
1	100 Amp Panel Box	
1	Single Phase	
4	240 Flourescent Lights- Surface Mount	
1	Porch Lights - Photo Cell	
2	Blank J Boxes	
1	Bathroom Vent/Light Combo	
160	EMT CONDUIT (UPGRADE)	
1	Receptacles @ 10' On Center Max.	
1	Receptacles - GFI Protected	



8'x24' Unit Specifications

Serial Number DBI04137

Qty	Description/Memo	Color/Location
<u>ELECTRICAL</u>		
1	Receptacles - Exterior GFI Protected	
1	Em./Exit Lite @Ext. Doors	
1	Double Switch	
<u>HVAC</u>		
15	Standard Duct w/ Diffuser 12' OC	
8	Plenum Wall	
1	1 Ton 5KW	
1	10 KW Heat Strip	
1	Thermostat- Standard	
	Fiberglass Supply Duct	
	Fiberglass Return Duct	
<u>CABINETS</u>		
1	Standard File Cabinet	
8	Counter Top/No cabinets	
<u>EXTERIOR</u>		
56	Hi-rib Steel 29 Gauge	
<u>WINDOWS</u>		
2	24x54 V/S Insulated B/B	
1	46x27 H/S Insulated B/B	
3	PVC Blinds	
<u>EXTERIOR DOORS</u>		
1	36x80 Classroom 10x10 V/B	
1	Lever Hardware	
1	Closer	
<u>INSULATION</u>		
160	R-19 Floor	
56	R-13 Exterior Wall	