

Type	Rev.	Fixture Type	Voltage	Lamp	Catalog Number	Notes
SA		RECESSED	120	(2) PHILIPS PL-C18W/830/4P/ALTO	LIGHTOLIER 8051CCD-P-6218HU; OR PRE-APPROVED EQUAL BY KURT VERSEN, KIRLIN, OR JUNO	COMPACT FLUORESCENT DOWN LIGHT
SA1		RECESSED	120	(2) PHILIPS PL-C18W/830/4P/ALTO	LIGHTOLIER 8096CCL-P-7218HU; OR PRE-APPROVED EQUAL BY KURT VERSEN, KIRLIN, OR JUNO	COMPACT FLUORESCENT SHOWER LIGHT
SB		RECESSED	120	Q500PAR56/MFL	TIMES SQUARE LIGHTING SB56 (ALDMOD)-B-MC-GF9-600 SPREAD LENS-CC18 COIL CORD-SC-24 SAFETY CABLE	PROSCENIUM ARCH DOWN LIGHT
SB1		RECESSED	120/12	USHIO 50W TITAN LAMP 1003553 EXN/FG/ULTRA TITAN	LIGHTOLIER 2000LVR-2013CD-PAINT TRIM RING TO MATCH ADJACENT SURFACE	LOWER LOBBY #001: ARCADE BOX OFFICE #109; ARCADE DOWN LIGHT
SB2		RECESSED	XXX	PHILIPS CDM35/TC/830	HE WILLIAMS DOWN LIGHTING CMH45-W-T4.5/G8.5-SATIN GLOW-RETRO FIT PAN	EXTERIOR DOWN LIGHTS
SB3		RECESSED	120/12	USHIO 50W TITAN LAMP 1003553 EXN/FG/ULTRA TITAN	LIGHTOLIER 2000LVR-2013CD-AF25Y SPREAD LENS-PAINT TRIM RING TO MATCH ADJACENT SURFACE	ORCHESTRA HOUSE LIGHTS; ORCHESTRA LOGE BAR
SB4	4	RECESSED	120/12	USHIO 50W TITAN LAMP 1003553 EXN/FG/ULTRA TITAN	EUREKA LIGHTING 1008-CLR-HAL MR16 500W-1600C-0.35.E	VIP BAR
SB5	2	RECESSED	120/12	USHIO 50W TITAN LAMP 1003553 EXN/FG/ULTRA TITAN	LIGHTOLIER 2000LVR-2013CD-AL2HC HEXCELL LOUVER-PAINT TRIM RING TO MATCH ADJACENT SURFACE	ARCADE NICHE UP LIGHT
SC		SCONCE	120	PHILIPS F14T5/830/ALTO	LIGHTOLIER FC14U-FCG1	STAGE LEVEL BATHROOM: BASEMENT DRESSING RM
SC1		SCONCE	120	PHILIPS F28T5/830/ALTO	LIGHTOLIER FC28U-FCG3	PRINCIPAL DRESSING RM: BASEMENT DRESSING RM
SC2	4	SCONCE	120	PHILIPS BC60B10C/CLL6/2	CORBETT LIGHTING 120-11	LOGE LEVEL VIP LADIES RESTROOM
SC3	4	SCONCE	120	PHILIPS BC60B10C/CLL6/2	SCHONBEK MARIA THERESA 5600-HERITAGE GEMCUT CRYSTAL-23 ETRUSCAN GOLD FINISH-PROVIDE CUSTOM SHADE TO MATCH HISTORIC SHADE SHROUD	LOGE LEVEL WOMEN'S RESTROOM
SC4		SCONCE	120	60A - CLEAR	HINKLEY LIGHTING 2989SN	BASEMENT LEVEL RESTROOM
SC5	3	SCONCE	120	PHILIPS BC60B10C/CLL6/2	SCHONBEK MARIA THERESA 5600-HERITAGE GEMCUT CRYSTAL-23 ETRUSCAN GOLD FINISH-PROVIDE CUSTOM SHADE TO MATCH HISTORIC SHADE SHROUD	LOGE LEVEL WOMEN'S RESTROOM
SC6	2	SCONCE	120	(2) PHILIPS BC40B10C/CLL6/2	PECASO GROUP ROMANZA 4900-2W-ANTIQUA GOLD-HEIRLOOM GRANDCUT CRYSTAL	ORCHESTRA/LOGE LOBBY
SC7		SCONCE	120	60T10/64F24II	WINONA LIGHTING 4618-I-120-CPL-BRONZE PAINTED FINISH	ORCHESTRA LEVEL STAIRS TO LOWER LEVEL BATHROOMS
SC8	2	SCONCE	120	PHILIPS PL-C18W/830/4P/ALTO	CHARLES LOOMIS PANINO S14-FLUORESCENT-ETCHED WHITE ACRYLIC	ARCADE MEN'S RESTROOM
SC9	2	SCONCE	120	PHILIPS PL-C18W/830/4P/ALTO	CHARLES LOOMIS PANINO S14-FLUORESCENT-ETCHED WHITE ACRYLIC	ARCADE WOMEN'S RESTROOM
SC10	3	NOT USED				
SC11	4	SCONCE	120	PHILIPS PL-C18W/830/4P/ALTO	CHARLES LOOMIS PANINO S14-FLUORESCENT-ETCHED WHITE ACRYLIC	VIP RESTROOMS
SC12	2	SCONCE	120	60A	HINKLEY LIGHTING 11400L	GROTTO WALL SCONCE BASEMENT LEVEL
SC13	2	SCONCE	120	60A	HINKLEY LIGHTING 11400L	GROTTO WALL SCONCE BASEMENT LEVEL
SC14	3	SCONCE	120	60A	EUROFASE 16036-017 PENCHANT WALL SCONCE	VIP ROOM
SD		RECESSED WALL	120	LED (INCLUDED)	COLE LIGHTING 6P/SL157-BLUE-SCL-BLK; PROVIDE JUNCTION BOX. (THIS FIXTURE HAS A BLUE LED, A BLACK SHARP CUT-OFF LOUVER, AND BLACK FACEPLATE) - OR PRE-APPROVED EQUAL BY DEVINE	STAGE RUNNING LIGHTS
SD1		RECESSED WALL	120	LED (INCLUDED)	LIGHTOLIER LP-2-S-IV-VERIFY MOUNTING CONDITIONS PRIOR TO ORDERING. CONTRACTOR TO PROVIDE RECESSED SINGLE GANG JUNCTION BOX AS REQUIRED. IF RECESSING FIXTURE IS NOT POSSIBLE, PROVIDE PANDUIT JB1F5EA-EI ELECTRIC IVORY SURFACE MOUNT OUTLET BOX AS REQUIRED. ALL DIP SWITCHES SET TO LOW UNLESS NOTED OTHERWISE-FIELD PAINT TO MATCH ADJACENT SURFACE	HOUSE SAFETY LIGHTS
SD2		SURFACE WALL	120	LED (INCLUDED)	COLE LIGHTING 6P/SL157-BLUE-SCL-BLK; PROVIDE SURFACE MOUNT JUNCTION BOX. (THIS FIXTURE HAS A BLUE LED, A BLACK SHARP CUT-OFF LOUVER, AND BLACK FACEPLATE) - OR PRE-APPROVED EQUAL BY DEVINE	SURFACE STAGE RUNNING LIGHTS
SD3		SURFACE WALL	120	LED (INCLUDED)	LIGHTOLIER LP-2-S-IV-VERIFY MOUNTING CONDITIONS PRIOR TO ORDERING-FIELD PAINT TO MATCH ADJACENT SURFACE-PROVIDE PANDUIT JB1F5EA-EI ELECTRIC IVORY SURFACE MOUNT OUTLET BOX AS REQUIRED. ALL DIP SWITCHES SET TO LOW UNLESS NOTED OTHERWISE-FIELD PAINT TO MATCH ADJACENT SURFACE	SURFACE HOUSE SAFETY LIGHTS
SD4		SURFACE WALL	120	LED (INCLUDED)	COLE LIGHTING 6P/SL157-GLASS-WARM WHITE-BLK; PROVIDE SURFACE MOUNT JUNCTION BOX. (THIS FIXTURE HAS A WARM WHITE LED, GLASS FRONT FACES, AND BLACK FACEPLATE) - OR PRE-APPROVED EQUAL BY DEVINE	BALCONY WORK LIGHTS
SE		NOT USED				
SF		SURFACE WALL	120	OSRAM CF26DT/E/IN/827	CANLET BFWF26H-120-G-GPC-PROVIDE INTEGRAL JUNCTION BOX FOR SIDE ENTRY CONDUIT - OR PRE-APPROVED EQUAL BY STONCO	CATWALKS
SG		TRACK	120	NONE	LIGHTOLIER 800TBK SERIES - CONTRACTOR IS RESPONSIBLE FOR ALL LENGTHS, FEEDS AND FITTINGS AS REQUIRED TO ENSURE A COMPLETE SYSTEM - OR PRE-APPROVED EQUAL BY JUNO, HALO	CONTROL ROOM & SPOT PLATFORM
SG1		TRACK FIXTURE	120	OSRAM 75PAR30/CAP/SPL/FL30	LIGHTOLIER 7630; OR PRE-APPROVED EQUAL BY JUNO, HALO	CONTROL ROOM & SPOT PLATFORM
SH		SURFACE	130	500T3/CL	HUBBELL QL-505 - PROVIDE ALL HARDWARE REQUIRED TO MOUNT FIXTURES PER DRAWINGS - OR PRE-APPROVED EQUAL	STAGE WORK LIGHT
SI		NOT USED				

Type	Rev.	Fixture Type	Voltage	Lamp	Catalog Number	Notes
SJ		RECESSED	120	LED (INCLUDED)		EDGELYTE EL/F/32-87/12" o.c./X/C (BLUE LED WITH 1 RED LED AT CENTERLINE) WITH REMOTE POWER SUPPLY WITH INTEGRAL DIMMER-PROVIDE DMX CONTROL. AVAILABLE FROM FUTURE-LIGHT 440-801-1310
SK		RECESSED	XXX	F025/830/XP/ECO F032/830/XP/ECO QUANTITIES AS REQUIRED		LITECONTROL 20-LENGTHS PER DRAWINGS-T8-CWM-ELB10-XXX
SL		SURFACE WRAP	XXX	(2)F032/830/XP/ECO		H.E. WILLIAMS 17-4-232-A-EB2-VERIFY VOLTAGE- SURFACE MOUNT
SL1		SURFACE WRAP	XXX	(4)F032/830/XP/ECO		H.E. WILLIAMS 17-4-232-A-EB2-VERIFY VOLTAGE- SURFACE MOUNT-CREATE AN 8'-0" LONG FIXTURE
SL2	2	SURFACE	XXX	F032/830/XP/ECO		PRUDENTIAL LIGHTINGWAL-14-P-1T8-04-TMW TEXTURE MATTE WHITE FINISH-SC-XXX-WM-
SL3		SURFACE	XXX	(1) TL5C22W/830 (1) TL5C40W/830		PRISMA LIGHTING 074994
SL4		SURFACE	XXX	(2) F032/830/XP/ECO		HE WILLIAMS 91-4-232-EB2-XXX-SURFACE MOUNT
SL5		SURFACE	XXX	(2) F032/830/XP/ECO		HE WILLIAMS 31-4-232-4-EB2-XXX-SURFACE MOUNT
SM		RECESSED	XXX	(2)F032/830/XP/ECO		H.E. WILLIAMS 50-G-524-2-32-SA12125-EB2-VERIFY VOLTAGE
SN		SURFACE	120	60A		BELFER LIGHTING 2504-12"-S-F-P-1294-01-45 WIRE GUARD-PROVIDE LENGTHS, FEEDS, FITTINGS, MOUNTING HARDWARE, END AND CORNER CONDITIONS AS REQUIRED FOR COMPLETE INSTALLATION: OR PRE-APPROVED EQUAL BY TIVOLI
SO		NOT USED				
SP		EXTERIOR PENDANT	120	26W COMPACT FLUORESCENT INCLUDED		HINKLEY LIGHTING 1422AHES
SP1		CASE LIGHTING	120	LED (INCLUDED)		JO LIGHTING 0-034-3KHO-65-101-1-LENGTHS PER DRAWING-120V; OR PRE-APPROVED EQUAL BY WINONA LIGHTING
SP2		EXTERIOR SURFACE	XXX	PHILIPS CDM35/PAR30/LM/SP3/K/ALTO		QBK LIGHTING SE-0-BZW-0-C FLUSH-PC-H35M-XXX
SP3		EXTERIOR SURFACE	XXX	PHILIPS CDM35/PAR30/LM/SP3/K/ALTO		QBK LIGHTING SE-0-BZW-10-C FLUSH-PC-H35M-XXX
SP4		EXTERIOR SCONCE	120	26W COMPACT FLUORESCENT INCLUDED		HINKLEY LIGHTING 1424AHES
SP5	2	EXTERIOR POST TOP	120	18W COMPACT FLUORESCENT INCLUDED		HINKLEY LIGHTING 1421AHES-COORDINATE ATTACHMENT TO POST WITH CONTRACTOR
SP6	1	EXTERIOR SURFACE	120	LED (INCLUDED)		COLOR KINETICS eW GRAZE POWERCORE 2700K 30X60-LENGTHS PER DRAWING-PAINT FINISH TO MATCH ADJACENT SURFACE-LENGTHS PER DRAWINGS-120V-PROVIDE CLARE SHIELD-PROVIDE LENGTHS, FEEDS, FITTINGS, MOUNTING HARDWARE AS REQUIRED FOR COMPLETE INSTALLATION
SP7		EXTERIOR SURFACE	XXX	CDM70T6/830		BK LIGHTING YO-FL-0-BZW VERIFY FINISH-9-CS-RM-H70M-120-SN-0-BZW-12" IN LENGTH-REMOTE BALLAST IN ACCESSIBLE LOCATION OUT OF SITE FROM PUBLIC VIEW
SP8	2	EXTERIOR SCONCE	XXX	PHILIPS PL-C 13W/830		CANLET 68-03 MIDNIGHT BLACK FINISH-FWF-13W-XXX-00-29 PRISMATIC GLOBE - OR PRE-APPROVED EQUAL BY STONCO
SP9	2	EXTERIOR SURFACE	XXX	CDM70T6/830		KIM LIGHTING ALF13-70PMHXXX-BL BLACK FINISH PRIOR TO ORDERING-HDS-FS/BL BLACK-SMT/BL
SP10	2	EXTERIOR SURFACE	XXX	MHC100C/U/MP/3K/ALTO		GARDCO LIGHTING 104-WT-XXX-BLP BLACK FINISH-SL-VERIFY MOUNTING CONDITION AND CONDUIT RUN PRIOR TO PURCHASE
SP11		EXTERIOR RECESSED	XXX	QL85W/80TWIST BASE		KIRLIN LIGHTING QRR-10079-DAMP LABEL
SQ		SURFACE	120	(3) PHILIPS BC40B10C/CLL6/2		HINKLEY LIGHTING 2999SN
SQ1	3	SURFACE	120	CFS38W/GR10q-4		BOYD LIGHTING 9932-FLUORESCENT-SATIN NICKEL
SQ2	3	SURFACE	120	CFS38W/GR10q-4		BOYD LIGHTING 9932-FLUORESCENT-SATIN NICKEL
SQ3	4	SURFACE	120	(3) 60A		CORBETT LIGHTING 86-33
SQ4	4	SURFACE	120	(3) 60A		CORBETT LIGHTING 86-33
SQ5	4	SURFACE	120	CFS38W/GR10q-4		BOYD LIGHTING 9932-FLUORESCENT-SATIN NICKEL
SQ6	3	SURFACE	120	(6) 60A		EUROFASE 16035-010 PENCHANT-MODIF OVER ALL HEIGHT 17"
SR	2	HISTORIC EXISTING	120	(2) S11 AMBER/ORANGE		EXISTING LIGHT FIXTURE TO BE RESTORED PER SPECIFICATIONS NOTED IN SECTION 16512 HISTORIC ORNAMENTAL LIGHT FIXTURES - BY OWNER
SR1	2	HISTORIC EXISTING	120	(1) S11 AMBER/ORANGE		EXISTING LIGHT FIXTURE TO BE RESTORED PER SPECIFICATIONS NOTED IN SECTION 16512 HISTORIC ORNAMENTAL LIGHT FIXTURES - BY OWNER
SR2	2	HISTORIC EXISTING	120	(1) 25W A-19 AMBER		EXISTING LIGHT FIXTURE TO BE RESTORED PER SPECIFICATIONS NOTED IN SECTION 16512 HISTORIC ORNAMENTAL LIGHT FIXTURES - BY OWNER
SR3	2	HISTORIC EXISTING	120	(6) PHILIPS BC25F15/A/LL6/2		EXISTING LIGHT FIXTURE TO BE RESTORED PER SPECIFICATIONS NOTED IN SECTION 16512 HISTORIC ORNAMENTAL LIGHT FIXTURES - BY OWNER
SR4	2	HISTORIC EXISTING	120	PHILIPS BC25F15/A/LL6/2		EXISTING LIGHT FIXTURE TO BE RESTORED PER SPECIFICATIONS NOTED IN SECTION 16512 HISTORIC ORNAMENTAL LIGHT FIXTURES - BY OWNER
SR5	2	HISTORIC EXISTING	120	(1) A19		EXISTING LIGHT FIXTURE TO BE RESTORED PER SPECIFICATIONS NOTED IN SECTION 16512 HISTORIC ORNAMENTAL LIGHT FIXTURES - BY OWNER
SR6	2	HISTORIC EXISTING	120	(12) S11 AMBER (18) 25W CLEAR FLAME		EXISTING LIGHT FIXTURE TO BE RESTORED PER SPECIFICATIONS NOTED IN SECTION 16512 HISTORIC ORNAMENTAL LIGHT FIXTURES - BY OWNER
SR7	2	HISTORIC EXISTING	120	(4) CIRCUITS TO BE DETERMINED; 40w LAMPS		EXISTING LIGHT FIXTURE TO BE RESTORED PER SPECIFICATIONS NOTED IN SECTION 16512 HISTORIC ORNAMENTAL LIGHT FIXTURES - BY OWNER

THE SAENGER THEATRE RENEWAL PROJECT

142 North Rampart Street
New Orleans, LA

Client
Saenger Theatre Redevelopment Company
200 West Loop South, Suite
1040 Houston TX 77027

Architect
MARTINEZ+JOHNSON
ARCHITECTURE

1412 Eye St., NW
Washington, DC 20005
202.333.4480

Structural Engineer
Shawn J. Franke, P.E.
549 Heimer Road San
Antonio TX 78232
210.979.7900

Theatre Consultant
Schuler Shook
123 Third Street North #210
Minneapolis, MN 55401
612.339.5958

Acoustical Engineer
Akustiks
93 North Main Street South
Norwalk, CT 06884
202.299.1504

MEP Engineer
JBA Consulting Engineers, Inc.
3525 N. Causeway Blvd, Suite
500 Metairie, LA 70002
504.830.0139

Civil Engineer
Linfield, Hunter, & Junius, Inc.
3608 18th Street Suite 200
Metairie, LA 70002
504.833.5300

Architectural Historian
EHT Traceries, Inc.
1121 Fifth Street NW
Washington, DC 20001
202.393.1199

THEATRE PLANNERS LIGHTING DESIGNERS Schuler Shook

THESE DRAWINGS, SPECIFICATIONS, AND OTHER DOCUMENTS, COLLECTIVELY, THE "DOCUMENTS" INCLUDING WITHOUT LIMITATION ELECTRONIC VERSIONS THEREOF AND THE IDEAS, DESIGNS, AND ARRANGEMENTS REPRESENTED THEREBY, ARE AND SHALL REMAIN THE PROPERTY OF MARTINEZ + JOHNSON ARCHITECTURE PC, AS DEFINED BY APPLICABLE CONTRACTUAL AGREEMENTS ("THE AGREEMENTS") AND AS PROTECTED BY THE COPYRIGHT STATUTES OF THE UNITED STATES. USE OF THE DOCUMENTS SHALL BE STRICTLY LIMITED TO THE PROJECT FOR WHICH THEY WERE PREPARED AND DEVELOPED ("THE PROJECT") PER THE TERMS OF THE AGREEMENTS. NO PART OF THE DOCUMENTS SHALL BE COPIED, DISCLOSED TO OTHERS, OR USED IN CONNECTION WITH ANY OTHER WORK OR PROJECT, OR BY ANY OTHER PERSONS FOR ANY PURPOSES, OTHER THAN THE COMPLETION OF THE PROJECT, WITHOUT THE SPECIFIC WRITTEN AUTHORIZATION OF MARTINEZ + JOHNSON ARCHITECTURE PC. THE DOWNLOADING, OPENING, OR VIEWING OF ELECTRONIC VERSIONS OF THE DOCUMENTS OR VISUAL CONTACT WITH ANY PRINTED FORM THEREOF SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE RESTRICTIONS.

7502

DATE:	No.:	ISSUE:
02.19.10	1	PERMIT SET
04.02.10	2	GMP CONTRACT SET
11.11.10	-	CONTRACT SET

DATE:	No.:	REVISION:

SHEET TITLE:

LIGHT FIXTURE SCHEDULE

AL-4.10