

| Type | Rev. | Fixture Type | Voltage | Lamp | Catalog Number | Notes |
|------|------|--------------------|---------|--------------------------------|---|--------------------------------------|
| SW3 | | NOT USED | | | | |
| SW4 | 2 | PENDANT | 120 | (12) PHILIPS BC40B10C/CL/LL8/2 | PECASO GROUP VERSAILLES 5100-12-ANTIQUE GOLD-HEIRLOOM GRANDCUT CRYSTAL | LOGE LEVEL STAIRS TO ORCHESTRA |
| SW5 | 2 | PENDANT | 120 | (6) PHILIPS BC40B10C/CL/LL8/2 | PECASO GROUP VERSAILLES 5100-J&S 5100-6-ANTIQUE GOLD-HEIRLOOM GRANDCUT CRYSTAL | ORCHESTRA/LOGE LOBBY |
| SW6 | | PENDANT | 120 | (8) PHILIPS BC40B10C/CL/LL8/2 | QUORUM INTERNATIONAL 6916-8-86 OIL RUBBED BRONZE FINISH VERIFY | GROTTO PENDANT BASEMENT LEVEL |
| SX | | NOT USED | | | | |
| SY | | THEATRICAL FIXTURE | 120 | HPL575/115X | ELECTRONIC THEATRE CONTROLS SOURCE FOUR 14DEGREE 414-BLACK-C TWIST LOCK CONNECTOR-414LT-400SC-400CC-400RS-407CF-400PTH6-400PH-A-TEMPLATE TO BE DETERMINED | AUDIENCE ARCHITECTURAL ORNAMENTATION |
| SY1 | | THEATRICAL FIXTURE | 120 | HPL575/115X | ELECTRONIC THEATRE CONTROLS SOURCE FOUR PARNEL-BLACK-C TWIST LOCK CONNECTOR-407CF-400SC-400CC-400PTH6-BLUE DICHROIC COLOR FILTER TO BE DETERMINED-T-PROVIDE 1 1/2" I.D. PIPE BOOM AND FLANGE BASE PER DETAIL-PROVIDE ONE MATING TWIST LOCK RECEPTACLE PER FIXTURE, CONNECT TO CIRCUIT INDICATED | BLUE CEILING |
| SY2 | | CLOUD MACHINE | 120 | HPL575/115X | ELECTRONIC THEATRE CONTROLS SOURCE FOUR 50DEGREE 450-BLACK-C TWIST LOCK CONNECTOR-450LT-400SC-400CC-407CF-400PTH-PROVIDE GREAT AMERICAN MARKET TSL5801-UTILIZE TSLGAM-15 CLOUDS PATTERN | AUDIENCE CLOUDS |
| SY3 | | THEATRICAL FIXTURE | 120 | HPL575/115X | ELECTRONIC THEATRE CONTROLS SOURCE FOUR PAR MCM-BLACK-C TWIST LOCK CONNECTOR-407CF-400SC-400CC-400 WFL-400XBTH CROSS BAFFLE TOP HAT-PROVIDE 1 1/2" I.D. PIPE BOOM AND FLANGE BASE PER DETAIL-PROVIDE ONE MATING TWIST LOCK RECEPTACLE PER FIXTURE, CONNECT TO CIRCUIT INDICATED | MAIN FLOOR HOUSE LIGHT |
| SY4 | | THEATRICAL FIXTURE | 120 | CDM150/T6/830 | ELECTRONIC THEATRE CONTROLS SOURCE FOUR HID-PAR-150-BLACK-C TWIST LOCK CONNECTOR-407CF-400SC-400CC-400 LS4-400XBTH CROSS BAFFLE TOP HAT-PROVIDE ONE MATING TWIST LOCK RECEPTACLE PER FIXTURE, CONNECT TO CIRCUIT INDICATED | METAL HALIDE HOUSE LIGHT |
| SZ | 3 | FIBEROPTICS | 120 | 250WATT MR16 (INCLUDED) | VISUAL LIGHTING TECHNOLOGIES LGE250H-3-28-D1-T-D-120/60-3LC DIMMING CONTROL OF ILLUMINATOR AND SEPARATE CONTROL OF TWINKLE WHEEL-PROVIDE (2) 2.0MM F-MF-EL-PM-2 FIBERS, (48) 1.5MM F-MF-EL-PM-1.5 FIBERS, (100) 1.0MM F-MF-EL-PM-1 FIBERS, (408) 0.75MM F-MF-EL-PM-0.75 FIBERS; COORDINATE ILLUMINATOR QUANTITIES, LOCATIONS, INSTALLATION AND SYSTEM REQUIREMENTS WITH MANUFACTURER FOR COMPLETE STAR CEILING SYSTEM-FIBER-OPTIC SYSTEM TO BE INSTALLED BY ELECTRICAL CONTRACTOR | STAR CEILING |

GENERAL NOTES:

- A - CONTRACTOR SHALL VERIFY ALL MOUNTING AND RECESS CONDITIONS PRIOR TO ORDERING FIXTURES
- B - CONTRACTOR SHALL PROVIDE ALL HARDWARE, BRACKETS, WIRING, TRANSFORMERS, REMOTE BOXES AND EQUIPMENT TO INSTALL A COMPLETE AND FUNCTIONAL SYSTEM
- C - NO SUBSTITUTIONS SHALL BE ACCEPTED WITHOUT PRIOR REVIEW AND WRITTEN APPROVAL BY SCHULER SHOOK

KEYED NOTES:

- A - PROVIDE COLOR KINETICS IPLAYERS AS REQUIRED TO CONTROL ALL TYPE SS, SS1, SS2, SS3, SS4, SS5, SS6 FIXTURES. PROVIDE CONNECTION TO STAGE AND HOUSE LIGHTING SYSTEM AND CONTROLLER KEY PAD.

REVISIONS:

- #1 - 14 DECEMBER 2009
- #2 - 25 JANUARY 2010 - Addendum #3
- #3 - 18 FEBRUARY 2010
- #4 - 2 APRIL 2010

THE SAENGER THEATRE RENEWAL PROJECT

142 North Rampart Street
New Orleans, LA

Client
Saenger Theatre Redevelopment Company
200 West Loop South, Suite
1040 Houston TX 77027

Architect
MARTINEZ+JOHNSON
ARCHITECTURE

1412 Eye St., NW
Washington, DC 20005
202.333.4480

Structural Engineer
Shawn J. Franke, P.E.
549 Heimer Road San
Antonio TX 78232
210.979.7900

Theatre Consultant
Schuler Shook
123 Third Street North #210
Minneapolis, MN 55401
612.339.5958

Acoustical Engineer
Akustiks
93 North Main Street South
Norwalk, CT 06854
202.299.1904

MEP Engineer
JBA Consulting Engineers, Inc.
3525 N. Causeway Blvd, Suite
500 Metairie, LA 70002
504.830.0139

Civil Engineer
Linfield, Hunter, & Junius, Inc.
3608 18th Street Suite 200
Metairie, LA 70002
504.833.5300

Architectural Historian
EHT Traceries, Inc.
1121 Fifth Street NW
Washington, DC 20001
202.393.1199

**THEATRE PLANNERS
LIGHTING DESIGNERS
Schuler Shook**



THESE DRAWINGS, SPECIFICATIONS, AND OTHER DOCUMENTS, COLLECTIVELY, THE "DOCUMENTS" INCLUDING WITHOUT LIMITATION ELECTRONIC VERSIONS THEREOF AND THE IDEAS, DESIGNS, AND ARRANGEMENTS REPRESENTED THEREBY, ARE AND SHALL REMAIN THE PROPERTY OF MARTINEZ & JOHNSON ARCHITECTURE PC, AS DEFINED BY APPLICABLE CONTRACTUAL AGREEMENTS ("THE AGREEMENTS") AND AS PROTECTED BY THE COPYRIGHT STATUTES OF THE UNITED STATES. USE OF THE DOCUMENTS SHALL BE STRICTLY LIMITED TO THE PROJECT FOR WHICH THEY WERE PREPARED AND DEVELOPED ("THE PROJECT") PER THE TERMS OF THE AGREEMENTS. NO PART OF THE DOCUMENTS SHALL BE COPIED, DISCLOSED TO OTHERS, OR USED IN CONNECTION WITH ANY OTHER WORK OR PROJECT, OR BY ANY OTHER PERSONS FOR ANY PURPOSES, OTHER THAN THE COMPLETION OF THE PROJECT, WITHOUT THE SPECIFIC WRITTEN AUTHORIZATION OF MARTINEZ & JOHNSON ARCHITECTURE PC. THE DOWNLOADING, OPENING, OR VIEWING OF ELECTRONIC VERSIONS OF THE DOCUMENTS OR VISUAL CONTACT WITH ANY PRINTED FORM THEREOF SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE RESTRICTIONS.

7502

| DATE: | No.: | ISSUE: |
|----------|------|------------------|
| 02.19.10 | 1 | PERMIT SET |
| 04.02.10 | 2 | GMP CONTRACT SET |
| 11.11.10 | - | CONTRACT SET |

| DATE: | No.: | REVISION: |
|-------|------|-----------|
| | | |
| | | |
| | | |
| | | |

SHEET TITLE:

**LIGHT FIXTURE
SCHEDULE**

AL-4.12