WIRING DEVICE KEY:
PB PLUG BOX
PS PLUG STRIP
UB UTILITY BOX

					CIRCUITS TERMINATE AT DIMMER RACK(S) OR RELAY CABINET(S) AS NOTED											CIRCUITS TERMINATE AT DIMMER RACK(S) OR RELAY CABINET(S) AS NOTED							CIRCUITS TERMINATE AT PANEL BOARD(S) PER ELEC. ENGINEER			
					20-AMP THEATRICAL LIGHTING BRANCH CIRCUITS CONNECTOR PER SPECIFICATIONS					20-AMP 6-CIRCUIT MULTI-CONDUCTOR CONNECTOR			50-AMP THEATRICAL LIGHTING BRANCH CIRCUITS			DIMMER RACK OR RELAY PANEL	20-AMP HOUSE LIGHTING BRANCH CIRCUITS NEMA L5-20R TWIST-LOCK CONNECTOR						DIMMER RACK OR RELAY PANEL	20AMP 120V NON-DIM THEATRICAL CONNECTOR	20AMP 120V DUPLEX NEMA 5-20R	20AMP 120/208V 3-PHASE NEMA L21-20R	
DEVICE NUMBER	LOCATION	MOUNTING	FINISH	PLUG STRIP LENGTH	CIRCUIT QUANTITY	THEATRICAL FLUSH RECEPTACLES	CIRCUIT NUMBERS FROM	CIRCUIT NUMBERS TO	CIRCUIT NUMBERS WORK	6-CIRCUIT RECEPTACLES	CIRCUIT NUMBERS FROM	CIRCUIT NUMBERS TO	CIRCUIT QUANTITY	CIRCUIT NUMBERS FROM	CIRCUIT NUMBERS TO		CIRCUIT QUANTITY	HOUSE FLUSH RECEPTACLES	HOUSE PIGTAILS	PIGTAIL LENGTH	CIRCUIT NUMBERS FROM	CIRCUIT NUMBERS TO					REMARKS
PB-01	TRAP ROOM LEFT	SURFACE	BLACK		3	3	1	3								DR-1											CIRCUITS DUPLICATE
PB-02	TRAP ROOM RIGHT	SURFACE	BLACK		3	3	4	6								DR-1											CIRCUITS DUPLICATE
PB-03	ORCHESTRA PIT LEFT	SURFACE	BLACK		3	3	1	3								DR-1											CIRCUITS DUPLICATE
PB-04	ORCHESTRA PIT RIGHT	SURFACE	BLACK		3	3	4	6								DR-1											CIRCUITS DUPLICATE
PB-05	PIT LIFT LEFT	FLOOR BOX	BLACK		3	3	1	3								DR-1									1		CIRCUITS DUPLICATE, FLEXIBLE CONNECTION FROM SUB-PIT JUNCTION BOX
PB-06	PIT LIFT RIGHT	FLOOR BOX	BLACK		3	3	4	6								DR-1									1		CIRCUITS DUPLICATE, FLEXIBLE CONNECTION FROM SUB-PIT JUNCTION BOX
PB-11	DOWNSTAGE LEFT	SURFACE	BLACK		3	3	13	15								DR-1											CIRCUITS DUPLICATE
PB-12	DOWNSTAGE RIGHT	SURFACE	BLACK		3	3	16	18								DR-1											CIRCUITS DUPLICATE
PB-13	UPSTAGE LEFT	SURFACE	BLACK		12	6	7	12		2	1	12	1	301		DR-1, 3											CIRCUITS DUPLICATE
PB-14	UPSTAGE RIGHT	SURFACE	BLACK		12	6	19	24		2	13	24	1	302		DR-1, 3											CIRCUITS DUPLICATE
PB-21	BALCONY RAIL LEFT	SURFACE	PER ARCHITECT		6					1	265	270				DR-4	1	1			429		DR-4		1	1	CONFIRM LOCATION WITH ARCHITECT
PB-22	BALCONY RAIL LEFT	SURFACE	PER ARCHITECT		6					1	271	276				DR-4									1		CONFIRM LOCATION WITH ARCHITECT
PB-23	BALCONY RAIL CENTER	SURFACE	PER ARCHITECT		6					1	277	282				DR-4	1	1			430		DR-4		1	1	CONFIRM LOCATION WITH ARCHITECT
PB-24	BALCONY RAIL CENTER	SURFACE	PER ARCHITECT		6					1	283	288				DR-4	1	1			431		DR-4		1	1	CONFIRM LOCATION WITH ARCHITECT
PB-25	BALCONY RAIL RIGHT	SURFACE	PER ARCHITECT		6					1	289	294				DR-4									1		CONFIRM LOCATION WITH ARCHITECT
PB-26	BALCONY RAIL RIGHT	SURFACE	PER ARCHITECT		6					1	295	300				DR-4	1	1			432		DR-4		1	1	CONFIRM LOCATION WITH ARCHITECT
PB-31	TORMENTOR LEFT	SURFACE	PER ARCHITECT		6					1	169	174				DR-2									1		
PB-32	TORMENTOR RIGHT	SURFACE	PER ARCHITECT		6					1	175	180				DR-2									1		
PB-41	PINRAIL GALLERY LEFT	SURFACE	BLACK		6	6	25	30		1	25	30	1	303		DR-1, 3										1	
PB-42	PINRAIL GALLERY LEFT	SURFACE	BLACK		6	6	31	36		1	31	36				DR-1											
PB-43	PINRAIL GALLERY LEFT	SURFACE	BLACK		6	6	37	42		1	37	42				DR-1										1	
PB-44	PINRAIL GALLERY LEFT	SURFACE	BLACK		6	6	43	48		1	43	48				DR-1											
PB-45	PINRAIL GALLERY RIGHT	SURFACE	BLACK		30	6	49	54		5	49	78	1	304		DR-1, 3										1	
PB-46	PINRAIL GALLERY RIGHT	SURFACE	BLACK		30	6	79	84		5	79	108				DR-1, 2											
PB-47	PINRAIL GALLERY RIGHT	SURFACE	BLACK		30	6	109	114		5	109	138				DR-2										1	
PB-48	PINRAIL GALLERY RIGHT	SURFACE	BLACK		30	6	139	144		5	139	168				DR-2											
PB-51	FOLLOW SPOT ROOM	SURFACE	BLACK		12					2						DR-4											
PB-61	ATTIC CATWALK	SURFACE	BLACK		24					1	193	198	4	301	302	DR-3										2	CIRCUITS DUPLICATE AT BOX BOOMS
										1	211	216															
										1	229	234		305	306												
										1	247	252															
PS-33	BOX BOOM #1 LEFT	SURFACE	PER ARCHITECT	24'-0"	18	18	181	198								DR-2, 3	1		3	3'-0"	423		DR-3		2	1	CIRCUITS DUPLICATE AT ATTIC
PS-34	BOX BOOM #1 RIGHT	SURFACE	PER ARCHITECT	24'-0"	18	18	199	216								DR-3	1		3	3'-0"	424		DR-3		2	1	CIRCUITS DUPLICATE AT ATTIC
PS-35	BOX BOOM #2 LEFT	SURFACE	PER ARCHITECT	16'-0"	18	18	217	234					1	305		DR-3									2	1	CIRCUITS DUPLICATE AT ATTIC
PS-36	BOX BOOM #2 RIGHT	SURFACE	PER ARCHITECT	16'-0"	18	18	235	252					1	306		DR-3									2	1	CIRCUITS DUPLICATE AT ATTIC
PS-49	BOX BOOM #3 LEFT	SURFACE	PER ARCHITECT	16'-0" VERIFY	6	6	253	258								DR-4	2		4	3'-0"	425	426	DR-4		1		
																	2		4	3'-0"	339	340	RP-2				
PS-50	BOX BOOM #3 RIGHT	SURFACE	PER ARCHITECT	16'-0" VERIFY	6	6	259	264								DR-4	2		4	3'-0"	427	428	DR-4		1		
																	2		4	3'-0"	339	340	RP-2				
UB-11	DOWNSTAGE LEFT	SURFACE	BLACK																					6	6		DEDICATED CIRCUITS AT PANEL BOARD
UB-12	DOWNSTAGE RIGHT	SURFACE	BLACK																					6	6		DEDICATED CIRCUITS AT PANEL BOARD
UB-13	UPSTAGE LEFT	SURFACE	BLACK																					6	6		DEDICATED CIRCUITS AT PANEL BOARD
UB-14	UPSTAGE RIGHT	SURFACE	BLACK																					6	6		DEDICATED CIRCUITS AT PANEL BOARD
	WORK LIGHTS																24				311	334	RP-1				HARDWIRED FIXTURES PER AL SHEETS
	WORK LIGHTS																24				335	358	RP-2				HARDWIRED FIXTURES PER AL SHEETS
	WORK LIGHTS																24				359	382	RP-3				HARDWIRED FIXTURES PER AL SHEETS
	HOUSE LIGHTS																24				401	424	DR-3				HARDWIRED FIXTURES PER AL SHEETS
	HOUSE LIGHTS																48				425	472	DR-4				HARDWIRED FIXTURES PER AL SHEETS
	LOBBY LIGHTS																96				501	596	DR-5				HARDWIRED FIXTURES PER AL SHEETS

THE SAENGER THEATRE RENEWAL PROJECT

142 North Rampart Street
New Orleans, LA

Client
Saenger Theatre Redevelopment Company
200 West Loop South, Suite
1040 Houston TX 77027

Architect
MARTINEZ+JOHNSON
ARCHITECTURE
1412 Eye St., NW
Washington, DC 20005
202.333.4480

Structural Engineer
Shawn J. Franke, P.E.
549 Heimer Road San
Antonio TX 78232
210.979.7900

Theatre Consultant
Schuler Shook
123 Third Street North #210
Minneapolis, MN 55401
612.339.5958

Acoustical Engineer
Akustiks
93 North Main Street South
Norwalk, CT 06584
202.299.1904

MEP Engineer
JBA Consulting Engineers, Inc.
3525 N. Causeway BLVD. Suite
500 Metairie, LA 70002
504.830.0139

Civil Engineer
Linfield, Hunter, & Junius, Inc.
3608 18th Street Suite 200
Metairie, LA 70002
504.833.5300

Architectural Historian
EHT Traceries, Inc.
1121 Fifth Street NW
Washington, DC 20001
202.393.1199

THESE DRAWINGS, SPECIFICATIONS, AND OTHER DOCUMENTS, (COLLECTIVELY, THE "DOCUMENTS"), INCLUDING WITHOUT LIMITATION ELECTRONIC VERSIONS THEREOF AND THE IDEAS, DESIGNS, AND ARRANGEMENTS REPRESENTED THEREBY, ARE AND SHALL REMAIN THE PROPERTY OF MARTINEZ & JOHNSON ARCHITECTURE PC, AS DEFINED BY APPLICABLE CONTRACTUAL AGREEMENTS ("THE AGREEMENTS") AND AS PROTECTED BY THE COPYRIGHT STATUTES OF THE UNITED STATES. USE OF THE DOCUMENTS SHALL BE STRICTLY LIMITED TO THE PROJECT FOR WHICH THEY WERE PREPARED AND DEVELOPED ("THE PROJECT") PER THE TERMS OF THE AGREEMENTS. NO PART OF THE DOCUMENTS SHALL BE COPIED, DISCLOSED TO OTHERS, OR USED IN CONNECTION WITH ANY OTHER WORK OR PROJECT, OR BY ANY OTHER PERSONS FOR ANY PURPOSE WITHOUT THE PRIOR WRITTEN CONSENT OF THE ARCHITECT, UNLESS SPECIFICALLY AUTHORIZED BY AGREEMENT OR WRITTEN AUTHORIZATION OF MARTINEZ & JOHNSON ARCHITECTURE PC. THE DOWNLOADING, OPENING, OR VIEWING OF ELECTRONIC VERSIONS OF THE DOCUMENTS OR VISUAL CONTACT WITH ANY PRINTED FORM THEREOF SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE RESTRICTIONS.

7502

DATE:	No.:	ISSUE:
02.19.10	1	PERMIT SET
04.02.10	2	GMP CONTRACT SET

DATE:	No.:	REVISION:
11.11.10		CONTRACT SET

SHEET TITLE:
DIMMER SCHEDULES

09.0394

E8.00

ISSUED FOR PERMIT

© 2010 M+J

P:\09.0394 Saenger Theatre\DRAWINGS\ELECTRICAL\090394_E800.dwg, 11/19/2010 5:34:13 PM, dhiggins