

**THE SAENGER
THEATRE RENEWAL
PROJECT**

142 North Rampart Street
New Orleans, LA

Client
Saenger Theatre Redevelopment Company
200 West Loop South, Suite
1040 Houston TX 77027

Architect
**MARTINEZ+JOHNSON
ARCHITECTURE**

1412 Eye St., NW
Washington, DC 20005
202.333.4480

Structural Engineer
Shawn J. Franke, P.E.
549heimer Road, San
Antonio TX 78232
210.979.7900

Theatre Consultant
Schuler Shook
123 Third Street North #210
Minneapolis, MN 55401
612.333.5959

Acoustical Engineer
Akustiks
93 North Main Street South
Norwalk, CT 06584
202.299.1904

MEP Engineer
JBA Consulting Engineers, Inc.
3525 N. Causeway Blvd. Suite
500 Metairie, LA 70002
504.830.0139

Civil Engineer
Linfield, Hunter, & Junius, Inc.
3608 18th Street Suite 200
Metairie, LA 70002
504.833.5300

Architectural Historian
EHT Tracerics, Inc.
1121 Fifth Street NW
Washington, DC 20001
202.393.1199

NOTES

- 1 44/28 OPEN END R.A. DUCT DOWN W/ 1/2" G.B.S. (RF-4)
- 2 34/36 S.A. FROM ABOVE & DN. (AH-4)
- 3 26/26 S.A. FROM ABOVE & DN. (AH-3)
- 4 46/26 R.A. DN. (RF-5)
- 5 20/46 S.A. FROM ABOVE & DN. (AH-2)
- 6 14/12 E.A. FROM BELOW & UP. (EF-3)
- 7 18/18 E.A. FROM BELOW & UP. (EF-2)
- 8 P.O.C. TO EXISTING. (TYP.)
- 9 24/20 S.A. FROM ABOVE. (AH-2)
- 10 8' X 4' HIGH RETURN AIR GRILLE W/ MINIMUM 50% FREE AREA. LOCATE AT 8'-0" ABOVE STAGE FLOOR.
- 11 16/16 E.A. FROM BELOW & UP. (EF-4)
- 12 78/30 S.A. FROM ABOVE & DN. (AH-3)
- 13 ARCHITECT TO PROVIDE MIN. 32 SQ. FT. RETURN GRILLE AT 50% FREE AREA.
- 14 18/18 S.A. UP. (AH-4)
- 15 18/18 S.A. UP. (AH-3)
- 16 REF. SHEET M-1.05 FOR CONT.
- 17 26/26 S.A. FROM ABOVE & DN. (AH-4)
- 18 46/26 R.A. DN. (RF-6)
- 19 36/24 R.A. FROM BELOW & UP. (AH-2)
- 20 EXISTING DIFFUSER TO REMAIN.
- 21 6" Ø DRYER VENT UP FROM BELOW. TERMINATE THROUGH APPROVED WALL CAP.
- 22 COORDINATE EXACT LOCATION WITH ARCHITECT.
- 23 26/18 O.A. FROM ABOVE & DN. (AH-7)
- 24 44/28 OPEN END R.A. DUCT DOWN W/ 1/2" G.B.S. (RF-3)
- 25 PROVIDE AIRFLOW MEASURE STATION & CONTROL DAMPER IN RISER.
- 26 EXISTING DIFFUSER BALANCE DAMPER TO LISTED CFM.
- 27 INTERNALLY LINE WITH 1/2"-1/2# DENSITY F.G. LINER.
- 28 SUPPLY DIFFUSER IN FLOOR. ONE SUPPLY FOR EVERY OTHER SEAT IN THEATER. ALL ROWS TYPICAL TOTAL OF 1,105 SUPPLY DIFFUSERS FOR THEATER SEATING.

THESE DRAWINGS, SPECIFICATIONS AND OTHER DOCUMENTS, COLLECTIVELY THE "DOCUMENTS", INCLUDING WITHOUT LIMITATION ELECTRONIC VERSIONS THEREOF AND THE IDEAS, DESIGNS, AND ARRANGEMENTS REPRESENTED THEREBY, ARE AND SHALL REMAIN THE PROPERTY OF MARTINEZ+JOHNSON ARCHITECTURE P.C. AS PROTECTED BY APPLICABLE CONTRACTUAL AGREEMENTS ("THE AGREEMENTS") AND AS PROTECTED BY THE COPYRIGHT STATUTES OF THE UNITED STATES. USE OF THE DOCUMENTS SHALL BE STRICTLY LIMITED TO THE PROJECT FOR WHICH THEY WERE PREPARED AND DEVELOPED ("THE PROJECT") FOR THE TERM OF THE AGREEMENTS. NO PART OF THE DOCUMENTS SHALL BE COPIED, DISCLOSED TO OTHERS, OR USED IN CONNECTION WITH ANY OTHER WORK OR PROJECT, OR BY ANY OTHER PERSONS FOR ANY PURPOSE, OTHER THAN THE COMPLETION OF THE PROJECT, WITHOUT THE SPECIFIC WRITTEN AUTHORIZATION OF MARTINEZ+JOHNSON ARCHITECTURE P.C. THE DOING, GIVING, OPENING, OR VIEWING OF ELECTRONIC VERSIONS OF THE DOCUMENTS OR VISUAL CONTACT WITH ANY PRINTED FORM THEREOF SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE RESTRICTIONS.

7502

DATE:	No.:	ISSUE:
02.19.10	1	PERMIT SET
04.02.10	2	GMP CONTRACT SET

DATE:	No.:	REVISION:
11.11.10		CONTRACT SET

SHEET TITLE:
**THEATRE - ORCHESTRA
LEVEL PLAN**

M-1.02

NOTES (CONT.)

- 29 DUCTWORK AND EQUIPMENT LOCATED IN SUPPLY PLENUM WHICH SERVES THE LOBBY SHALL BE ENCLOSED IN DRYWALL SOUND ENCLOSURE. COORDINATE REQUIREMENTS W/ GENERAL CONTRACTOR PROVIDE MANUFACTURER RECOMMENDED CLEARANCES AND ACCESS TO EQUIPMENT AND DAMPER.
- 30 PROVIDE DUCT LAGGING OR DRYWALL ENCLOSURE AROUND DUCTS EXPOSED IN STAGE HOUSE. PROVIDE ACCESS TO DAMPERS.
- 31 GENERAL CONTRACTOR TO PROVIDE DRYWALL ENCLOSURE FOR DUCTWORK.
- 32 GENERAL CONTRACTOR TO PROVIDE 2-HR ENCLOSURE FOR DUCTWORK.

