

**THE SAENGER
THEATRE RENEWAL
PROJECT**

142 North Rampart Street
New Orleans, LA

Client
Saenger Theatre Redevelopment Company
200 West Loop South, Suite
1040 Houston TX 77027

Architect
**MARTINEZ+JOHNSON
ARCHITECTURE**

1412 Eye St., NW
Washington, DC 20005
202.333.4480

Structural Engineer
Shawn J. Franke, P.E.
549 Heimer Road San
Antonio TX 78232
210.979.7900

Theatre Consultant
Schuler Shook
123 Third Street North #210
Minneapolis, MN 55401
612.333.5559

Acoustical Engineer
Akustiks
93 North Main Street South
Norwalk, CT 06584
202.299.1904

MEP Engineer
JBA Consulting Engineers, Inc.
3525 N. Causeway Blvd. Suite
500 Metairie, LA 70002
504.830.0139

Civil Engineer
Linfield, Hunter, & Junius, Inc.
3608 18th Street Suite 200
Metairie, LA 70002
504.333.5559

Architectural Historian
EHT Traceries, Inc.
1121 Fifth Street NW
Washington, DC 20001
202.393.1199

THESE DRAWINGS, SPECIFICATIONS, AND OTHER DOCUMENTS, COLLECTIVELY, THE "DOCUMENTS", INCLUDING WITHOUT LIMITATION ELECTRONIC VERSIONS THEREOF AND THE IDEAS, DESIGNS, AND ARRANGEMENTS REPRESENTED THEREBY, ARE AND SHALL REMAIN THE PROPERTY OF MARTINEZ & JOHNSON ARCHITECTURE PC AS DEFINED BY APPLICABLE CONTRACTUAL AGREEMENTS ("THE AGREEMENTS") AND AS PROTECTED BY THE COPYRIGHT STATUTES OF THE UNITED STATES. USE OF THE DOCUMENTS SHALL BE STRICTLY LIMITED TO THE PROJECT FOR WHICH THEY WERE PREPARED AND DEVELOPED ("THE PROJECT") FOR THE TERMS OF THE AGREEMENTS. NO PART OF THE DOCUMENTS SHALL BE COPIED, DISCLOSED TO OTHERS, OR USED IN CONNECTION WITH ANY OTHER WORK OR PROJECT, OR BY ANY OTHER PERSONS FOR ANY PURPOSES, OTHER THAN THE COMPLETION OF THE PROJECT, WITHOUT THE SPECIFIC WRITTEN AUTHORIZATION OF MARTINEZ & JOHNSON ARCHITECTURE PC. THE DOWNLOADING, OPENING, OR VIEWING OF ELECTRONIC VERSIONS OF THE DOCUMENTS OR VISUAL CONTACT WITH ANY PRINTED FORM THEREOF SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE RESTRICTIONS.

7502

DATE:	No.:	ISSUE:
02.19.10	1	PERMIT SET
04.02.10	2	GMP CONTRACT SET

DATE:	No.:	REVISION:
11.11.10		CONTRACT SET

SHEET TITLE:
THEATRE - BASEMENT
LEVEL ENLARGED
PLANS

P-4.01

NOTES

- ① 4" W. FROM ABOVE - REFER TO SHEET P-1.00 FOR CONT.
- ② 4" W. DOWN IN CORNER TO BELOW GRADE WITH W.C.O.
- ③ 3/4" T.W. FROM BELOW.
- ④ REFER TO SHEET P-1.00 FOR CONTINUATION.
- ⑤ REFER TO ENLARGED PLAN FOR CONTINUATION. (C) P-4.08
- ⑥ 1" H. & C.W. TO ABOVE, 3/4" H.W.R. FROM ABOVE.
- ⑦ 4" W. DOWN TO BELOW GRADE WITH W.C.O.
- ⑧ 2 1/2" C.W. DOWN WITH S.O.V. AND HEADER IN CHASE.
- ⑨ 2" C.W. DOWN WITH S.O.V. AND HEADER IN CHASE.
- ⑩ TEMPERED WATER (T.W.) TO LOOP DOWN AND HEADER IN CHASE.
- ⑪ 3" W. DOWN, 2" V. UP, AND 3/4" H. & C.W. DOWN TO SERVICE SINK.
- ⑫ 2" V. FROM BELOW.
- ⑬ 2" V. UP TO ABOVE CEILING.
- ⑭ 3" V. UP TO ABOVE CEILING. (A)
- ⑮ 3/4" C.W. DOWN WITH S.O.V. TO ELECTRONIC TRAP PRIMER MANIFOLD EQUAL TO P.P.P. INC. "PRIME-TIME" #PT-10 WITH 1/2" C.W. PRIMING LINES DOWN AND CONNECT TO P-TRAP OF EACH E.D. REFER TO DETAIL (6) P-6.00
- ⑯ 1" H. & C.W. DOWN TO TEMPERING STATION WITH 1" T.W. UP. REFER TO DETAIL (3) P-6.00
- ⑰ 2" W. DOWN, 2" V. UP, AND 3/4" H. & C.W. DOWN TO CLOTHES WASHER BOX.
- ⑱ 2" W. DOWN, 2" V. UP, AND 3/4" H. & C.W. DOWN TO LAUNDRY SINK.
- ⑲ 2" W. DOWN WITH W.C.O., 2" V. UP, AND 3/4" H. & C.W. DOWN TO KITCHEN SINK WITH 3/4" H.W. TEE TO DISHWASHER.
- ⑳ 1/2" C.W. DOWN TO ICE MAKER BOX.
- ㉑ 4" W. DOWN, 2" V. UP, AND 2" C.W. DOWN TO WATER CLOSET.
- ㉒ 2" W. DOWN AND 2" V. UP FROM LAV. 1/2" H. & C.W. DOWN TO THERMOSTATIC MIXING VALVE LOCATED BELOW LAVATORY SERVING 1/2" 105° TEMPERED WATER AND CONNECT TO FAUCET SIMILAR TO DETAIL (2) P-6.01
- ㉓ 2" W. DOWN, 2" V. UP, AND 1/2" C.W. DOWN TO ELECTRIC WATER COOLER.
- ㉔ 2" W. DOWN, 2" V. UP, AND 3/4" H. & C.W. DOWN TO TEMPERING STATION AND PIPE T.W. TO EYEWASH.
- ㉕ 3" W. DOWN TO BELOW GRADE WITH W.C.O.
- ㉖ PIPING SUPPORTED BELOW STAGE AND ORCHESTRA SEATING AREAS SHALL BE RESILIENTLY SUSPENDED FROM STRUCTURE ABOVE USING VIBRATION ISOLATION HANGERS.
- ㉗ 2" W., 2" V. UP FROM DRINKING FOUNTAIN. CONNECT 2" W. FROM EACH DRINKING FOUNTAIN IN WALL AND DOWN TO BELOW FLOOR. (A)
- ㉘ 3/4" C.W. DOWN IN WALL WITH 1/2" TEE TO EACH DRINKING FOUNTAIN.

