




P.E. Matt J. V. Foundation, 3000 South Lakeshore, Metairie, LA 70001, 504-885-9999, www.dammoneengineering.com




1 FOUNDATION PLAN
SCALE: 1/4"=1'-0"



2 STAIR PLAN
SCALE: 1/2"=1'-0"



1 TYPICAL PILING DETAIL
SCALE: 1/2"=1'-0"



GENERAL NOTES

- ENGINEER DID NOT INSPECT THIS SITE AND DOES NOT ATTEST TO ANY EXISTING UNUSUAL SITE OR SOIL CONDITIONS ON THE BUILDING SITE.
- ENGINEER DOES NOT ATTEST THAT SETTLEMENT OF THE FOUNDATION WILL NOT OCCUR.
- ENGINEER DOES NOT INSPECT THIS FOUNDATION FOR PLAN COMPLIANCE (UNLESS BY SEPARATE CONTRACT).
- OWNER IS CAUTIONED TO EXERCISE POSITIVE DRAINAGE OF THE SITE BOTH FROM RAINFALL AND ANY INSTALLED SPRINKLER SYSTEMS.
- ENGINEER DOES NOT ATTEST TO THE STRUCTURAL DESIGN OR ADEQUACY OF THE PROPOSED BUILDING.
- ANY DEVIATION FROM THIS PLAN OR SPECIFICATIONS WILL VOID ENGINEER'S LIABILITY AND RESPONSIBILITY.
- THIS DESIGN SHALL BE USED ONLY FOR THE ATTACHED REFERENCED PROJECT.
- CONTRACTOR TO CONTACT ALL UTILITY COMPANIES FOR ALL UTILITY RELOCATIONS PRIOR TO CONSTRUCTION.
- PILING LOCATIONS ARE ONLY AN APPROXIMATION BY ENGINEER, FIELD TO VERIFY EXISTING PILING LOCATIONS.
- CONTRACTOR TO ENSURE THAT EXISTING SLAB AND FOOTINGS ARE STRUCTURALLY CAPABLE TO BE RAISED WITH THE HOUSE. OTHERWISE SLABS SHALL REMAIN AT GRADE.

LIFT DESIGN CRITERION

- THE PILING BELOW THE BUILDING SHALL FIRST BE EXPOSED BY REMOVING THE SURROUNDING SOILS FOR A DEPTH OF APPROXIMATELY 3 FEET. THEN APPROXIMATELY EVERY OTHER FILE IS CUT LEAVING ROOM FOR A HYDRAULIC JACK TO BE INSTALLED BETWEEN CUT OFF FILE AND BUILDING'S EXISTING SLAB.
- A UNIFIED HYDRAULIC JACKING SYSTEM SHALL BE USED TO RAISE THE BUILDING IN A UNIFIED MODE UNTIL THE DESIGNED ULTIMATE HEIGHT IS ACHIEVED. AT THIS STAGE 8'x8'x8' SOLID CONCRETE SEGMENTAL BLOCKS ARE FINED TOGETHER WITH INTERLOCKING #5 DOVELS ON TOP OF THE EXPOSED FILE, WHICH DOES NOT HAVE A JACK ON IT. THE JACKS ARE THEN REMOVED FROM THE PILES AND 8'x8'x8' CONCRETE SEGMENTAL BLOCKS ARE INSTALLED ON THESE REMAINING PILES. SINCE THE CONCRETE SEGMENTAL PILES ARE GENERALLY INSTALLED UNTIL A MINIMUM LIFT OF ONE HALF INCH IS ACHIEVED ON THE STRUCTURE, THE CORRESPONDING GAUGE PRESSURE CONVERTS TO A PILE LOAD CAPACITY OF APPROXIMATELY 7 TONS.

DAMMON
ENGINEERING, INC.
 LOUISIANA & MISSISSIPPI
 Chief Engineer: Brian Michich, PE
 www.dammoneengineering.com
 info@dammoneengineering.com
 PH: 985.649.5832
 554 Old Spanish Trail
 Slidell, LA 70458

| REVISIONS | DATE | DESCRIPTION |
|-----------|------|-------------|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

SEAL:

CASTILLO
BUILDERS
 2604 ALEATHA STREET
 METAIRIE, LA
 JOB NO: 08-08-2018
 DATE: 08-08-2018
 DRAWN BY: CSD
 CHECKED BY: CSD

SHEET TITLE:
FOUNDATION PLAN
& DETAILS

DRAWING NUMBER:

S101