

**Notice of Addendum #01 - 10/26/2022**

Permit Office  
Town Of Grand Isles  
170 Ludwig Ln,  
Grand Isle, LA 70358

REF: Gwen Mcinnis  
185 West Central Ave.  
Grand Isle, LA. 70358

Nora, please find the comments that were of concern to be corrected as noted below.

- 1) Corrected the depth of the 6"x6" stair post to be 4' deep for the landing and stairs.
- 2) Added note to reflect 1/ 2" sheathing on the first four feet of the ceiling on all the parameter walls.
- 3) The front and rear porches shall have 12"x12" wood columns and 6"x6" wood post leading to the stair landing.
- 4) All load bearing column walls shall have tripled up 2x4 studs. All load bearing walls shall have tripled up 2x12 floor joists under all load bearing walls including the tub and shower.