



1 2ND FLOOR REFERENCE PLAN
A2.02 3/32"=1'-0"

- GENERAL NOTES:**
- REFER TO SHEET A3.09 FOR PARTITION TYPE DEFINITIONS.
 - REFER TO SHEET A2.01 & A2.02 FOR DOOR NUMBERS.
 - REFER TO SHEET A5.03 FOR TYPICAL TOILET ACCESSORIES AND DIMENSIONS.
 - ALL DIMENSIONS ARE TO FINISH FACE OF BASE PARTITION UNLESS NOTED OTHERWISE.
 - G.C. TO COORDINATE & PROVIDE 20 GA. GALV. SHEET METAL BLOCKING OR FIRE / THERMITE TREATED WOOD BLOCKING AS REQUIRED AT ALL ACCESSORIES, CASEWORK, & OWNER PROVIDED EQUIPMENT, TO BE INSTALLED BY CONTRACTOR.
 - REFER TO LIFE SAFETY PLAN A1.01 & A1.02 FOR HOURLY RATED WALL AND SMOKE PARTITION LOCATIONS. NOTIFY ARCHITECT OF ANY DISCREPANCIES WITHIN ENLARGED PLAN PARTITION CALL OUTS FOR CLARIFICATION.
 - SEE SHEET A3.01 & A3.02 FOR FINISH FLOOR SCHEDULES.

MARK	DESCRIPTION	MFG. / MDL.	QTY.	O/O	O/V	O/C	C/C	REMARKS
PROVIDED BY / INSTALLED BY								
O = OWNER, V = VENDOR, C = CONTRACTOR								
1A	60" FLAT SCREEN TV	SONY	1		o			POWER/VOICE-DATA/CABLE: 66" AFF - Wall Mount
1B	WALL MOUNT TV SHELF	PEERLESS / #PM1327(S)(W)	10			o		POWER/VOICE-DATA/CABLE: 87" AFF - Wall Mount
1C	23" FLAT SCREEN TV	SONY	1		o			POWER/VOICE-DATA/CABLE: 66" AFF - Wall Mount
1D	42" FLAT SCREEN TV	SONY	1		o			POWER/VOICE-DATA/CABLE: 66" AFF - Wall Mount
2	UPRIGHT REFRIGERATOR	MAGIC CHEF	2		o			PROVIDE WATER FEED - ICE MAKER
3	MICROWAVE	G.E.	5	o				POWER: 58" AFF
4	UNDER COUNTER ICE MAKER	G.E.	1			o		POWER: PROVIDE WATER FEED
5	WARMING CART OUTLETS	SEE MEP SPECIFICATIONS	2			o		POWER: 36" AFF / SEE E2.0
6	COFFEE MACHINES	ALL VEND	7		o			POWER: PROVIDE WATER FEED
7	VENDING MACHINES	ALL VEND	2		o			POWER
8A	4" X 16" MARKER BOARD	SEE GEN. SPECIFICATIONS	2			o		36" AFF - WALL MOUNT
8B	4" X 10" MARKER BOARD	SEE GEN. SPECIFICATIONS	1			o		36" AFF - WALL MOUNT
8C	4" X 6" MARKER BOARD	SEE GEN. SPECIFICATIONS	4			o		36" AFF - WALL MOUNT
8D	4" X 4" MEDIA BOARDS	NUCRAFT or NEVERS	3		o			36" AFF - WALL MOUNT
8E	4" X 6" MEDIA BOARD	NUCRAFT or NEVERS	1		o			36" AFF - WALL MOUNT
9	PERSONNEL LOCKERS	REPUBLIC STORAGE	TBD			o		12" WIDE - DBL. TIER WITH CLOSED BASE; COLOR: GRAY
10	UNDER COUNTER REFRIGERATOR	G.E.	5			o		POWER
11	EMPLOYEE TIME CLOCK	KRONOS	2		o			POWER/VOICE-DATA: 48" AFF - Wall Mount / SEE A1.01 FOR LOCATIONS
12	MAILBOXES	SEE GEN. SPECIFICATIONS	TBD			o		SEE A1.01 FOR LOCATION
13	4" X 5" SMART BOARD	POLYVISION	2		o			POWER/VOICE-DATA: 36" AFF - Wall Mount
14	COPY MACHINES	XEROX	6		o			POWER/VOICE-DATA
15A	DROP DN. PROJECTOR PLATFORM	SEE MEP SPECIFICATIONS	1			o		POWER/VOICE-DATA ABOVE CEILING GRID / SEE A6.01A
15B	10" X 10" DROP DN. SCREEN	DRAPER, INC. / ENVOY	1			o		POWER ABOVE CEILING GRID / SEE A6.01A
17	TROPHY DISPLAY CASES	TBD	5	o				POWER - FLOOR OUTLETS
18	METAL DETECTOR / X-RAY	TBD	1		o			POWER/VOICE-DATA - FLOOR OUTLETS
19	PAPER RECYCLE BOXES	I-SHRED	5		o			SEE A1.01 AND A2.01 FOR LOCATIONS
20	WATER COOLER DISPENSERS	ABITA SPRINGS WATER	4	o				POWER
21	INFORMATIONAL KIOSK	TBD	1	o				POWER/VOICE-DATA IN COLUMN FACE - COLL. LN. 8.7/F.1
22	THROUGHWALL DROP BOX	AUTH.FLORENCE OR EQUAL	1			o		Rear Loading, Horizontal Style, Anodized Alum. "Lift off rear cover", 1" Engraved Letters. See www.mailboxworks.com

NOTE: GC RESPONSIBLE FOR ALL HARD CONNECTIONS.