FIRE SUPPRESSION SPRINKLER SYSTEM NOTE

CONTRACTOR TO PROVIDE A COMPLETE FIRE SPRINKLER SYSTEM, INCLUDING ALL COMPONENTS, DENSITY AND FLOW CALCULATIONS, INSTALLATION, PIPING, HEADS, SERVICE ENTRANCE "TREE", ETC., ALL AS REQUIRED AND NEEDED. PROVIDE SHOP DRAWINGS, IN ACCORDANCE WITH THESE DOCUMENTS AND OSFM AND CODE REQUIREMENTS. SYSTEM TO COMPLY WITH ALL NATIONAL, STATE AND LOCAL CODES AND ORDINANCES, INCLUDING INSURANCE UNDERWRITER'S REQUIREMENTS, IN PARTICULAR, COMPLIANCE WITH NFPA 13. COORDINATE WITH FIRE ALARM SYSTEM WHEN APPLICABLE.OTHER DIVISIONS OF WORK FOR INSTALLATION AND FOR INTERFACE WITH THE FIRE ALARM SYSTEM.

PROVIDE FLOW TEST TO ASSURE PROPER AND ADEQUATE WATER FLOW AT DESIGN CONDITIONS.

1 1ST FLOOR SPRINKLER PLAN

NOT TO SCALE

RCL CONSULTANTS, L.L.C.
Planning • Architecture • Engineering • Construction Management

RICHARD C. LAMBERT CONSULTANTS, L.L.C.
521 N. Causeway Blvd.
Mandeville, LA 70448
985-727-4440
Fax: 985-727-4467

#1 Poydras St., Ste. 1400 #10
New Orleans, LA 70130
504-837-7346

This drawing and design is the exclusive property of Richard C. Lambert Consultants, LLC and may not be reproduced or used without authorization and written permission. © 2007

RCLC
Project Number: 0687

Date Issued: 05/15/07
Drawn By: EDA
Checked By: EDA

Revisions:

ST. TAMMANY PARISH SHERIFF'S OFFICE

BROWNSWITCH ROAD
SLIDELL, LOUISIANA

CONSTRUCTION DOCUMENTS

SPRINKLER PLAN
1ST FLOOR

Sheet Number:

M-3.0

EDA Project 9173
Engineering Design Associates, L.L.C.
Consulting Engineers
3350 Ridgelake Drive Suite 190 Metairie, Louisiana 70002
504 836 3889 - 504 836 3887 (facsimile) - eda@engineeringdesignassoc.com

Copyright © 2007
Copyright 2007