



LANDSCAPING NOTES

- ALL LANDSCAPING SHALL BE INSTALLED BY A LANDSCAPING COMPANY LICENSED IN THE STATE OF LOUISIANA.
- CONTACT LOCAL UNDERGROUND UTILITY SERVICES FOR UTILITY LOCATION AND IDENTIFICATION, PRIOR TO COMMENCING WORK.
- PERFORM EXCAVATIONS IN THE VICINITY OF UNDERGROUND UTILITIES WITH CARE AND BY HAND, IF NECESSARY. THE CONTRACTOR BEARS FULL RESPONSIBILITY FOR THIS WORK AND DISRUPTION OR DAMAGE TO UTILITIES AND SHALL BE IMMEDIATELY REPAIRED AND AT NO EXPENSE TO THE OWNER.
- ITEMS ENCOUNTERED BELOW GRADE AND NOT SHOWN ON THE DRAWINGS SHALL BE BROUGHT TO THE ATTENTION OF THE CONTRACTOR.
- CONTACT THE LOCAL UNDERGROUND SERVICE UPDATE FOR UTILITY LOCATION AND IDENTIFICATION PRIOR TO DEMOLITION.
- DESIGNING PLANTING AREAS, ESPECIALLY THOSE BY PASSING TREATMENT SYSTEMS, TO ENCOURAGE INFILTRATION TO THE DEGREE POSSIBLE.
- IN ORDER TO ENCOURAGE INFILTRATION OF STORMWATER AND TO MINIMIZE THE MIGRATION OF SEDIMENTS, THE FINISHED GRADE FOR ALL LANDSCAPING AREAS SHALL BE SET 3/8" AMP, QUOT; MINIMUM BELOW SURROUNDING HARDSCAPE CONTAINMENTS (CURBING, SIDEWALKS, FOUNDATIONS ETC.). THIS STANDARD MAY BE WAIVED IF NECESSARY TO PROMOTE THE PRESERVATION OF TREES SHOWN AS SUCH.

LEGEND

- DD BLANCHARD MAGNOLIA
ALL CLASS 'A' TREES, AT THE TIME OF PLANTING, SHALL HAVE A MINIMUM CALIPER OF THREE INCH (3") 10'-12' TALL WITH A MINIMUM FORK HEIGHT OF 5'.
COMMON NAME: SOUTHERN MAGNOLIA
LATIN NAME: MAGNOLIA GRANDIFLORA
- AZALEA
SHRUB; A RELATIVELY LOW-GROWING BUSHY PLANT, USUALLY WITH WOODY STEMS. FOR THE PURPOSE OF THIS DEFINITION, GROUND COVER, TREES AND ANNUALS ARE NOT CONSIDERED SHRUBS. ALL SHRUBS, AT THE TIME OF PLANTING, SHALL HAVE A MINIMUM HEIGHT OF TWO (2) FEET.
- DRIFT ROSE
SHRUB; A RELATIVELY LOW-GROWING BUSHY PLANT, USUALLY WITH WOODY STEMS. FOR THE PURPOSE OF THIS DEFINITION, GROUND COVER, TREES AND ANNUALS ARE NOT CONSIDERED SHRUBS. SHALL HIDE BACKFLOW PREVENTER.
- AFRICAN IRIS
SHRUB; A RELATIVELY LOW-GROWING BUSHY PLANT. FOR THE PURPOSE OF THIS DEFINITION, GROUND COVER, TREES AND ANNUALS ARE NOT CONSIDERED SHRUBS.
- GRASS
- PINE MULCH

HARD & GREEN SPACE

EXISTING AREA = 14,319 SQ. FT.
 BUILDING AREA = 6,017 SQ. FT.
 PERMEABLE PAVING AREA = 1,415 SQ. FT.
 SIDEWALKS & HANDICAP AREA = 1,065 SQ. FT.
 GREEN AREA = 5,816 SQ. FT.
 TOTAL AREA = 14,319.00 SQ. FT.

LICENSED LANDSCAPER

BILL BROWN JR.
 LUXURY LANDSCAPE SERVICES 905-TT4-5211
 HORT. #2971
 THIS LICENSED CONTRACTOR SHALL INSTALL ALL LANDSCAPING MATERIALS AS SHOWN ON THIS DRAWING.

DAMMON ENGINEERING, INC.
 LOUISIANA & MISSISSIPPI
 Chief Engineer: Brian Mistich, PE
 554 Old Spanish Trail
 Slidell, LA 70468
 www.dammonengineering.com
 info@dammonengineering.com
 PH: 985.449.5832

REVISIONS	DATE	DESCRIPTION

SEAL:

 BRIAN A. MISTICH
 License No. 30187

NEW FACILITY
NEW ORLEANS FIREFIGHTERS ASSOCIATION
 5710 GENERAL HAIG STREET
 NEW ORLEANS, LA 70124
 JOB No: 2493 | DATE: 06/30/2021 | DRAWN BY: BB JR.
 C&D CHECKED BY: BB JR.

SHEET TITLE:
LANDSCAPING PLAN
 DRAWING NUMBER:
L100
 SHEET No: 1 of 1

1 LANDSCAPING PLAN
 SCALE: 1" = 10'-0"