



1 REFLECTED CEILING PLAN
SCALE: 1/8"=1'-0"

CEILING SYSTEMS LEGEND

- ACT-1 ARMSTRONG: AXIOM TRIM - CLASSIC - AX2CUR - 2" CURVED-WH
ARMSTRONG: 9/16" SUPRAFINE - EXPOSED TEE SYSTEM - MIRROR
2'x2'x3/4"
ARMSTRONG - STICKS - 655 - WH - 9/16" SQUARE TEGULAR
2'x2'x3/4"
- ACT-2 ARMSTRONG: ULTIMA - 1912 - WH - 9/16" BEVELED TEGULAR
2'x2'x3/4" - FINE TEXTURE
ARMSTRONG: 9/16" SUPRAFINE - EXPOSED TEE SYSTEM -WH
2'x2'x3/4"
- ACT-3 ARMSTRONG: CERAMAGUARD - WH - 9/16" BEVELED TEGULAR
2'x2'x3/4"
ARMSTRONG: 9/16" SUPRAFINE - EXPOSED TEE SYSTEM -WH
2'x2'x3/4"
- CLG-1 1/2" GYPSUM BOARD CEILING, PAINTED.
REFER TO FINISH SCHEDULE.
- 1/21 VENTED SOFFIT PANEL

FIXTURE LEGEND

- A BRUCK - SILVA - TURQUOISE GLASS 220715CH
REFER TO ELEVATIONS FOR MOUNTING HEIGHT.
- B 3" DIA. MR16 SPOT - 50 WATT ON DIMMER- USHIO.
NOTE: FIXTURE OVER RESTROOM VANITIES TO
BE INSTALLED DIRECTLY CENTERED AT EACH
SINK.
- C BRUCK ORION FLEXIBLE BELT L.E.D.
- D 1x4 LENS TROFFER. SEE DETAIL 5/A2.2
- E BRUCK SCOBO SCONCE I. MATTE CHROME
- F CONCEALED FLUORESCENT STRIPLIGHT
- G ALKCO UNDER CABINET LIGHTING
- H HOOD VENT BY OTHERS. FINISH: STAINLESS STEEL
- I 2'x4' CEILING MOUNTED T8 STRIP FLUORESCENT
- J 2'x4' RECESSED T8 FLUORESCENT
- K COOPER LIGHTING COMPACT FLUORESCENT
PD6-V142-E-6VC 42 WATT LAMP COLOR TEMP.: 2,700 DEGREE
- L COOPER LIGHTING - SHAPER DIVISION
461-A-CFL or INC1126-120V- CORD LENGTH: 120" -29
LAMP: 2,700 DEGREE KELVIN. MOUNTED AT 12" A.F.F.
- M EXTERIOR METAL HALIDE DOWNLIGHT
- N EXTERIOR T8 FLUORESCENT SCONCE FIXTURE
- O EXTERIOR COMPACT FLUORESCENT
- P WALL-MOUNTED T8 FLUORESCENT LIGHT
- Q GREEN EDGE LIT EXIT SIGN
- R GREEN EDGE LIT DIRECTIONAL EXIT SIGN
- SK EXTERIOR WALL-MOUNTED EXIT SIGN.
MOUNTING HEIGHT: 7'-0" A.F.F.
- T FLUORESCENT STRIP LIGHT

