



REQUIRED PEDESTRIAN PLANTING: 1103.84 S.F.  
SUPPLIED PEDESTRIAN PLANTING: 1728.02 S.F.

-PARKING REQUIREMENT-  
TOTAL AREA= 42,928 SQ. FT.  
TOTAL USABLE AREA= 34,246 SQ. FT.  
TOTAL PARKING SPACES REQUIRED, 1 PER 200 SQ. FT.  
9 ACCESSIBLE, 3 VAN SPACES  
PREVIOUSLY AVAILABLE-90 SPACES

-FURNISHED-  
141 PARKING SPACES FURNISHED  
7 ACCESSIBLE, 4 VAN SPACES

"DETECTABLE WARNING"  
ON RAMP SURFACES  
CUT 1/4" DEEP GROOVES  
THAT ARE SPACED  
1" TO 3" ON CENTER  
AND SCORED INTO CONCRETE.  
PAINT CONTRASTING COLOR.  
INSTALL HDOP SIGNS TYP

LEGEND

- CENTERLINE OF ROAD
- PROPERTY LINE
- NEW BUILDING
- EXISTING FENCE LINE
- SETBACK LINE
- CREPE MYRTLE
- SHUWARD OAK
- LARGE CAMELLIA
- HORN BEAM
- SHRUB
- NEW DROP INLET
- LANDSCAPE UPLIGHT
- LIGHT POLE
- TRASH RECEPTACLE

REVISED: 03-01-07ab  
REVISED: 02-27-07

<p>SCALE: 1"=20'</p>	<p>RENOVATE OFFICE BUILDING</p> <h2 style="margin: 0;">DAMMON ENGINEERING, INC.</h2> <p style="font-size: small;">1095 FLORIDA AVENUE 985-649-5832 SLIDELL, LA. 70458 DAMMONENGINEERING.COM</p>	<p>PROPOSED SITE PLAN</p> <p>ST. TAMMANY PARISH OFFICE BUILDING 520 OLD SPANISH TRAIL SLIDELL, LOUISIANA</p>
<p>SHEET</p> <h1 style="font-size: 2em; margin: 0;">C-3</h1> <p>OF</p>	<p>FILE:</p> <p>JOB NO. 1729</p> <p>DATE: 1-8-07</p>	