



LEGEND

NEW WALLS - [Hatched Pattern]

FIRST FLOOR STRUCTURAL PLAN
 SCALE: 1/8" = 1'-0"

- NOTES:**
- ELEVATOR CONTRACTOR SHALL RELOCATE 1ST FLOOR STOPS TO ACCOUNT FOR RAISING FLOOR 3".
 - INSTALL 4" SCHEDULE 40 PIPE COLUMN W/ 6" X 8" X 1/4" PLATE T & B @ FLOORS 1 THRU 6 TO SUPPORT EXISTING HORIZONTAL WF BEAM PRESENTLY ATTACHED TO VERTICAL COLUMN AT EXTERIOR OF WALL. WELD NEW COLUMN TO BOTTOM OF EXISTING BEAM ABOVE. REMOVE EXTERIOR COLUMN, TRIM BEAM TO WALL AND ADD NEW SIDING TO MATCH. PATCH INTERIOR WALL (4 LAYERS OF 5/8" GYPSUM W/ GYP. BOARD).
 - ALL MISC. STEEL SHALL BE ASTM A36.

REVISED: 05/21/07
 REVISED: 03/07/07

OF S-1	SHEET	DATE: 1-8-07	JOB NO. 1729	FILE:	SCALE: AS NOTED	1ST FLOOR STRUCTURAL PLAN ST. TAMMANY PARISH ADMIN. COMPLEX 520 OLD SPANISH TRAIL SLIDELL, LOUISIANA
DAMMON ENGINEERING. INC. 1095 FLORIDA AVENUE 985-649-5832 SLIDELL, LA. 70458 DAMMONENGINEERING.COM						