

DOOR & HARDWARE SCHEDULE

MARK	DETAILS	SIZE	DOOR TYPE	FRAME	HWDR. NO.	STC	REMARKS
EXTERIOR DOORS							
1	12-18 A1.20	PR. 3/0 x 7/0	GAUV. PTD. STEEL INSUL.	GAUV. PTD. STEEL	-	NA	FULL GLAZED LITE GLAZING TO MATCH WINDOWS
2	12-17 A1.20	PR. 3/0 x 7/0	GAUV. PTD. STEEL INSUL.	GAUV. PTD. STEEL	-	NA	6"x12" VISION LITE, GLAZING TO MATCH
3	12-13 A1.20	PR. 2/10 x 7/0	GAUV. PTD. STEEL INSUL.	GAUV. PTD. STEEL	-	NA	
4	12-13 A1.20	4/0 x 7/0	GAUV. PTD. STEEL INSUL.	GAUV. PTD. STEEL	-	NA	6"x12" VISION LITE, GLAZING TO MATCH
5	12-13 A1.20	3/6 x 7/0	GAUV. PTD. STEEL INSUL.	GAUV. PTD. STEEL	-	NA	6"x12" VISION LITE, GLAZING TO MATCH
6	12-13 A1.20	3/0 x 7/0	GAUV. PTD. STEEL INSUL.	GAUV. PTD. STEEL	-	NA	6"x12" VISION LITE, GLAZING TO MATCH
7	26-27 A1.21	26/0 x 16/0	GAUV. PTD. STEEL INSUL.	GAUV. PTD. STEEL	-	NA	OVERHEAD DOOR
8	26-27 A1.21	12/0 x 16/0	GAUV. PTD. STEEL INSUL.	GAUV. PTD. STEEL	-	NA	OVERHEAD DOOR
INTERIOR DOORS							
9	18-19 A1.21	PR. 3/0 x 6/8	PTD. STEEL INSUL.	PTD. STEEL	-	50	
10	-	5/0 x 6/8	HOL. METAL CASED OPENING	PTD. STEEL	-	NA	
11	-	4/0 x 7/4	CMU CASED OPENING	NA	-	NA	SHOWER ROD & CURTAINS
12	-	3/6 x 6/8	VAULT DOOR	PTD. STEEL	-	NA	
13	15-16 A1.20	3/6 x 6/8	PTD. STEEL	PTD. STEEL	-	NA	1 HR. MIN. RATED ASSEMBLY, 6"x12" VISION LITE GLAZING TO MATCH
14	15-16 A1.20	3/0 x 7/0	PTD. STEEL	PTD. STEEL	-	NA	
15	15-16 A1.20	3/0 x 7/0	PTD. STEEL INSUL.	PTD. STEEL	-	40	
16	15-16 A1.20	3/0 x 7/0	PTD. STEEL INSUL.	PTD. STEEL	-	40	
17	15-16 A1.20	3/0 x 7/0	PTD. STEEL	PTD. STEEL	-	NA	1 HR. MIN. RATED ASSEMBLY, 6"x12" VISION LITE GLAZING TO MATCH
18	15-16 A1.20	3/0 x 7/0	PTD. STEEL	PTD. STEEL	-	NA	6"x12" VISION LITE, GLAZING TO MATCH
19	-	3/0 x 7/4	CMU CASED OPENING	NA	-	NA	SHOWER ROD & CURTAINS
20	18-19 A1.21	3/0 x 6/8	PTD. STEEL INSUL.	PTD. STEEL	-	42	6"x12" VISION LITE, GLAZING TO MATCH
21	18-19 A1.21	3/0 x 6/8	PTD. STEEL INSUL.	PTD. STEEL	-	45	6"x12" VISION LITE, GLAZING TO MATCH
22	18-19 A1.21	3/0 x 6/8	PTD. STEEL INSUL.	PTD. STEEL	-	45	
23	18-19 A1.21	3/0 x 6/8	PTD. STEEL INSUL.	PTD. STEEL	-	42	
24	18-19 A1.21	3/0 x 6/8	PTD. STEEL	PTD. STEEL	-	NA	
25	18-19 A1.21	3/0 x 6/8	PTD. STEEL	PTD. STEEL	-	NA	
26	18-19 A1.21	3/0 x 6/8	PTD. STEEL INSUL.	PTD. STEEL	-	45	

WINDOW SCHEDULE

MARK	DETAILS	SIZE	DOOR/WINDOW TYPE	FRAME	GLASS	LITES	REMARKS
A	20-21 A1.22	3/4 x 4/0	FIXED	ALUMINUM	TINTED INSULATED, LOW-E	NONE	BLINDS, SEE NOTE 1
B	20-21 A1.22	4/0 x 3/6	FIXED	ALUMINUM	TINTED INSULATED, LOW-E	NONE	BLINDS, SEE NOTE 1
C	23-24 A1.22	12/0 x 6/2	FIXED	ALUMINUM	TINTED INSULATED, LOW-E	NONE	

NOTES: 1. BLINDS TO BE 1" WIDE "VENETIAN" ALUMINUM

FINISH SCHEDULE

ROOM NUMBER	ROOM NAME	WALLS C3010 (NOTE 3)	STC REQD./PRVD.	EXTEND WALL TO DECK ABOVE	FLOOR C3020	WALL BASE C30208 (NOTE 1)	CEILING C3030 (NOTE 3)	CLG. HT.	CABINETRY	NOTES	SO. FT. REQD./PRVD.	COMMENTS
FIRST FLOOR												
100	CANOPY ENTRANCE		NA		CONC		MS	12'-0"			NA/44'	6'x9'-4"; PROVIDE RECESSED MATS
101	REAR ENTRY	IRMT/EP	NA / 48		CONC	RB	MS	9'-0"		(NOTE 8)	NA/20'	PROVIDE RECESSED MATS
102	ENTRY	IRMT/EP	42 / 48	YES	QVT	RB	GMB	9'-0"		(NOTE 2) (NOTE 5) (NOTE 8)	120'/114'	PROVIDE RECESSED MATS
103	LOBBY	IRMT/EP	NA / 48		QVT	RB	GMB	10'-0"		(NOTE 8)	NA/426'	PROVIDE RECESSED MATS
104	SIDE ENTRY	IRMT/EP	NA / 48		CONC	RB	PS/MP	12'-6"		(NOTE 8)	NA/45'	PROVIDE RECESSED MATS
105	CAGES	EP	NA / 48		CONC	RB	PS/MP	12'-6"		(NOTE 5)	3629'/4516'	
106	CSS	P	40 / 48		CONC	RB	ACT	9'-0"			120'/220'	
107	ARMORY	EP	NA / 48		CONC	RB	PS/MP	11'-0"		(NOTE 5)	1500'/1484'	
108	SHOWER	PT	40 / 48		PT	PT	GMB	9'-0"			51'/59'	
109	HEAD	PT	40 / 48		PT	PT	GMB	9'-0"			48'/45'	
110	JANITOR	EP	NA / 48		CONC	RB	PS	12'-6"		(NOTE 5)	35'/28'	
111	MALE HEAD	PT	40 / 48		PT	PT	GMB	9'-0"			220'/204'	
112	MALE SHOWER	PT	40 / 48		PT	PT	GMB	9'-0"			180'/191'	
113	MAIN ELECTRICAL ROOM	P	42 / 50	YES	CONC	RB	PS	12'-6"		(NOTE 5) (NOTE 6)	120'/155'	
114	MECHANICAL ROOM	P	50 / 50	YES	CONC	RB	PS	12'-6"		(NOTE 5) (NOTE 6)	120'/130'	
115	INTERIOR STAIRS	IRMT/EP	NA / 48		QVT/RT	RB	PS/MP	12'-6"		(NOTE 5)	400'/267'	
116	VESTIBULE	IRMT/EP	NA / 48	YES	QVT	RB	GMB	10'-0"			NA/66'	
SECOND FLOOR												
200	CORRIDOR	IRMT/EP	NA / 45		QVT	RB	ACT	9'-6"			NA/983'	PROVIDE RECESSED MATS @ ENTRY
201	TELECOM ROOM	P	42 / 45	YES	QVT	RB	GMB	10'-6"			120'/148'	
202	RADIO ROOM	P	45 / 45	YES	QVT	RB	GMB	10'-6"			200'/197'	
203	MISSION BRIEFING ROOM(S) FOR 24	P	45 / 45	YES	QVT	RB	ACT	9'-6"			1050'/1085'	
204	RIVERINE TASK UNIT COMMANDER OFFICE	P	42 / 45	YES	QVT	RB	ACT	9'-6"			360'/395'	
205	RIVERINE TASK UNIT OFFICE	P	42 / 45	YES	QVT	RB	ACT	9'-6"			660'/339'	
206	RIVER OPS CONTROL WATCH STATION	P	42 / 45		QVT	RB	ACT	9'-6"		(NOTE 4)	300'/205'	
207	SQUADRON INTEROPERABILITY TASK UNIT OFFICE	P	45 / 45	YES	QVT	RB	ACT	9'-6"			360'/398'	
208	SQUADRON INTEROPERABILITY TASK UNIT OFFICE	P	45 / 45	YES	QVT	RB	ACT	9'-6"			480'/855'	
209	RIVERINE TASK UNIT COMMANDER OFFICE	P	42 / 45	YES	QVT	RB	ACT	9'-6"			360'/399'	
210	RIVERINE TASK UNIT OFFICE	P	42 / 45	YES	QVT	RB	ACT	9'-6"			660'/324'	
211	MALE HEAD	PT	40 / 45		PT	PT	GMB	9'-6"			220'/197'	
212	FEMALE HEAD	PT	40 / 45		PT	PT	GMB	9'-6"			36'/32'	
213	MECHANICAL/ELECTRICAL ROOM	P	50 / 51	YES	CONC	RB	PS	VAIRES			120'/327'	
214	JANITOR	EP	NA / 45		PT	RB	GMB	9'-6"			35'/31'	
215	INTERIOR STAIRS	IRMT/EP	NA / 48	YES	QVT/RT	RB	PS/MP	9'-6"			400'/267'	
216	COPY AREA	P	NA / 45		QVT	RB	ACT	9'-6"			NA/74'	
217	CHART ROOM	P	NA / 45		QVT	RB	ACT	9'-6"			NA/122'	
BOAT MAINTENANCE / STAGING BUILDING												
	BOAT SPACES	EP/MP	NA		CONC	RB	PS/MP			(NOTE 5)		
	MAINTENANCE SPACE	EP/MP	NA		CONC	RB	PS/MP			(NOTE 5)		

- NOTES:
- PROVIDE RB AT ALL GNB WALLS.
 - INCLUDES ENTRANCE FACILITY, TELECOMMUNICATIONS ROOMS AND OTHER SERVER/JAN ROOMS.
 - PAINT ALL STRUCTURAL STEEL COLUMNS, BRACING AND OTHER STRUCTURAL MEMBERS UNLESS INDICATED OTHERWISE.
 - PROVIDE DESK-HIGH COUNTERTOP ALONG WINDOWS AND BASE CABINETS, WALL CABINETS AND COUNTERTOP AT COFFEE MESS.
 - "PAINTED STRUCTURE" INCLUDES ALL VERTICAL AND HORIZONTAL STRUCTURAL MEMBERS OCCURRING WITHIN THIS SPACE.
 - ELECTRICAL AND MECHANICAL ROOMS ON FIRST FLOOR SHALL USE Minivol-1200 2" INDUSTRIAL BOARD.
 - ELECTRICAL AND MECHANICAL ROOMS ON SECOND FLOOR SHALL USE Minivol TYPICAL SOUND BARRIER ASSEMBLES STC 51.
 - PROVIDE PEREC MAT - ALUMINUM HINGE RECESSED MAT. FRAME 551: ALUMINUM, RECESSED. FRAME 548 MAY BE SUBSTITUTED.

ACT	ACOUSTICAL CEILING TILE
CONC	SEALED CONCRETE
QVT-1	CARPET TILE TYPE 1
QVT-2	CARPET TILE TYPE 2
EP	EPOXY PAINT
GMB	GYPSUM WALL BOARD
IRMT	IMPACT RESISTANT WALL TREATMENT
MP	MASTER PAINTERS' INSTITUTE (MPI)
MS	METAL SOFFIT
P	PAINT
PS	PAINTED STRUCTURE
PT	PORCELAIN TILE
QVT	QUARTZ VINYL TILE
RB	RUBBER BASE
RT	RUBBER STAR TREADS

DEPARTMENT OF THE NAVY
NAVAL FACILITIES ENGINEERING COMMAND SOUTHEAST
NAVAL AIR STATION JACKSONVILLE
MISSISSIPPI

JOHN C. STENNIS SPACE CENTER
SOF RIVERINE AND COMBATANT CRAFT OPERATIONS FACILITY - PRE-FINAL
DOOR, WINDOW & FINISH SCHEDULES

DESIGNED BY: R. WILSON
DRAWN BY: J. WHELAN

DATE: 01 JAN 2009

SCALE: AS SHOWN
SHEET NO.: P-210
WORK ORDER NO.: 510247
CONTRACT NO.: N62467-05-0-0096
NAVFAC DRAWING NO.: 3100-117

EMMETT B. DAMMON, JR.
REGISTERED PROFESSIONAL ENGINEER
STATE OF MISSISSIPPI
NO. 9832

DAMMON ENGINEERING, INC.
1000 W. GULF BLVD., SUITE 100
DAMMON, LA 70038
(989) 649-8312

NAVFAC

DATE	APPR	DESCRIPTION