



- SPECIFIC NOTES THIS SHEET:**
- ① 30A, NEMA-3R UNFUSED DISCONNECT. PROVIDE FINAL CONNECTIONS TO CHILLED WATER PUMP. ROUTE 3/4"C. 3-#10 AWG AND 1-#10 GRD TO VED LOCATED IN MECH ROOM #214. SEE CONTINUATION SHEET E4.1.
 - ② 200A, NEMA-3R UNFUSED DISCONNECT. 1-1/2"C. 3-#1 AWG AND 1-#6 GRD. PROVIDE FINAL CONNECTIONS TO CHILLER STARTER.
 - ③ 2-2"C ROUTED TO MAIN ELEC ROOM #213 FOR ANTENNA CABLING BY OWNER. SEE SHEET E5.1 FOR FURTHER INFORMATION ON ROUTING TO RADIO ROOM #202.
 - ④ 2-3"C. 4-250 KOWIL AND 1-#2 GRD. ROUTE FROM 450A MAIN DISCONNECT IN GENERATOR TO TRANSFER SWITCH IN MAIN ELEC ROOM #113.
 - ⑤ 1-1"C. CONTROL WIRING FOR GENERATOR START/STOP. ROUTE TO TRANSFER SWITCH IN MAIN ELEC ROOM #113.
 - ⑥ 3/4"C. 2-#12 AWG AND 1-#12 GRD. PROVIDE FINAL CONNECTIONS TO BLOCK AND SPACE HEATERS IN GENERATOR.
 - ⑦ ONAN DODAA 250KW STANDBY GENERATOR, DIESEL DRIVEN, WITH SUB-BASE FUEL TANK, SOUND ATTENUATED WEATHERPROOF ENCLOSURE, CRITICAL GRADE EXHAUST SILENCER, AND 450A MAIN CIRCUIT BREAKER.

PRE-FINAL SUBMISSION
MAY 15, 2009
NOT FOR CONSTRUCTION

<p>DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING COMMAND NAVAL FACILITIES ENGINEERING COMMAND SOUTHEAST NAVAL AIR STATION JACKSONVILLE MISSISSIPPI</p> <p>JOHN C. STENNIS SPACE CENTER</p> <p>SOF RIVERINE AND COMBATANT CRAFT OPERATIONS FACILITY</p> <p>ELECTRICAL DETAILS</p>	<p>STATE OF LOUISIANA M. KIMBALL SCHLAFLY REG. NO. 27699 PROFESSIONAL ENGINEER ELECTRICAL ENGINEERING</p>	<p>DES. K. SCHLAFLY DWG. K. SCHLAFLY REVIEWED BY: R. WILISE P.N./CHK. T. ARMBR CHIEF ENGINEER: P. DAMON</p>	<p>ENGINEERING LLC 121 SOUTH GENOIS STREET NEW ORLEANS, LA 70119 PHONE: 504-885-1447 FAX: 504-885-7980 M. KIMBALL SCHLAFLY, P.E. LA REG 27699</p>	<p>NAVFAC</p>	<table border="1"> <thead> <tr> <th>DATE</th> <th>DESCRIPTION</th> <th>APPR</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>	DATE	DESCRIPTION	APPR						
DATE	DESCRIPTION	APPR												

WORK ORDER NO. #####
SPL PROJ. NO. #####
SCALE: AS SHOWN
CODE ID. NO. N4412 SIZE 0
DRAWING NO. #####
CONSTR. CONTR. NO. N62467-05-D-0096
NAVFAC DRAWING NO. #####
SHEET XXX OF XXX

DATE: 01 JUN 2009