



- GENERAL NOTES: THIS SHEET:**
1. REFERENCE INTERIOR DESIGN CID DRAWINGS FOR DIMENSIONED LOCATIONS OF ALL CABLE TV JACKS.
  2. COORDINATE EXACT LOCATION OF ALL TELECOMMUNICATIONS JACKS WITH FURNITURE LOCATIONS. ADJUST ROUGH-IN TO AVOID CONFLICT WITH PARTITIONS MOUNTED TO WALLS.
  3. TELECOMMUNICATIONS JACKS WITH SUBSCRIPT "F" INDICATE INSTALLATION IN FURNITURE PARTITIONS. PROVIDE FLEXIBLE CONDUIT CONNECTION AND EXTEND WIRING FROM WALL BOX THROUGH RACEWAY IN FURNITURE. PROVIDE JACKS AND BEZELS AS NEEDED TO COMPLETE INSTALLATION IN FURNITURE PARTITION.
  4. FLUSH MOUNT ALL DEVICES IN CMU WALLS EXCEPT WITHIN MAINTENANCE 2441. ROUTE 3/4" CONDUIT OVERHEAD ELECTRICAL ROOM #113. SEE NOTE 5 FOR INFORMATION ON ROUTING CABLES TO TELECOMMUNICATIONS ROOM #201 ON SECOND FLOOR.

OPERATIONS/MAINTENANCE BLDG 2440/2441  
 1ST FLOOR PLAN - TELECOMMUNICATIONS  
 SCALE: 1/8"=1'-0"  
 0 4 8 16  
 PLAN  
 NORTH

- SPECIFIC NOTES: THIS SHEET:**
1. 6-4"C AND 4-2"C ROUTED TO MANHOLE. SEE SHEET E2.1 FOR CONTINUATION. TURN UP THROUGH SLAB OUTSIDE OF GRADE BEAM AND FOOTING. STAY BEHIND LINE OF CAGES AND DO NOT ENCRoACH ON CORRIDOR.
  2. ROUTE ALL COMMUNICATIONS CONDUIT TO CEILING AND CONTINUE HORIZONTALLY HELD TIGHT AS POSSIBLE TO UNDERSIDE OF BAR JOISTS. TURN UP INTO SECOND FLOOR TELECOMMUNICATIONS ROOM #201 AS SHOWN. COORDINATE PENETRATIONS WITH STRUCTURAL ENGINEER. ADJUST SPACING AS REQUIRED.
  3. 1" CONDUIT FOR REMOTE MONITORING OF ELECTRIC METER. STUB UP THROUGH SLAB INSIDE CMU WALL. TRANSITION INTO CEILING SPACE AND ROUTE TIGHT TO UNDERSIDE OF BAR JOISTS AS SHOWN. TURN UP THROUGH FLOOR INTO TELECOMMUNICATIONS ROOM #201.
  4. CONTINUE 1"C TO TRANSFORMER SLAB. STUB UP IN SECONDARY COMPARTMENT AND CAP FOR FUTURE USE.
  5. PROVIDE 4-2" CONDUITS THROUGH SECOND FLOOR SLAB INTO MECH/ELEC ROOM 213. SEE SHEET E5.2 FOR CONTINUATION. ROUTE ALL SECURE NETWORK CABLE IN 1" CONDUIT, AND ALL NONSECURE CABLES IN OTHER CONDUIT. PROVIDE PULLSTRING FOR FUTURE ADDITIONS BY OWNER. PROVIDE PULLSTRINGS IN EMPTY CONDUITS FOR FUTURE USE.
  6. PROVIDE 2-2"C ROUTED BELOW SLAB TO ANTENNA YARD. SEE SHEET E2.3 FOR CONTINUATION. TURN UP INTO WALL MOUNTED PULL BOX WITH LOCKABLE COVER. CONTINUE 2-2"C THROUGH SECOND FLOOR SLAB AND ROUTE ABOVE SECOND FLOOR CEILING TO RADIO ROOM #202.
  7. PROVIDE 2-1" CONDUITS THROUGH SECOND FLOOR SLAB INTO MECH/ELEC ROOM 213. SEE SHEET E5.2 FOR CONTINUATION. ROUTE ALL RG6 CABLE IN 1" CONDUIT. PROVIDE PULLSTRING FOR FUTURE ADDITIONS BY OWNER. PROVIDE PULLSTRINGS IN EMPTY CONDUIT FOR FUTURE USE.

**PRE-FINAL SUBMISSION**  
 MAY 15, 2009  
**NOT FOR CONSTRUCTION**

DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING COMMAND NAVAL FACILITIES ENGINEERING COMMAND SOUTHEAST NAVAL AIR STATION JACKSONVILLE MISSISSIPPI JOHN C. STENNIS SPACE CENTER <b>SOF RIVERINE AND COMBATANT CRAFT OPERATIONS FACILITY</b> BLDG 2440/2441 1ST FLOOR - TELCO		CHIEF ENGINEER P. DAMON	DESIGNED BY: R. WILSON P. DAMON	REG. NO. 27699 PROFESSIONAL ENGINEER M. KIMBALL SCHLAFLY, P.E. LA REG 27699	ENGINEERING LLC 121 SOUTH GNOUS STREET NEW ORLEANS, LA 70119 PH: 504-885-7947 FAX: 504-885-7930 M. KIMBALL SCHLAFLY, P.E. LA REG 27699	NAVFAC 	DATE APPR	DESCRIPTION SYM
--	--	----------------------------	------------------------------------	--	--	------------	--------------	--------------------

DEPARTMENT OF THE NAVY  
 NAVAL FACILITIES ENGINEERING COMMAND SOUTHEAST  
 NAVAL AIR STATION JACKSONVILLE  
 MISSISSIPPI  
 JOHN C. STENNIS SPACE CENTER  
**SOF RIVERINE AND COMBATANT CRAFT OPERATIONS FACILITY**  
 BLDG 2440/2441 1ST FLOOR - TELCO  
 SCALE: 1/8"=1'-0"  
 CODE ID NO. N4412 SIZE 0  
 DRAWING NO. #####  
 STA. PROJ. NO. #####  
 WORK ORDER NO. #####  
 CONSTR. CONTR. NO. N62467-05-D-0096  
 NAVFAC DRAWING NO. N62467-05-D-0096  
 SHEET XXX OF XXX  
**E5.1**