

\*RE-PRINT\*

CUSTOMER COPY

BILL TO:

MISC. CUSTOMER ACCT.  
MISC. CUSTOMER ST

MISC CUSTOMER CITY TN 00000

SHIP TO:

I&C MARKET - ASPEN POWER  
DISTRIBUTOR  
REF: RIVERINE PROJECT  
STENNIS, MS  
DENVER

CO80234

DESCRIPTION PRODUCT NUMBER

LOSSES DATA FOR TRANSFORMER IS BASED ON:  
LOSS GRT: REF TEMP BASIS: A VOLT% : 100  
FREIGHT PREPAID AND ALLOWED FOB: STENNIS, MS  
LEAD TIME 6 WEEKS ARO  
\*QUOTED PER SECTION 26 12 19.10  
REFERENCE 1.4, 1.5.1, 1.6.1: WILL BE PROVIDED ARO.  
REFERENCE 2.2.1: WILL BE NEMA ICS TYPE 3X AND  
FABRICATED OF 304 STAINLESS STEEL.  
REFERENCE 2.2.2.1: ERMCO WILL NOT PROVIDE LOAD-  
BREAK CONNECTORS.  
REFERENCE 2.2.1.2.B.: ERMCO WILL NOT INSTALL OR  
PROGRAM METERING. METERING PACKAGE WILL BE  
SHIPPED WITH UNIT.  
\*REFERENCE 2.2.2.1: ERMCO WILL PROVIDE THE MOST  
OPTIMUM DESIGN AVAILABLE FOR REQUESTED LOSSES.  
REFERENCE 2.4, 2.5, 2.6: ERMCO WILL NOT PROVIDE.  
REFERENCE 2.7.1.: DUE TO SCHEDULING CONSTRAINTS,  
ERMCO WILL NOT PROVIDE TEST SCHEDULE BUT CUSTOMER  
MAY WITNESS TESTS WITH PROIR NOTIFICATION.  
REFERENCE PART 3 EXECUTION:ERMCO WILL NOT PROVIDE.  
PRICES ARE FIRM FOR RECEIPT OF AN ORDER WITHIN 30  
DAYS FROM 5/12/09 AND DELIVERY WITHIN THE QUOTED  
LEAD TIME. DELIVERIES BEYOND THE QUOTED  
LEAD TIME WILL BE SUBJECT TO ESCALATION BASED  
ON THE ERMCO MATERIAL PRICE INDEX AT THE  
TIME OF SHIPMENT. THE BASE ERMCO MATERIAL  
PRICE INDEX FOR THIS QUOTATION IS -12.33%.

ITEM 1  
ERMCO 3 PHASE PAD TRANSFORMER 3PH-PAD

ITEM# : 1.00

PROTECTIVE CAPS

OPTIONS BEGIN.....

ERMCO ERMCO STD 3PH TRANSFORMER  
0300 300 KVA  
D DELTA  
522 13800 95 BIL  
N NO NEUTRAL GROUND  
003 2 TAPS 2.5% ABOVE & BELOW  
003 480Y/277 LHL  
S5 ANSI SPECIFIC K DIM=5.0  
L LOOP FEED  
01 TIKA NO LOCKING SUPPORT ARM  
000 ERMCO STD FIXED STUD WELL

\*RE-PRINT\*

CUSTOMER COPY

QUOTED DATE 5/12/09

BILL TO:  
MISC. CUSTOMER ACCT.  
MISC. CUSTOMER ST

SHIP TO:  
I&C MARKET - ASPEN POWER  
DISTRIBUTOR  
REF: RIVERINE PROJECT  
STENNIS, MS  
DENVER

MISC CUSTOMER CITY TN 00000

CO80234

DESCRIPTION	PRODUCT NUMBER
G15	STD INSERT SYSTEM SELECT
A18	ELBOW ARRESTERS GENERIC 18KV
S	STAGGERED LV BUSHING ARRANGEMENT
000	ERMCO STD STUD LV BUSHINGS
600	6 HOLE NEMA SPADES
F58	DUAL SENSING BAYO W/ELSP (GENERIC)
CLA	GENERIC BACKUP CL FUSE
F	GENERIC FLAPPER BAYONET HOLDER
304	304L STAINLESS TANK & PEDESTAL
4	SS TANK COVER W/RECT. HANDHOLE
304	304L STAINLESS CABNET & SILL
0	STD CABINET PARTITION
0	PADMOUNT GREEN FINISH
2	SS HARDWARE W/BRONZE NUTS
11	SILICON BRONZE PENTABOLT
1	S.S. 2HOLE GRD PAD IN PRI & SEC
00	GENERIC PR VALVE .25 10PSI 35SCFM
5	HJ DV1000-001 1NPT W/S
0	1"NPT FILL PLUG
Z	ERMCO STD LEVEL GAGE
Z	ERMCO STD VACUUM GAGE
Z	ERMCO STD TEMPERATURE GAGE
23	3 TWO POS. 38KV ERMCO STD LBOR
H	HOT STICK STYLE SWITCH HANDLE
0	STD TX OIL
A	STANDARD TWO NAMEPLATES
00	STD KVA DECAL OUTSIDE
00	DOES NOT REQUIRE PCB DECAL.
01	"DANGER HIGH VOLTAGE" 7 X 10
02	WARNING "MR OUCH" GENERIC
99	STD PRIMARY DECAL INSIDE (HV)
00	NO SECONDARY VOLTAGE DECALS
00	STD ERMCO "E" LOGO DECAL
3	PLASTIC DRIP SHIELD (ECI)
OPTIONS END.....	

CUSTOMER: RIVERINE PROJECT

RFQ/Spec: \_\_\_\_\_

ERMCO Quote#: 264036

For detail information about the transformer, refer to the ERMCO quote documents.

Quote

Item	A	B	C	D	E	F	G	H	J	K	L	M	N
1	57	63.5	24	54.5	61.5	36.5	26.5	27	6	5	31	8	6.33

Quote

Item	Wt(lbs)	Oil(gn)
1	5220	253

**STANDARD FEATURES**

- 1 HV Bushing
- 2 Lifting Lugs
- 3 Bolted Cover
- 4 1" Upper Fill Plug
- 5 Pressure Relief Valve
- 6 Nameplate
- 7 Hinged Top Cabinet
- 8 LV Bushing
- 9 Drain Valve w/Sampler



ISSD BY: GS DATE: 05/12/09

REV/ISSUE DATE: SCALE: NTS

3 Phase  
Quote  
Drawing

