



Basic Quality Statistical Summary Report

Plant 141-Long Beach Yard
 Product 476-B-Base
 Specification ALDOT 825 B

Sieve/Test	Tests	Average	Target	Specification
1 1/2" (37.5mm)	5	100.0		90-100
1" (25mm)	5	94.4		75-98
3/4" (19mm)	5	86.9		
1/2" (12.5mm)	5	74.7		60-86
3/8" (9.5mm)	5	67.9		
#4 (4.75mm)	5	53.3		40-70
#6 (2.36mm)	5	39.9		28-54
#10 (2mm)	5	36.6		
#16 (1.18mm)	5	27.5		19-42
#30 (0.6mm)	5	20.1		
#40 (0.425mm)	5	17.6		
#50 (0.3mm)	5	15.6		9-32
#100 (0.15mm)	5	12.3		
#200 (75um)	5	10.04		4-18
PAN (0um)	5	0.00		

HAMMON ENGINEERING INC

Date: 5.12.09
 Reviewed: [Signature]
 Reviewed as Noted: [Signature]
 Resubmit and Resubmit: [Signature]
 Rejected: [Signature]
 Other: [Signature]

Project: Sofennis Rof

Corrections or comments made on the shop drawings during this review do not relieve the contractor from compliance with requirements of the drawings and specifications. This check is only for review of the general conformance with the design concept of the project and general compliance with the information given in the contract documents. This contractor is responsible for confirming and correlating all quantities and dimensions, selecting fabrication processes and techniques of construction, coordinating his or her work with that of all other trades and performing all in a safe and satisfactory manner.

Vulcan Materials Company

Submital Item: Base Course
 Comments

BROADMOOR, L.L.C.

I hereby agree that the (equipment) (material) (article) shown and marked in this submittal is that proposed to be incorporated with contract number N69450-05-D-0096, is in compliance with the contract documents, can be installed in the allocated spaces, and is submitted for Government approval.

Robert [Signature] 5.12.09
 Date

DQC Manager

Page: 1 of 2

Jeffrey M Collins 5-12-09
 CC Officer Date