


FINISH SCHEDULE										
ROOM NAME	WALLS C3010 (NOTE 1)	STC REDD./PRVD.	EXTEND WALL TO DECK ABOVE	FLOOR C3020	WALL BASE C302008	CEILING C3030 (NOTE 1)	CABINETRY	NOTES	SQ. FT. REDD./PRVD.	COMMENTS
INTERIOR	EP/MPI	NA	NO	CONC	RB	PS / MPI	NA	(NOTE 1) (NOTE 2)	9207 / 8554	

- NOTES:  
1. PAINT ALL STRUCTURAL STEEL COLUMNS, BRACING AND OTHER STRUCTURAL MEMBERS UNLESS INDICATED OTHERWISE.  
2. "PAINTED STRUCTURE" INCLUDES ALL VERTICAL AND HORIZONTAL STRUCTURAL MEMBERS OCCURRING WITHIN THIS SPACE.

DOOR & HARDWARE SCHEDULE							
MARK	DETAILS HEAD JAMB SILL	SIZE	DOOR TYPE	FRAME	HINGE	LOCK	REMARKS
<b>EXTERIOR DOORS</b>							
1	12 A1.20	13 A1.20	14 A1.20	3/0 x 6/8 INSULATED HOLLOW METAL	STEEL HOLLOW METAL	BUTT 1-1/2 PR	KEYED HANDLE DOOR STOP, SILENCER, CLOSER, KICK PLATES AT INTERIOR AND VISION LITE
2	26 A1.21	27 A1.21	28 A1.21	26/0 x 16/0 OVERHEAD DOOR			

WINDOW SCHEDULE							
MARK	DETAILS HEAD JAMB SILL	SIZE	DOOR / WINDOW TYPE	FRAME	GLASS	LITES	REMARKS
A	23 A1.22	24 A1.22	25 A1.22	4/0 x 3/6 FIXED	ALUMINUM	TINTED, INSULATED, LOW-E	NONE

SYMBOL	DESCRIPTION	DATE	APPR
	REVISED AS PER URS COMMENTS 9 OCTOBER 2009	11-6-09	RW



**DAMMON ENGINEERING, INC.**  
REGISTERED PROFESSIONAL ENGINEER  
DAMMON, P. C. & ASSOCIATES  
SUITE 100, 700 N. WILSON  
DALLAS, TEXAS 75202  
(972) 649-5812



**EMMET G. DAMMON**  
REGISTERED PROFESSIONAL ENGINEER  
STATE OF MISSISSIPPI  
9662

DESIGNED BY: R. WITSE  
CHECKED BY: T. ARBIB  
DATE: 11/06/09  
PROJECT: NAVAL FACILITIES ENGINEERING COMMAND SOUTHEAST  
NAVAL AIR STATION JACKSONVILLE  
MISSISSIPPI

DEPARTMENT OF THE NAVY  
**NAVAL FACILITIES ENGINEERING COMMAND SOUTHEAST**  
IPT GULF COAST  
**JOHN C. STENNIS SPACE CENTER**  
**SOF RIVERINE AND COMBATANT CRAFT OPERATIONS FACILITY - PRE-FINAL**  
**DOOR, WINDOW & FINISH SCHEDULES**

SCALE: AS SHOWN  
SHEET NO. P-210  
WORK ORDER NO. 510247  
CONSTR. CONTR. NO. N62467-05-0-0096  
NAVFAC DRAWING NO. 15026703  
SHEET 36 OF 132

