



BOAT STORAGE BLDG. 2442
 FLOOR PLAN - LIGHTING
 SCALE: 1/8" = 1'-0"
 PLAN NORTH

- GENERAL NOTES THIS SHEET:
1. ALL FIXTURES TYPE N UNLESS NOTED OTHERWISE.
 2. ALL WIRING SHALL BE 3/4" C. 2-#12 AWG AND 1-#12 GRD UNLESS NOTED OTHERWISE.
 3. ALL CONDUIT SHALL CONTAIN MINIMUM #12 AWG GROUND WIRE UNLESS NOTED OTHERWISE.
 4. ALL MOUNTING HEIGHTS SHOWN ARE TO BOTTOM OF FIXTURE AS MEASURED FROM FINISHED FLOOR ELEVATION.
 5. ALL TYPE N FIXTURES SHALL BE MOUNTED 21'-8" AFF.
 6. ALL LIGHT SWITCHES SHALL HAVE INTEGRAL TIMERS, MAXIMUM SETTING 4 HOURS, INTERMATIC FF4H.

THESE PLANS AND SPECIFICATIONS HAVE BEEN PREPARED BY OR UNDER OUR DIRECT SUPERVISION, AND WE ARE AWARE OF ALL REGULATORY REQUIREMENTS. WE ARE NOT GENERALLY ADMINISTERING THE WORK.

SCHLAFLY ENGINEERING LLC
 9-4-09
 PER: *[Signature]*
 REG. # 27699

<p>SCHLAFLY ENGINEERING LLC 121 SOUTH GENOIS STREET NEW ORLEANS, LA 70119 PH: 504-885-1947 FX: 504-885-1930 M. KIMBALL SCHLAFLY, P.E. LA REG. 27699</p>		DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING COMMAND NAVAL FACILITIES ENGINEERING COMMAND SOUTHEAST NAVAL AIR STATION JACKSONVILLE MISSISSIPPI JOHN C. STENNIS SPACE CENTER	DEPARTMENT OF THE NAVY NAVAL FACILITIES ENGINEERING COMMAND NAVAL FACILITIES ENGINEERING COMMAND SOUTHEAST NAVAL AIR STATION JACKSONVILLE MISSISSIPPI JOHN C. STENNIS SPACE CENTER
		BLDG 2442 FLOOR PLAN - LIGHTING	BLDG 2442 FLOOR PLAN - LIGHTING
REG. # 27699 PER: <i>[Signature]</i> 9-4-09	REG. # 27699 PER: <i>[Signature]</i> 9-4-09	CODE ID NO. N4412 SIZE 0 SCALE 1/8" = 1'-0" SHEET 112 OF 132	CODE ID NO. N4412 SIZE 0 SCALE 1/8" = 1'-0" SHEET 112 OF 132