SITE PLAN - PHOTOMETRICS
SCALE: 1"=40'

Luminaire Schedule						
Symbol	Qty	Label	Arrangement	Lumens	LLF	Description
	22	J	SINGLE	27500	0.650	HPIP-TM-250-MT-4-F1-BK
	10	K	SINGLE	50000	0.650	HPTR-3S-400-MT-BK
	6	L	SINGLE	50000	0.650	HPTR-5F-400-MT-BK

Calculation Summary							
Label	CalcType	Units	Avg	Max	Min	Avg/Min	Max/Min
CAMPUS-PARK-REAR DRIVE	Illuminance	Fc	1.90	19.4	0.2	9.50	97.00
REAR CAMPUS	Illuminance	Fc	2.02	8.9	0.1	20.20	89.00
FUTURE PARK-ROADWAY	Illuminance	Fc	1.37	3.0	0.1	13.70	30.00

MAY 15, 2009

NAVFAC
SCHLAFLY ENGINEERING LLC
121 SOUTH GENOIS STREET
NEW ORLEANS LA 70119
PHONE 504-415-3347
FAX 504-482-7943
M. KIMBALL SCHLAFLY, P.E.
LA REG 27699

STATE OF LOUISIANA
M. KIMBALL SCHLAFLY
REG. No. 27699
REGISTERED PROFESSIONAL ENGINEER
IN
ELECTRICAL ENGINEERING
SEAL

DES: K. SCHLAFLY | DRW: K. SCHLAFLY
REVIEWED BY: R. WILTSE
PM/DM: T. ARTRIP
CHIEF ENG/ARCH: P. DAMMON

DEPARTMENT OF THE NAVY
NAVAL FACILITIES ENGINEERING COMMAND
NAVAL FACILITIES ENGINEERING COMMAND SOUTHEAST
IPT SOUTH ATLANTIC
NAVAL AIR STATION JACKSONVILLE
JOHN C. STENNIS SPACE CENTER
MISSISSIPPI

SOF RIVERINE AND COMBATANT CRAFT OPERATIONS FACILITY

SITE PLAN - PHOTOMETRICS

CODE ID. NO. N4412 | SIZE D
SCALE: 1"=40'
MAXIMO NO. ######
STA. PROJ. NO. ######
WORK ORDER NO. ######
CONSTR. CONTR. NO. N62467-05-D-0096
NAVFAC DRAWING NO. ######-##-#-####
SHEET XXX OF XXX
PH1.4

DRAWFORM REVISION: 01 JAN 2009

REVDATE: FILE NAME: C:\Schlafly ENGR\08010 SOF Riverine\Drawings\Photometrics\OPS level 1 Photometrics pre-final.dwg LAYOUT NAME: PH1.4 PLOTTED: Wednesday, May 13, 2009 - 12:37pm