

#3 x16" DOWEL BARS
 @ 36" O.C. STAGGERED
 EPOXY SET 4"-6"



18" ±

FULL DEPTH
 SAW CUT

EXISTING

EXISTING

4"



6x6x 6/6 MESH

4"-6"



UNDERPIN

4"-6"

UNDERPIN

26"-36"

SKETCH 1



DR. DANIELA EVERSGERD 1901 HWY 190, SUITE 13, MANDEVILLE, LA. 70448			
ACADIAN STRUCTURAL SOLUTIONS 57362 ALLEN RD. SLIDELL, LA. 70461			
SCALE N.T.S.	DATE 18 JUL 16	DRAWN BY EPH	PROJECT No. 588-16



Acadian Structural Solutions, Inc.

57362 Allen Road · Slidell, LA 70461-2318
(985) 641-5794

July 18, 2016

K.B. Kaufmann
3173 Terrace Ave. East
Slidell, LA 70458


RE: Dr. Daniela Eversgerd
Dental Office
1901 Highway 190, Suite 13
Mandeville, LA 70448
Job # 588-16

To David Kaufmann ,

I have reviewed the proposed layout of the slab removal as shown on Sheet 0101 by Dammon Engineering, Inc.

Attached is a sketch of the proposed slab repair with a couple of integrated comments and recommendations.

Sincerely,



Harley Nethken P.E. PTIf

ND # PE-7266	AR # 14834
SC # 29816	AL # 18300
FL # 43112	GA # 033394
OH # 61507	MS # 10871
NC # 034656	VA # 046752
LA # 23451	TN # 00114084

HN/bl