SCHEDULE OF FINISHES

ROOM FINISH key:

No.	Finish	Category
1	Vinyl Composition Tile	FLOOR
2	Computer Access Floor(ing)	FLOOR
3	Quarry/ Porcelain Paver	FLOOR
4	Welded Resilient Sheet	FLOOR
5	Concrete With Sealer	FLOOR
6	Ceramic Tile	FLOOR
7	Carpet	FLOOR
8	Elastomeric Waterproof Coating	FLOOR
9	Rubber	BASE
10	Wood	BASE
11	Quarry/ Porcelain Paver	BASE
12	Ceramic Tile	BASE
13	Carpet	BASE
14	Welded Resilient Sheet	BASE
15	Elastomeric Waterproof Coating	BASE
16	Vinyl Wall Covering	WALLS
17	Vinyl Wall Covering	WALLS
18	Wall Covering Border	WALLS
19		WALLS
20		WALLS
21		WALLS
22	Painted Gypsum Board (Eggshell)	WALLS
23	Painted Gypsum Board (Semi-Gloss)	WALLS
24	Painted Gypsum Board (Epoxy)	WALLS
25		WALLS
26	Ceramic Wall Tile	WALLS
27	Chair Rail	WALLS
28	Gypsum Board (Painted)	CEILING
29	2x4 Lay-In Acoustic Tile	CEILING
30	2x2 Lay-In Acoustic Tile	CEILING
31	Ceramic Acoustic Ceiling	CEILING
32		CEILING
33	Exposed To Structure	CEILING

CLNG. HGT.: 8'-6" Unless Otherwise Noted

ROOM NAME	FLOOR	BASE	WALLS North	WALLS South	WALLS East	WALLS West	CEILING	CLNG. HGT.	REMARKS
LABORATORY									
2C-100 Waiting	1A	9A	17B/17C	17B/17C	17B/17C	17B/17C	30A		Chair Rail 17B ABOVE
2C-101 Blood Draw	1A	9A	23A/18C	23A/18C	23A/18C	23A/18C	30A		
2C-102 Staff Toilet	4A	14A	23A	23A	23A	23A	30A		
2C-103 Patient Toilet	4A	14A	23A	23A	23A	23A	30A		
2C-104 Conference	7A	13A	17D	17D	17D	17D	30A		Chair Rail
2C-105 Director's Office	7A	13A	13F/18D	23F/18D	23F/18D	23F/18D	30A		
2C-106 Central Process	1A	9A	17'F	17F	17F	—	30A		See Finish Plan for Extent of Finishes
2C-107 Computer Equipment	1A	9A	17F	17F	17F	17F	30A		
2C-108 Suprv. Work	1A	9A	17F	17	17F	17F	30A		
2C-109 Microbiology	1A	9A	23F	23F	23F	23F	30A		
2C-110 Micro. Storage	1A	9A	23F	—	23F	23F	30A		
2C-111 H. Toilet	1A	9A	23F	23F	23F	23F	30A		
2C-112 Shower	6	12	26A	26A	26A	26A	30A		
2C-113 Autopsy	3A	11A	23F	23F	23F	23F	30A		
2C-114 Histology	4B	9A	23F	23F	23F	23F	30A		Special Flooring
2C-115 Path. Office	7A	13A	18D/23F	18D/23F	18D/23F	18D/23F	30A		
2C-116 Trafsc. Office	7A	13A	18D/23F	18D/23F	18D/23F	18D/23F	30A		
2C-117 Storage	1A	9A	23F	23F	23F	23F	30A		
2C-118 Jan. Closet	1A	9A	23F	23F	23F	23F	30A		
2C-119 Blood Bank	1A	9A	23F	23F	23F	23F	30A		
2C-119A Blood Bank	1A	9A	23F	23F	23F	23F	30A		
2C-120 Hemo/Coag	1A	9A	—	18C/23F	18C/23F	18C/23F	30A		
2C-121 Passage	1A	9A	—	18C/23F	18C/23F	18C/23F	30A		
2C-122 Passage	1A	9A	18C/23F	—	18C/23F	18C/23F	30A		
2C-123 Passage	1A	9A	18C/23F	18C/23F	—	18C/23F	30A		
2C-124 Passage	1A	9A	18C/23F	18C/23F	18C/23F	—	30A		
2C-125 Chemistry	1A	9A	23F	23F	23F	23F	30A		Columns & Wingwalls 23 Semigloss
2C-126 Blocks/Slides/Specimens	1A	9A	23F	23F	23F	23F	30A		
2C-127 Walk-in Refrigerator	3A	11A	—	—	—	—	—		
2C-128 Water Treatment Closet	1A	9A	23F	23F	23F	23F	30A		
2C-129 Electrical Closet	1A	9A	23F	23F	23F	23F	30A		
DATA PROCESSING									
4I-101 Work Room	1A	9A	23F	23F	23F	23F	30A		
4I-102 Computer Room	2	9A	23F	23F	23F	23F	30A		
4I-103 Data Processing Director	7A	13A	17D	17D	17D	17D	30A		
4I-104 Data Processing Secretary	7A	13A	17D	17D	17D	17D	30A		
4L-101 Gift Shop Storage	1A	9A	23F	23F	23F	23F	30A		
4L-103 Gift Shop Storage	1A	9A	23F	23F	23F	23F	30A		
TEMPORARY ER									
2DT-100 Corridor	1A	9A	23F	23F	23F	23F	29A		
2DT-101 Nurse Station	1A	9A	—	—	—	23F	29A		
2DT-102 Toilet	*	*	23F	23F	23F	23F	*		*Existing to Remain
2DT-103 Corridor	1A	9A	23F	23F	—	23F	29A		
2DT-104 Doctor's Office	1A	9A	18D/23A	18D/23A	18D/23A	18D/23A	29A		
2DT-105 Trauma #5	1A	9A	23F	—	—	23	29A		
2DT-106 Trauma #4	1A	9A	23F	—	—	23F	29A		
2DT-107 Trauma #3	1A	9A	—	—	23F	—	29A		
2DT-108 Storage	1A	9A	23F	23F	23F	23F	29A		
2DT-109 Soiled Linen	1A	9A	23F	23F	23F	23F	29A		
2DT-110 Nurse Station	1A	9A	23F	—	23F	23F	29A		
2DT-111 Corridor	1A	9A	23F	—	23F	23F	29A		
2DT-112 Electrical Closet	1A	9A	23F	23F	23F	23F	29A		
2DT-113 Storage	1A	9A	23F	23F	23F	23F	29A		
2DT-114 Fast Track	1A	9A	—	23F	23F	23F	29A		
2DT-115 Vestibule	1A	9A	—	23F	—	23F	29A		
2DT-116 Private Treatment	1A	9A	18A/23F	18A/23F	18A/23F	18A/23F	29A		
2DT-117 Hopper	1A	9A	23F	23F	23F	23F	29A		
2DT-118 Trauma #1	1A	9A	—	24A	24A	24A	29A		
2DT-119 Trauma #2	1A	9A	—	24	24A	24A	29A		
TEMPORARY ADMITTING									
4D-101 Waiting	7A	13A	17B	17B	17B	17B	29A		
4D-102 Triage	1A	9A	23B	23B	23B	23B	29A		
4D-103 Admitting	7A	13A	17B	17B	17B	17B	29A		
4D-104 Work Area	7A	13A	23B	23B	23B	23B	29A		
4D-105 Corridor	1A	9A	17B	17B	17B	—	29A		
4D-106 Storage/Office	1A	9A	23B	23B	23B	23B	29A		
4D-107 Break Room	1A	9A	23B	23B	23B	23B	29A		

REMARKS: Electrical Room in ER to receive matching existing finishes- all surfaces.

ROOM NAME	FLOOR	BASE	WALLS North	WALLS South	WALLS East	WALLS West	CEILING	CLNG. HGT.	REMARKS
ER									
2D-100 Corridor	1A	9A	17A	17	17	17	30A		
2D-101 Quiet Room	7A	13A	17B	17	17	17	30A		
2D-102 Phone Lobby	7A	13A	17B	17	17	—	30A		
2D-103 Registration Workroom	7A	13A	23F	23	23	23	30A		
2D-104 Registration	7A	13A	17B	17	17	—	30A		
2D-105 Waiting	7A	13A	17B/27/17	17B/27/17	17B/27/17	17B/27/17	30A		
2D-106 H. Toilet	4A	14A	17B/27/17	17B/27/17	17B/27/17	17B/27/17	30A		
2D-107 H. Toilet	4A	14A	17B/27/17	17B/27/17	17B/27/17	17B/27/17	30A		
2D-108 Triage	1A	9A	17F	17F	17F	17F	30A		
2D-109 Control Vestibule	1A	9A	—	17F	17F	17F	30A		
2D-110 Exam/ Treatment	1A	9A	—	18E/17F	18E/17F	18E/17F	30A		
2D-111 Exam/ Treatment	1A	9A	—	18E/17F	18E/17F	18E/17F	30A		
2D-113 Cardiac	1A	9A	17F	17F	17F	17F	30A		
2D-114 Nurse Station	1A	9A	17F	17F	—	17F	30A		
2D-115 Emergency Shower	6	12	26A	26A	26A	26A	30A		Floor sloped for drainage.
2D-116 Ambulance Vestibule	1A	12	23F	23F	23F	23F	30A		
2D-117 Trauma	1A	9A	23F	23F	23F	23F	30A		
2D-118 Trauma	1A	9A	23F	23F	23F	23F	30A		
2D-119 Corridor	1A	9A	17A	17A	17A	—	30A		
2D-120 Supervisor Office	7A	13A	17D	17D	17D	17D	30A		
2D-121 Cardiac	1A	9A	18E/17F	18E/17F	18E/17F	18E/17F	30A		
2D-122 Alcove	1A	9A	17F	17F	17F	—	30A		
2D-123 Dictation	1A	9A	17F	17F	17F	—	30A		
2D-124 Corridor	1A	9A	17A	—	17A	17A	30A		
2D-125 Doctor's Office	7A	13A	17D	17D	17D	17D	30A		
2D-126 Staff Toilet	4A	14A	23F	23F	23F	23F	30A		
2D-127 Staff H. Toilet	4A	14A	23F	23F	23F	23F	30A		
2D-128 E.R. Bulk Supplies	1A	9A	23F	23F	23F	23F	30A		
2D-129 Staff Break Room	1A	9A	17F	17F	17F	17F	30A		
2D-130 Corridor	1A	9A	17A	17A	—	—	30A		
2D-131 Body Holding	1A	9A	23F	23F	23F	23F	30A		
2D-132 Soiled Holding	4A	14A	23F	23F	23F	23F	30A		
2D-133 Janitor	1A	9A	23F	23F	23F	23F	30A		
2D-134 Corridor	1A	9A	17A	17A	17A	17A	30A		
2D-135 H. Toilet	4A	14A	23F	23F	23F	23F	30A		
2D-136 Ortho. Equip. Storage	1A	9A	23F	23F	23F	23F	30A		
2D-137 Cast Room	1A	9A	18E/23D	18E/23D	18E/23D	18E/23D	30A		
2D-138 Cardiac	1A	9A	18E/23D	18E/23D	18E/23D	18E/23D	30A		
2D-139 Corridor	1A	9A	17A	17A	17A	17A	30A		
2D-140 Cardiac	1A	9A	23D	23D	23D	23D	30A		
2D-141 Private Exam/ Gyn.	1A	9A	23C/18E	23C/18E	23C/18E	23C/18E	30A		
2D-142 Supply	1A	9A	23F	23F	23F	23F	30A		
2D-143 Doctor's Workroom	1A	9A	23F	23F	23F	23F	30A		
2D-144 Fast Track Treatment Bays	1A	9A	17F	17F	17F	17F	30A		
2D-145 Nurse Station	1A	9A	—	17F	—	17F	30A		
2D-146 Med-Prep. Alcove	1A	9A	23F	23F	23F	23F	30A		
2D-147 H. Toilet	4A	14A	23F	23F	23F	23F	30A		

FINISH SCHEDULE NUMBER	SELECTION	FLOOR	MANUFACTURER / NUMBER / COLOR / PATTERN
1	A	VCT	ARMSTRONG, 52128, DESERT DUST,
			STONETEX
			DIVIDER STRIP- TOLI INTERNATIONAL
			BLK NO. 4-TYPE D
3	A	PAVER	CROSSVILLE CERAMICS, A233, SAND BISQUE,
			UPI, 12"X12", GROUT-CLASSIC COLORS,
			LATICRETE, D550 FAWN BEIGE-LATEX EPOXY
4	A	SHEET VINYL	MANNINGTON, 10124, PEACHES & CREAM, FINE FIELDS
4	B	RUBBER	FLEXCO,LR-70,BEIGE W/BROWN AND WHITE
7	A	CARPET	PORTER, 09, VINEYARD, EXETER
6	A	CERAMIC	DALTILE/2"X2" CUSHION DK-157 TAN STONE

FINISH SCHEDULE NUMBER	SELECTION	BASE	MANUFACTURER / NUMBER / COLOR / PATTERN
9	A	RUBBER	JOHNSONITE, DC-49 BEIGE
11	A	PAVER	CROSSVILLE CERAMICS A233, SAND BISQUE,
			UPI, 6" X 6", COVE BASE
			GROUT-CLASSIC COLORS, LATICRETE D550,
			FAWN BEIGE
13	A	CARPET	PORTER, 09,VINEYARD, EXETER
14	A	SHEET VINYL	MANNINGTON, 10124, PEACHES & CREAM, FINE FIELDS

FINISH SCHEDULE NUMBER	SELECTION	WALLS	MANUFACTURER / NUMBER / COLOR / PATTERN
17	A	V.W.C.	ESSEX/ SP-43-21/FOAM/KIRKHILL
17	B	V.W.C.	KOROSEAL/G221-97/TAKEN FOR GRANITE/SMOKEY TOPAZ
17	C	V.W.C	KOROSEAL/8421-85/EMERALD/MURATONE
17	D	V.W.C	ESSEX/SE-42-23/AZURE/TURNBRIDGE
17	E	V.W.C.	BOLTA/WALLIA-BC-426/FLEURCLOUD/DOUBLE TAKE
17	F	V.W.C.	KOROSEAL/8421--23/TRAVERTINE/MURATONE
18	A	BORDER	C&A/XX-3064 B
18	B	BORDER	SINGER/FL6252/C/O PT 8102/LITTLE FISH
18	C	BORDER	GUARD/ESSENCE/LB-034
18	D	BORDER	ESSEX/361-2559/GREEN & PEACH/AUTUMN LEAF
23	A	SEMI-GLOSS	BENJAMIN MOORE/ 906
23	B	SEMI-GLOSS	BENJAMIN MOORE/ 973
26	A	CERAMIC	DAL-TILE- 4"X4" GLAZED/ALMOND/D735
			GROUT-LATICRETE/CLASSIC COLOURS/C-578

FINISH SCHEDULE NUMBER	SELECTION	CEILING	MANUFACTURER / NUMBER / COLOR / PATTERN
28	A	PAINT	BENJAMIN MOORE, 872
29	A	2'X4'	ARMSTRONG, CORTEGA, MINABOARD
30	A	2'X2'	ARMSTRONG, STRATUS
18	E	BORDER	C&A/Y561 32B
24	A	EPOXY	PRATT & LAMBERT/ BISCUIT/1819
23	C	SEMI-GLOSS	BENJAMIN MOORE/ 051
23	D	SEMI-GLOSS	BENJAMIN MOORE/ 908
23	E	SEMI-GLOSS	DEVOE/ TRILLIUM / IHZ 2G
23	F	SEMI-GLOSS	BENJAMIN MOORE/ 903

FINISH NOTES:

1 Paint all metal doors, frames and trim with Benjamin Moore, #1018

2 Paint any exposed grilles, panel boxes and frames to match adjacent wall surfaces. Do not paint panel electrical data labels.

3 All new flush wood doors shall be Birch, plain sliced, book matched, sanded and sealed two coats with the specified sealer. All existing doors which are to be re-finished, shall be sanded and sealed two coats with the specified sealer.

4 Where there is a transition between carpet and VCT use matching color joiner. Install VCT tile, Alternating Pattern 90° between adjacent basket weave pattern). Tile pattern for areas indicated to receive both VCT colors will be provided by Architect.

6 Install border at ceiling height, unless otherwise noted.

7 All general casework, unless otherwise noted, is to be as follows:
Counter Tops: Formica, Antique White, Granito, #688
Wall and base cabinets: Formica, Pumice, 858
"T" edge mold color: Almond
If casework is on VCT, use: Johnsonite, DC-49, Beige, coved rubber base for toe kick
If casework is on carpet, use: Plastic laminate, Wilsonart, Black, 1595-6 for toe kick

8 Carpet Base Cap to be Johnsonite, #40, Black
Vinyl Cove Cap to be Johnsonite, #49, Beige

9 Lenses of all existing light fixtures, to remain, shall be removed, cleaned and re-installed.

10 Chemical Resistant Laminate, used in Lab areas only, to be Wilsonart, Mocha Glace, #4141-90, Chemsurf

11 Corner guards and wall protection to be Decoguard, Fawn, #196- corner guard profile SM20 floor to ceiling. Contact for special META Associates' pricing: Systems Plus, Lamar Burton, (800) 272-2021.

12 Rubber 12x12X1/8" tile, as manufacture by Flexco. Color: LR-70, beige w/white and brown.

OPENING SCHEDULE

DOORS

Mark	Dimensions (width x height x thickness)	Frame	Description	Fire Rating	Elevation	Remarks
EX	EXISTING	EXISTING	EXISTING DOOR TO REMAIN			
1	4'-0" x 6'-8" x 1 3/4"	Hollow Metal	Exterior Metal Door			
2	4'-0" x 6'-8" x 1 3/4"	Hollow Metal	Flush Door			
3	4'-0" x 6'-8" x 1 3/4"	Hollow Metal	Wood Veneer Corridor Door	20 minute		
4	3'-0" x 6'-8" x 1 3/4"	Hollow Metal	Wood Veneer Corridor Door	20 minute		
5	3'-0" x 6'-8" x 1 3/4"	Hollow Metal	Wood Veneer Flush Door			
6	3'-0" x 6'-8" x 1 3/4"	Hollow Metal	Glass Opaque Shower Door			
7	3'-0" x 6'-8" x 1 3/4"	Hollow Metal	Sliding Clear Glass Door			
8	3'-0" x 6'-8" x 1 3/4"	Hollow Metal	Wood Veneer Door w/24 x 36 Vision Panel			
9	3'-8 x 6'-8" x 1 3/4"	Hollow Metal	Wood Veneer Flush Door			
10	8'-0" x 7'-0" x 1 3/4"	Hollow Metal	Triple Glass Door – Break Away Hinges			Recessed Tracks
11	4'-0" x 6'-8" x 1 3/4"	Hollow Metal	Wood Veneer Flush Door w/Bulletproof 24 x 36 Vision Panel			
12	4'-0" x 6'-8" x 1 3/4"	Hollow Metal	Wood Veneer Door w/24 x 36 Vision Panel			
13	3'-0" x 6'-8" x 1 3/4"	Hollow Metal	Wood Veneer Flush Door w/Bulletproof 24 x 36 Vision Panel			
14	7'-4" x 6'-8" x 1 3/4"	Hollow Metal	Wood Veneer Flush Door			
15	3'-0" x 6'-8" x 1 3/4"	Hollow Metal	Wood Veneer Flush Door	45 minute		
16	10'-0" x 7'-0" x 1 3/4"	Hollow Metal	Pair, Electric Sliding Doors w/ sidelights			Recessed Tracks
17	9'-6" x 7'-0" x 1 3/4"	Hollow Metal	Pair, Electric Sliding Doors w/ sidelights w/Break Away Hinges			Recessed Tracks
18	2'-6" x 7'-0" x 1 3/4"	Hollow Metal	Fixed Sidelight			
19	3'-6" x 6'-8" x 1 3/4"	Hollow Metal	Cased Opening			
20	4'-0" x 6'-8" x 1 3/4"	Hollow Metal	Cased Opening			
21	3'-0" x 6'-8" x 1 3/4"	Hollow Metal	Cased Opening			
22	3'-0" x 6'-8" x 1 3/4"	Hollow Metal	Pair Wood Veneer Flush Corridor	20 minute		
23	12'-3" x 7'-6"	No Frame	Folding Partition			Clg. Mtd. Recessed Track

WINDOWS

Mark	Dimensions (wth. x hgt. x thkns.)	Frame	Description	Fire Rating	Elevation	Remarks
EX	EXISTING	EXISTING	EXISTING WINDOW TO REMAIN			Spandrel Panel, Top & Bottom
1	Existing Opening	Aluminum	Fixed, Insulated, Grey Tinted Exterior			
2	Existing Opening	Aluminum	Fixed, Insulated, Grey Tinted Exterior			
3	4'-0" x 4'-0"	Aluminum	Fixed, Insulated, Grey Tinted Exterior			
4		Aluminum	Fixed, Insulated, Grey Tinted Exterior			
5	4'-0" x 4'-0"	Aluminum	Fixed, Insulated, Grey Tinted Exterior			
6	2'-6" x 2'-6"	Aluminum	Fixed, Insulated, Grey Tinted Exterior			
7	1'-6" x 1'-6"	Aluminum	Fixed, Insulated, Grey Tinted Exterior			
8	3'-0" x 3'-6"	Aluminum	Interior Window			
9	3'-6" x 3'-6"	Aluminum	Interior Window			One Way Glass
10	2'-6" x 3'-6"	Aluminum	Interior Window			One Way Glass
11	7'-0" x 3'-6"	Aluminum	Interior Window			One Way Glass
12	3'-0" x 3'-6"	Aluminum	Interior Window			One Way Glass
13	3'-0" x 3'-6"	Metal	Cased Opening			

REMARKS: In Window Schedule "B" = Bulletproof Glass for All Exterior Doors & Windows, Openings are to "course out" in brick coursing.

PHASE 1C LAB/ER RENOVATIONS
SLIDELL MEMORIAL HOSPTIAL
1001 GAUSE BLVD.,SLIDELL, LA.

JOHN T. CAMPO & ASSOCIATES, INC.
ARCHITECTS · PLANNERS
THE LYKES CENTER, SUITE 2018 NEW ORLEANS, LA 70130
300 POYDRAS STREET (504) 568-9912

ISSUE DATES

DATE	ISSUED TO	USE RESTRICTION
9/27/94	META	95%REVIEW
12/6/94	SMH	BID

REVISIONS

DATE	BY	DESCRIPTION

☐ PROGRESS PRINT
NOT FOR CONSTRUCTION.

☐ PARTIAL RELEASE
ONLY TO EXTENT NOTED HEREON. PARTS OF THIS DRAWING ARE RELEASED BY THE ARCHITECT FOR CONSTRUCTION.

DATE

☒ FULL RELEASE
THIS DRAWING IS FULLY RELEASED BY THE ARCHITECT FOR CONSTRUCTION OF THIS PROJECT ONLY.
DATE December 6, 1994

ALL RIGHTS RESERVED NOT TO BE COPIED OR REPRODUCED WITHOUT EXPRESSED WRITTEN CONSENT OF JOHN T. CAMPO & ASSOCIATES, INC.

COPYRIGHT © JOHN T. CAMPO & ASSOCIATES, INC., 1993

JOB NUMBER 9215-16M
DRAWN BY CW
CHECKED BY JTC

JOHN T. CAMPO · STATE OF LOUISIANA · REGISTERED ARCHITECT

OPENING, FINISH SCHEDULES
A2.1
OF 106 SHEETS