


XB80L

ULTRA GREEN™ Series 80 CFM Single-Speed Fan/Light/Night Light, Recognized as the Most Efficient of ENERGY STAR® 2015



4 Additional Images



Overall rating [Read all 5 reviews](#) | [Write a review](#)

Product Q&A [20 questions](#) | [23 answers](#)
[Read all Q&A](#)

- [Spec Sheet](#)
- [Where To Buy](#)
- [Installation Guide](#)
- [Shop for Parts](#)
- [Download catalog](#)
- [Share](#)
- [Print](#)

Overview	Video Links	Continuous Ventilation Selector	Specifications	Accessories	Reviews	Answers
----------	-------------	---------------------------------	----------------	-------------	---------	---------

Ceiling Installation	Yes
CFM @ 0.10"	80
CFM @ 0.25"	80 w/ 6" Duct
Duct Size	6" or 4"
ENERGY STAR® Most Efficient 2015	Yes
ENERGY STAR® qualified	Yes
Grille Finish	White Polymeric
Grille Length	13
Grille Width	13-3/4
Housing Height	7-5/8
Housing Length	10-1/2
Housing Width	11-3/8
HVI Certified	Yes
Light Bulb Quantity	2
Light Bulb Wattage	18
Light Bulbs Included	Yes
Nightlight	Yes
Rated Amps	0.7
Sones	<0.3 w/6" Duct
UL Listed for use over bathtubs or showers when connected to a GFCI circuit	Yes
Warranty	3 Years
Watts @ 0.1"	6.0