



FIRST FLOOR PLAN
SCALE: 1/8" = 1'-0"

LEGEND

- 1 HOUR RATED INTERIOR WALL SEE U/F U333 - SHEET A-2
- 1 HOUR RATED EXTERIOR WALL SEE U/F U356 - SHEET A-2
- 2 HOUR RATED EXTERIOR WALL SEE U/F U301 - SHEET A-2
- FIRE EXTINGUISHER

GENERAL NOTES

1. INSULATION AND INSULATION ASSEMBLIES SHALL MEET THE REQUIREMENTS OF SECTION 7.19. CONSTRUCTION. COMPANY: IRC 2009.
2. PROVIDE 5/8" LAMINOS, LEVEL WITH FINISHED FLOOR, OUTSIDE EXTERIOR DOORS ON WEST SIDE OF BUILDING. TR-259-029 SHALL BE NOT MORE THAN 1/2" IN HEIGHT AND SHALL BE BEVELLED IF MORE THAN 1/4".
3. CONTRACTOR TO VERIFY ALL SITE CONDITIONS, BUILDING LOCATIONS, AND DIMENSIONS PRIOR TO CONSTRUCTION.
4. MATERIALS SHALL BE NEW AND U.L. LISTED.
5. NOT WORK SHALL BE CONCEALED UNTIL APPROVED BY LOCAL INSPECTORS.
6. CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS, FEES, AND LOCAL CODES.
7. CONTRACTOR TO GUARANTEE WORK FOR ONE YEAR.
8. CONTRACTOR SHALL FURNISH WATER AND POWER FROM EXISTING SOURCES.
9. EXTERIOR PAINTING SHALL BE TYPICAL PAINT.
10. PAINT GRADE TO SHALL BE SPESHIN WILUAVS OR EQUIVALENT. ALL WORK TO RECEIVE 3 COATS. COLOR SELECTION BY OWNER.
11. PROVIDE CLEANUP AND REMOVE ALL DEBRIS AND TOOLS FROM SITE DURING AND AFTER CONSTRUCTION.
12. PROVIDE PROTECTION TO EXISTING WORK AND ADJACENT AREAS IN CONFORMANCE WITH APPLICABLE CODE.
13. USE 5/8" STUDS OR 4" STRAGGLED STUDS AT ALL FLOORING WALLS.
14. PROVIDE GALVANIZED METAL PAN WITH DRAIN AT WATER FEATER LOCATION.
15. ALL CORNERS SHALL BE PROPERLY BRANED FOR WIND LOADS. A 4X4 SH-FASTING SHALL BE PROVIDED EVERY 20 FEET OF WALL LENGTH.
16. INTERIOR DOORS ON BOARDS IN VIEWS OF EGRESS SHALL NOT REQUIRE THE USE OF A KEY. SPECIAL KNOWLEDGE, OR SPECIAL DEVICE TO OPEN IN THE DIRECTION OF EGRESS.
17. PROVIDE PORTABLE FIRE EXTINGUISHERS IN ACCORDANCE WITH NFPA 101. SEE APPENDIX "B" OF NFPA 101 FOR DISTRIBUTION OF EXTINGUISHERS.
18. ALL WORK SHALL COMPLY WITH THE LATEST EDITION OF ALL LOCAL, STATE, AND NATIONAL CODES COVERING THE TYPE OF WORK BEING PERFORMED.
19. PROVIDE PORTABLE FIRE EXTINGUISHERS IN ACCORDANCE WITH NFPA 101. SEE APPENDIX "B" OF NFPA 101 FOR DISTRIBUTION OF EXTINGUISHERS.
20. ALL FIRE WALLS SHALL EXTEND UP TO ROOF DECK AND BE SEALED WITH AN APPROVED FIRE CAULK.
21. ALL ELECTRICAL, MECHANICAL, AND PLUMBING MATERIALS PREPARING THE WALLS SHALL BE THE CALKED. PENETRATIONS THROUGH RATED CONSTRUCTION SHALL BE DONE IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS. SEE U/F U301 AND U302 FOR DETAILS.
22. PROVIDE FIRE EXTINGUISHER CABINET EQUAL TO FABRICATIONS ACCRITICAL SERIES VERTICAL DUAL PAINTED STEEL WITH COLOR SELECTED BY OWNER WITH STANDARD CLEAR ACRYLIC DOOR GLASSING. FULLY RECESSED WITH FLAT TBM OR ROLLED EDGE SEAM RECESSED WHERE LIMITED BY WALL CAVITY DEPTH. INCLUDE MP-54 MULTIPURPOSE EXTINGUISHER WITH 3A-40BC CAPACITY.

PRELIMINARY (NOT FOR CONSTRUCTION)

<p>SHEET No: A 1</p>	<p>FIRST FLOOR PLAN</p>	<p>LAQUINTA INNS & SUITES HATTIESBURG, MISSISSIPPI</p>	<p>2158 03-27-2013</p>	<p>JTL</p>									
<p>REVISIONS</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>#</th> <th>DESCRIPTION</th> <th>DATE</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>		#	DESCRIPTION	DATE							<p>CHIEF ENGINEER: EMMETT DAMMON, P.E. 554 OLD SPANISH TRAIL SUDELL, LA 70450</p> <p>dammoneengineering.com dammoneg@bellsouth.net PHONE: 905-649-5332 FAX: 905-641-5950</p>		
#	DESCRIPTION	DATE											