

**Gable Exhaust Fan Specification:**

Gable Exhaust Fan to be “Greenheck”, or equal, nominal 36” diameter; belt driven unit with Type “L” fabricated propeller. Provide wall collar, motor side guard, motorized damper with low leakage blade and jamb seals, and all items as required for a complete installation. Exterior components shall be constructed to meet the basic wind load speed of 140 mph and shall be fastened to meet the windborne debris protection requirements.