



FLOOR PLAN
SCALE: 1/4" = 1'-0"
TOTAL SQ. FT. = 2220 SF

DOOR & HARDWARE SCHEDULE					
MARK	SIZE	DOOR TYPE	FRAME	HWR. NO.	REMARKS
EXTERIOR DOORS					
1	30x7/0	STORE FRONT	MATCH DOOR	1	STOREFRONT UNIT, SEE ELEVATIONS
2	30x6/6	FLUSH GALV. HOL. MET. STEEL INSUL.	GALV. PTD. HOL. MET.	1	GALVANIZING TO BE G90
3	8/0x4/0	ROLLUP SHOP DOOR	GALV. PTD. HOL. MET.	NA	
INTERIOR DOORS					
4	30x6/6	FLUSH SOLID CORE WD.	PTD. HOL. MET.	2	NA
5	30x6/6	FLUSH SOLID CORE WD.	PTD. HOL. MET.	3	45 MIN. FIRE RATED DOOR SYSTEM
6	20x4/0	FLUSH SOLID CORE WD.	PTD. HOL. MET.	-	JOINT DOOR AT HEIGHT REQUIRED FOR AC RETURN, GLUE BELOW
7	30x6/6	FLUSH SOLID CORE WD.	PTD. HOL. MET.	4	STAIN SELECT BY OWNER
8	30x6/6	CASED OPENING	CASED	NA	NA
9	(2) 1/0x6/6	FLUSH SOLID CORE WD.	PTD. HOL. MET.	-	NA

MARK	SIZE	WINDOW TYPE	FRAME	GLASS	LITES	REMARKS
4	40 x 40	ALUMINUM STOREFRONT	ALUMINUM 2" x 4-1/2"	LOW E		SEE EXTERIOR ELEVATIONS

WINDOW SCHEDULE NOTES:
1. ALL FINISHMANUFACTURES TO BE SELECTED BY OWNER, VERIFY MANUFACTURER, STYLE, AND COLOR, WITH OWNER.

REF. DESIGN No.	DESCRIPTION	SIC TEST No.
WH 651-0489.01	5/8" FIRE SHIELD TYPE X WALLBOARD SCREW ATTACHED VERTICALLY TO BOTH SIDES OF 3-5/8" 20ga. STEEL STUDS 16" O.C. WALLBOARD JOINTS STAGGERED.	40 BASED ON NGC 2501
UL U495	2-1/2" FIBERGLASS INSULATION IN CAVITY	43 BASED ON NGC 2502

ROOM NUMBER	ROOM NAME	WALLS	EXTEND WALL TO ROOF DECK (CARDINAL DIRECTION)	FLOOR	WALL BASE	WAINSCOT	CLG	CLG HGT	COMMENTS
100	RECEPTION	5/8" PTD GWB	-	VCT	RB	NONE	CT	8'	
101	WARMING KITCHEN	5/8" PTD GWB	W	VCT	RB	NONE	CT	8'	
102	OFFICE	5/8" PTD GWB	W	CRP	RB	NONE	CT	8'	
103	OFFICE	5/8" PTD GWB	W	CRP	RB	NONE	CT	8'	
104	OFFICE	5/8" PTD GWB	-	CRP	RB	NONE	CT	8'	
105	SHOP	BY OWNER	-	-	RB	NONE	CT	8'	
106	MEN TOILET	5/8" PTD GWB	-	VCT	RB	NONE	CT	8'	
107	WOMEN TOILET	5/8" PTD GWB	-	VCT	RB	NONE	CT	8'	

LEGEND:

- GWB: GYPSUM WALL BOARD
- CT: CEILING TILE, 2X2
- RB: RUBBER BASE, 4" HIGH
- WB: WOOD BASE
- VCT: VINYL COMPOSITION TILE (NON-SKID)
- CRP: COMMERCIAL LOW PILE CARPET, GLUE DOWN, NO PAD
- RT: INTERLOCKING RUBBER TILES
- KRT: 1" CERAMIC TILE
- EKS: EXPOSED STRUCTURE

MOREAU'S THERMAL SERVICE

SHANE MOREAU
200 JOSEPH STREET
SLUDELL, LA 70458

JOB No: 2127 DATE: 03-20-2013
DRAWN BY: JCT CHECKED BY: CD



DAMMON
ENGINEERING, INC.
Architects & Engineers

CHIEF ENGINEER: EMMETT DAMMON, P.E.
CHIEF ARCHITECT: KEVIN KINCHEN
554 OLD SPANISH TRAIL
SLUDELL, LA 70458

dammoneengineering.com
dammoneing@bellsouth.net
PHONE: 905-649-5832
FAX: 905-641-5950

FLOOR PLAN

SHEET No: 05 OF 11

A1