




FILE NAME: C:\Projects\8PAVING\8PAVING.dwg  
 PLOT DATE: 8/27/14  
 PLOT TIME: 10:57:17 AM  
 PLOT SCALE: 1"=10'-0"  
 PLOT SHEET: 1 OF 1




**7 SITE PAVING PLAN**  
 SCALE: 1" = 10'-0"




**(F) CURB DOWEL DETAIL**




**(E) TYPICAL CURB**



**(D) TYPICAL PAVEMENT JOINT**



**(C) TYPICAL WHEEL STOP**




**(A) DRIVEWAY ROLLOVER CURB**

**8 PAVING DETAILS**  
 SCALE: 1" = 1'-0"

**GENERAL PAVING NOTES**

- ALL NEW CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 4,000 PSI AT 28 DAYS AND A MINIMUM THICKNESS OF 6". CONCRETE MIX SHALL BE IN ACCORDANCE WITH THE LATEST REVISION OF ASTM C-150 TYPE I.
- CONCRETE PAVING THICKNESS SHALL VARY AS FOLLOWS:
  - APRONS & LOADING AREAS = 8" THICKNESS (INDICATED WITH CROSS HATCH WHERE OCCURS)
  - DRIVE LANES & PARKING AREAS = 6" THICKNESS (STANDARD UNO)
- ALL REINFORCING STEEL SHALL MEET ASTM-A615 (GRADE 60).
- ALL REINFORCING STEEL SHALL BE SECURELY SUPPORTED TO PREVENT BOTH VERTICAL AND HORIZONTAL MOVEMENT DURING CONCRETE PLACEMENT. ALL CONTROL AND EXPANSION JOINTS SHALL BE LOCATED AND INSTALLED AS SHOWN ON THE PAVING PLAN AND IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.
- ALL SUB GRADE FILL SHALL BE SELECT GRANULAR MATERIAL COMPACTED TO 95% STANDARD PROCTOR DENSITY IN A MAXIMUM OF 6" LIFTS.
- ANY WORK WITHIN THE ROADWAY OR ADJACENT TO THE ROADWAY CAUSING AN INTERFERENCE TO VEHICULAR TRAFFIC MUST CONFORM TO THE REQUIREMENTS SET FORTH BY THE UNIFORM MANUAL OF TRAFFIC CONTROL DEVICES OF THE STATE OF LOUISIANA. THE CONTRACTOR MUST FURNISH ALL NECESSARY TRAFFIC SIGNS AND/OR BARRICADES AND MAINTAIN THEM DURING CONSTRUCTION ACTIVITY.

**PAVING LEGEND**



**DAMMON ENGINEERING, INC.**  
 LOUISIANA & MISSISSIPPI  
 Chief Engineer: Brian Anstich, PE  
 554 Old Spanish Trail  
 Slidell, LA 70458  
 www.dammonengineering.com  
 info@dammonengineering.com  
 PH: 985.649.8832

| # | DESCRIPTION | DATE |
|---|-------------|------|
|   |             |      |
|   |             |      |
|   |             |      |
|   |             |      |
|   |             |      |
|   |             |      |
|   |             |      |
|   |             |      |
|   |             |      |

SEAL: \_\_\_\_\_  
 REVISIONS: \_\_\_\_\_

**NEW OFFICE WAREHOUSE**  
**ZEIGLER & TRIMBER, CO.**  
 L.A. HWY 1085 DEER CROSS DRIVE  
 MADISONVILLE, LA 70447  
 JOB No: 2895 DATE: 7-25-2014  
 DRAWN BY: C&D CHECKED BY: BAY

SHEET TITLE:  
**SITE PAVING PLAN**  
 DRAWING NUMBER:  
**C101**  
 SHEET No: 2 of 1