



1 FIRST FLOOR PLAN  
SCALE 1/8" = 1'-0"  
10,000 SQUARE FEET

**PARTITION TYPES:**

- P1 EXTERIOR WALLS OF BUILDING: METAL BUILDING FRAME WITH SPLIT FACE CONCRETE BLOCK. 2x6 WD STUDS @ 16" O.C. W/ BATT INSULATION R-19, VAPOR BARRIER. 5/8" GYPSUM BOARD, TAPE, FLOAT AND PAINT.
- P2 EXTERIOR WALLS OF BUILDING: METAL BUILDING FRAME WITH METAL WALL PANELS. 2x6 WD STUDS @ 16" O.C. W/ BATT INSULATION R-19, VAPOR BARRIER. 5/8" GYPSUM BOARD, TAPE, FLOAT AND PAINT.
- P3 EXTERIOR WALLS OF BUILDING: METAL BUILDING FRAME WITH METAL WALL PANELS.
- P4 2x4 WD. STUDS @ 16" O.C. W/ ONE LAYER OF 5/8" GYPSUM BD. EA. SIDE TO CLG.
- P5 2x6 STUDS @ 16" O.C. W/ ONE LAYER OF 5/8" WATER RESISTANT GYPSUM BD. EA. SIDE TO CEILING.
- P6 2x6 WD. STUDS @ 16" O.C. W/ ONE LAYER OF 5/8" GYPSUM BD. EA. SIDE TO ROOF DECK. 1 HR. RATED UL. DES. U305.
- P7 2x6 WD. STUDS @ 16" O.C. W/ ONE LAYER OF 5/8" GYPSUM BD. EA. SIDE;

**SPECIFIC NOTES:**

- 1 PROVIDE FIRE EXTINGUISHER ON BRACKET HOLDER 2A10 BC @ 60" A.F.F TO TOP.
- 2 LANDING LEVEL W/ FLOOR SLAB.
- 3 6" DIA. PIPE BOLLARD FILLED W/ CONC.
- 4 CONTRACTOR TO SIZE AND PROVIDE HVAC UNIT. SEE A-9
- 5 PULL DOWN ATTIC STAIR
- 6 SEE SHEET A-7 FOR RESTROOM AND CABINET DETAILS

**DOOR SCHEDULE**

- 1 PR. 3'-0" x 7'-4" EXTERIOR METAL / GLASS DOORS. STORE FRONT SYSTEM.
- 2 3'-0" x 7'-0" EXTERIOR METAL DOORS W/ PANIC DEVICE
- 3 3'-0" x 7'-0" INTERIOR WOOD DOOR
- 4 3'-0" x 7'-0" INTERIOR WOOD DOOR 1 HR. RATED DOOR AND FRAME.
- 5 PR. 3'-0" x 7'-0" INTERIOR WOOD DOORS 1 HR. RATED DOOR AND FRAME.
- 6 4'-0" x 7'-0" WOOD CASED OPNG.

**WINDOW SCHEDULE**

- A 7'-5" x 3'-0" ALUMINUM STOREFRONT
- B 2- 3'-0" x 4'-0" ALUMINUM FRAME WINDOWS.
- C 3'-0" x 4'-0" ALUMINUM FRAME WINDOWS.
- D 6'-0" x 4'-0" ALUMINUM FRAME VISION PANEL

NEW OFFICE / WAREHOUSE  
AMERICAN TRADESHOW SERVICES  
LOTS 4 & 5, NORTHSORE COMMERCIAL PARK  
ST. TAMMANY PARISH, LOUISIANA

RATLIFF ARCHITECTS  
814 MARINERS PLAZA DRIVE  
MANDEVILLE, LOUISIANA  
(985) 626-5236

JULY 30, 2007  
JOB # 03-07

SHEET:

**A-3**

3 OF 10