

LEGACY GMC

MILLWORK SCHEDULE

CODE	ITEM	MANUFACTURER	PRODUCT	FINISHES	DIMENSIONS	LOCATION	DETAILS	ARCHITECTURAL REFERENCE
M1	CONCIERGE DESK	GLOBAL COMMERCIAL FURNISHINGS	CONCIERGE DESK	LEGS: SLATE TRIM & REVEALS: ALU MEDIUM COUNTER TOP: CAMBRIA KIRKSTEAD	H: 42" W: 120" D: 36"	CONCIERGE	Approx. size: 120" wide x 36" deep x 42" tall; Table Legs: PL2 Pionite #SG228 'Slate' Suede w/MB2: Chemetal #353 'Alu Medium' Trim/Reveals; Modesty Panel: PL2 Pionite #SG228 'Slate' Suede; Support Apron w/Brackets & Cleats; Countertop: SS2: Cambria Quartz 2cm 'Kirkstead' Signature Series;	4/A5.1 5 /A5.1
M2	CONCIERGE WALL	GLOBAL COMMERCIAL FURNISHINGS	CONCIERGE WALL	PANELS: OLMO MONTANO ACCENTS: SATIN SILVER ALUMINUM ACCENTS: WD1 WALNUTVENEER	H: 120" W: 144" D: 8"	CONCIERGE	Approx. size: 144" wide x 8" deep x 120" tall; Wall Structure: Front Side: Plant-On Panels: Abet Lamina #639 'Olmo Montano' Grainwood Finish w/MF1 Chemetal #909 Satin Silver Aluminum Reveals & Back Side: WD1 Walnut Veneer w/Trim; 2 Sides Inset TV Structure & Frame: Abet Lamina #639 'Olmo Montano' Grainwood Finish & WD1 Walnut Veneer; Support Steel Tubes w/Steel Plate; Toe Kick: MF1 Chemetal #909 Satin Silver Aluminum - (Signage By Others)	3/A5.1 18 /A5.1
M3	GMC LIFESTYLE WALL	GLOBAL COMMERCIAL FURNISHINGS	GMC LIFESTYLE WALL	PANELS: OLMO MONTANO ACCENTS: SATIN SILVER ALUMINUM	H: 120" W: 123" D: 8"	GMC LIFESTYLE	Approx. size: 123" wide x 8" deep x 120" tall; Wall Structure: Plant-On Panels: G-MW1: McNichols Slotted perforated Panel 1/8" x 1" Slotted Round end Slot Brushed Finish w/MF1 Chemetal #909 Satin Silver Aluminum Reveals; Inset TV Structure & Frame: Abet Lamina #639 'Olmo Montano' Grainwood Finish; Support Steel Tubes w/Steel Plate; Toe Kick: MF1 Chemetal #909 Satin Silver Aluminum - (Signage By Others)	15/A5.1 17 /A5.1

M5	MEDIA WALL	GLOBAL COMMERCIAL FURNISHINGS	MEDIA WALL	PANELS: OLMO MONTANO ACCENTS: SATIN SILVER ALUMINUM	H: 99" W: 96" D: 6"	CUSTOMER LOUNGE	Approx. size: 96" wide x 6" deep x 99" tall; Wall Structure: Support Structure: Blocking, Substrate & MF1 Chemetal #909 Satin Silver Aluminum Trim; Inset TV Structure & Frame; Finish Face Panels: PL3 Abet Lamina #639 'Olmo Montano' Grainwood Finish Over Substrate; Toe Kick: MF1 Chemetal #909 Satin Silver Aluminum	7/A5.1
M6	REFRESHMENTS COUNTER	GLOBAL COMMERCIAL FURNISHINGS	REFRESHMENTS COUNTER	COUNTERTOP: CAMBRIA FIELDSTONE CABINETS: OLMO MONTANO	H: 34" W: 251" D: 25"	CUSTOMER WORK AREA	Approx. size: 251" wide x 25" deep x 34" tall; Cabinets, Panels: PL3 Abet Lamina #639 'Olmo Montano' Grainwood Finish; Support Apron w/Brackets & Cleats; Countertop: SS1: Cambria Quartz 'Fieldstone' Signature Series; Includes: Upgraded Pulls, Self Close Hardware, Levelers - (Sink, Fixtures by Others)	8/A5.1 13 /A5.1
M10	SERVICE WRITER DESK	GLOBAL COMMERCIAL FURNISHINGS	SERVICE WRITER DESK	COUNTERTOPS: ANGEL WHITE LEGS: SILVER METALLIC	H: 40" W: 66" D: 45"	SERVICE WRITERS	Approx. Size: 66" wide x 45" deep x 40" tall; Countertop: PL1 Pionite #SW826-VE 'Angel White'; Silver Metallic Support Leg; Includes: Countertop Support @ Credenza	6/A5.1 14 /A5.1
M11	SERVIE WITER CREDENZA	GLOBAL COMMERCIAL FURNISHINGS	SERVIE WITER CREDENZA	COUNTERTOPS: ANGEL WHITE PANELS: OLMO MONTANO ACCENTS: SATIN SILVER ALUMINUM	H: 30" W: 189" D: 25"	SERVICE WRITERS	Approx. Size: 189" wide x 25" deep x 30" tall; File Cabinet, Panels: PL3 Abet Lamina #639 'Olmo Montano' Grainwood Finish; Countertop: PL1 Pionite #SW826-VE 'Angel White'; Back Wall Panels: PL1: Pionite #SW826-VE 'Angel White' & MB-1 Chemetal #909 Satin Silver Aluminum Panels & Trim; Inset TV Structure & Frame; Toe Kick: MB1: Chemetal #909 'Satin Silver Aluminum'; Includes: Upgraded Pulls, Self Close Hardware, Levelers	6/A5.1 14 /A5.1

M12	CUSTOMER REST ROOMS	GLOBAL COMMERCIAL FURNISHINGS	CUSTOMER REST ROOMS	COUNTERTOP: CAMBRIA FIELDSTONE BASE: ANGEL WHITE	H: 34" W: 36" D: 25"	CUSTOMER REST ROOMS	Approx. size: 36" wide x 25" deep x 34" tall; Vanity Base: PL1: Pionite #SW826-VE 'Angel White'; Countertop: SS1: Cambria Quartz 'Fieldstone' Signature Series; Toe Kick: MF1 Chemetal #909 Satin Silver Aluminum; Includes: Upgraded Pulls, Self Close Hardware, Levelers: - (Elevation Shows Wall Mount Sink - Adjustments Will Be Necessary)	11/A5.1 12 /A5.1
M13	RETAIL PARTS COUNTER	GLOBAL COMMERCIAL FURNISHINGS	RETAIL PARTS COUNTER	COUNTERTOPS: ANGEL WHITE PANELS: OLMO MONTANO REVEALS: SATIN SILVER ALUMINUM	H: 42" W: 122" D: 32"	RETAIL PARTS COUNTER	Approx. size: 122" wide x 32" deep x 42" tall; Half-wall: PL3 Abet Laminal #639 'Olmo Montano' Grainwood Finish w/MF1 Chemetal #909 Satin Silver Aluminum Reveals; Cabinets: PL3 Abet Laminal #639 'Olmo Montano' Grainwood Finish; Countertop: PL1 Pionite #SW826-VE 'Angel White'; Toe Kick: MF1 Chemetal #909 Satin Silver Aluminum; Includes: Upgraded Pulls, Self Close Hardware, Levelers	9/A5.1 19 /A5.1