



1 SITE PLAN
SCALE: 1" = 20'-0"

SITE LIGHTING
EXTERIOR LIGHTING SHALL BE SHADED OR INWARDLY DIRECTED IN SUCH A MANNER SO THAT NO DIRECT LIGHTING OR GLARE BE CAST BEYOND THE PROPERTY LINE. THE INTENSITY OF SUCH LIGHTING SHALL NOT EXCEED ONE FOOT CANDLE AS MEASURED AT THE ABUTTING PROPERTY LINE. (N/A FOR THIS PARTICULAR JOB)

SITE PLAN NOTES
1. ROOFING MATERIAL: METAL ROOFING PANEL
2. SIDING MATERIAL: CONVENTIONAL STUCCO VENEER & METAL PANELS.
3. UTILITIES: ALL UTILITIES SHALL BE PLACED UNDERGROUND

OFFICE/WAREHOUSE PARKING REQUIREMENTS
1. SPACE PER EACH 700 SQ. FT. OF STORAGE AREA PLUS 1 SPACE PER EACH 400 SQ. FT. OF OFFICE, SALES OR OTHER SPACE TO BE USED BY VISITORS, CUSTOMERS OR SALESMEN.
3,750 SQ. FT. BUILDING TOTAL
1,250 SQ. FT. WAREHOUSE = 2 PARKING SPACES
2,500 SQ. FT. OF SALES = 7 PARKING SPACES
TOTAL PARKING PROVIDED = 9 INCLUDING 1 HANDICAP

DAMMON ENGINEERING, INC.
Architects & Engineers
www.dammonengineering.com
Chief Architect: Kevin J. Kinchen, NCARB
Chief Engineer: Brian Mistich, PE
554 Old Spanish Trail
Slidell, LA 70458
PH: 985.649.5832
F: 985.641.5950

REVISIONS		DATE
#	DESCRIPTION	

NEW CONSTRUCTION FOR
SKENET DORMAZO MATRIMONIO # FURNITURAS
U.S. HWY 190
SLIDELL, LOUISIANA
JOB No: [###] DATE: 11-07-14
DRAWN BY: JTL CHECKED BY: CKD

SHEET NO: **C1**
DRAWING NUMBER:
CO. #