

Bethancourt A/C & Heating LLC

238 Goldenwood Drive
 Slidell, LA 70461
 (985) 290-0637
 bethancourtac@gmail.com



Estimate

ADDRESS

Gray Dragon

ESTIMATE # 1225

DATE 10/19/2021

EXPIRATION DATE 11/19/2021

ACTIVITY	QTY	RATE	AMOUNT
Service Remove and haul away old duct work from job site	1	0.00	0.00
Material 5 ton heat pump 3 phase 14 seer condenser unit HEIL refrigerant 410a	2	0.00	0.00
Material 5 Air handler unit	2	0.00	0.00
Material 10 kw heat kit 3 phase	2	0.00	0.00
Material Drain pan and safety shut off switches	2	0.00	0.00
Material 4 foot metal Plenum	2	0.00	0.00
Material Filter frame	2	0.00	0.00
Material Hard metal pipe trunk line wrapped with bubble wrap insulation and duct sealed All new supply collars with dampers 8 inch flex ducts ran to office	2	0.00	0.00
Material 10 x 6 one-way curved blade aluminum grill	12	0.00	0.00
Material New 18/8 thermostat wire going down wall to thermostat	2	0.00	0.00
Heat pump thermostat			
Material 7/8 copper line set, 3/8 copper line, rubber Tex, and 18/5 stat wire. Ran from inside air handler unit to outside condenser unit.	2	0.00	0.00
Material PVC drain line and rubber Tex, PVC emergency drain line ran outside	2	0.00	0.00
Material Metal mastic tape, duct sealant , copper fittings, PVC fittings,Air handler blocks, Un-strut, all thread rods, wall hangers, wire	2	0.00	0.00

ACTIVITY	QTY	RATE	AMOUNT
connectors... Etc.			
Material	1	0.00	0.00
Material lift rental			
Labor	1	0.00	0.00
Three technicians one week			
Total Job	1	34,400.00	34,400.00
Total job			

Install new 5 ton 14 seer heat pump 3 phase condenser unit, 5 ton Air handler unit, 3 phase 10KW heat kit with breaker, 4 foot metal Plenum, Hard pipe duct work with bubble wrap insulation and duct sealed, drain pan with safety shut off switches, and Filter frame. R6 flex duct work ran to office with 24x24 layin grills. Thermostat wire, and copper line set.

TOTAL

\$34,400.00

- 1 year parts warranty
- 5 year compressor warranty
- 1 year labor warranty

Accepted By

Accepted Date