

General Information



Presentation.	100 lb (sack)	50 lb (sack)	Big Bag	Bulk
Availability.	OK	N/A	N/A	OK
Code	3P-100	N/A	N/A	3P-BB
Qualities Available*.	P1	N/A	N/A	P1

Color: White

Technical Information

Total Alkalinity (as Na₂O) ASTM D-1208..... 0.04%
 Bulk Density (ASTM D-1895)..... 92.92 Lb/ft³
 Moisture..... 1.00%
 Acid Insoluble..... 0.14%
 pH (ASTM D-1208)..... 10.22
 Particle Shape (Microscope)..... Geometric
 Dry Brightness (Hunter Reflectance)..... 91.26

Typical Chemical Analysis

%CaCO₃..... 98.650%
 %MgO..... 0.528%
 %SiO₂..... 0.128%
 %Al₂O₃..... 0.008%
 %Fe₂O₃..... 0.008%
 %Hg..... < 0.0001%
 %As..... < 0.0001%
 %Cd..... < 0.0001%
 %Pb..... < 0.0001%
 %Sb..... < 0.0001%
 %Bi..... < 0.0001%



Sieve Information

% Accumulated retained

Mesh #200 ≥..... 86.00%

Market Applications

Pool Plastering

*Qualities available: P1=PREMIUM 1

Calcium Carbonate is subject to normal variations related to deposits from which it is extracted.