DOOR & HARDWARE SCHEDULE

NO.	SIZE	TYPE: S. C. WOOD	TYPE: H. C. WOOD	TYPE: HOLLOW METAL	FRAME: WOOD	FRAME: HOLLOW METAL	HINGE: BUTT	HINGE: FULL-SWING	LOCK: DEADBOLT	LOCK: KEYED HANDLE	LOCK: PASSAGE	LOCK: PRIVACY	ACCESS.: THRESHOLD	ACCESS.: WEATHERSTRIP	ACCESS.: CLOSER	ACCESS.: DOOR STOP	REMARKS
1	(2)2/6x7/0	●			●		●		●	●			●	●	●		
2	3/0x7/0	●			●		●		●	●			●	●	●		
3	4/0x7/0 C.O.																CASED OPENING
4	3/0x7/0	●			●		●				●				●	●	
5	3/0x7/0	●			●		●					●				●	
6	2/0x7/0	●			●		●				●						RETURN AIR IN DOOR
7	2/0x7/0	●			●		●				●						
8	3/0x7/0	●			●			●			●					●	
9	3/0x7/0	●			●		●				●					●	
10	3/0x7/0	●			●		●				●					●	60 MIN. RATED DOOR
11	3/0x7/0	●			●		●		●	●			●	●	●		60 MIN. RATED DOOR
12	(2)3/0x7/0	●			●		●				●					●	

WINDOW SCHEDULE

	WINDOW (WIDTH x HEIGHT)	TYPE: FRAMED OPENING	FRAME: WOOD	GLASS: NONE	LITES: NONE	ACCESS.: NONE	REMARKS
A	3/0x4/0	●	●	●	●	●	SILL HT. FLUSH WITH BAR

ROOM FINISH SCHEDULE

RM. NO.	ROOM NAME	FLOOR: VCT	FLOOR: CONC. W/SEALER	FLOOR: CERAMIC TILE	BASE: VINYL BASE	BASE: CERAMIC TILE	BASE: NONE	WALL: GYP.BD. PAINTED	WALL: M. R. GYP.BD.PTD.	WALL: CERAMIC TILE	CEILING: GYP.BD. PAINTED	CEILING: 2'x4' SUSP. ACOUST.	CLG. HGT.	REMARKS
101	RECEPTION/DINING ROOM	●			●			●			●		9'-0"	
102	AHU CLOSET		●				●	●					NONE	
103	ELECTRIC CLOSET		●				●	●					NONE	
104	RESTROOM VESTIBULE	●			●			●			●		9'-0"	
105	MENS RESTROOM			●		●			●		●		9'-0"	
106	WOMENS RESTROOM			●		●			●		●		9'-0"	
107	HALL	●			●			●			●		9'-0"	
108	SPRINKLER ROOM		●				●		●				NONE	
109	AHU CLOSET		●				●	●					NONE	
110	BRIDES ROOM	●			●			●			●		9'-0"	
111	AHU CLOSET		●				●	●					NONE	
112	JANITORS CLOSET	●			●			●			●		9'-0"	
113	VENDING AREA	●			●			●			●		9'-0"	
114	KITCHEN AREA	●			●			●			●		9'-0"	
115	DUMBWAITER		●				●	●					NONE	
116	BAR AREA	●			●			●			●		9'-0"	
117	AHU CLOSET		●				●	●					NONE	
118	ELEVATOR		●				●	●					NONE	
119	ENTRY AREA	●			●			●			●		9'-0"	
120	CORRIDOR	●			●			●			●		9'-0"	
121	FOYER	●			●			●			●		9'-0"	
201	FOYER	●			●			●			●		9'-0"	
202	SUPPLIES CLOSET	●			●			●			●		9'-0"	
203	STAIRS	●			●			●			●		9'-0"	
204	RECEPTION/DINING ROOM	●			●			●			●		9'-0"	
205	AHU CLOSET		●				●	●					NONE	
206	BAR AREA	●			●			●			●		9'-0"	
207	DUMBWAITER		●				●	●					NONE	
208	KITCHEN PREP AREA	●			●			●			●		9'-0"	
209	ALCOVE	●			●			●			●		9'-0"	
210	HALL	●			●			●			●		9'-0"	
211	AHU CLOSET		●				●	●					NONE	
212	AHU CLOSET		●				●	●					NONE	
213	AHU CLOSET		●				●	●					NONE	
214	AHU CLOSET		●				●	●					NONE	
215	RESTROOM VESTIBULE	●			●			●			●		9'-0"	
216	WOMENS RESTROOM			●		●			●		●		9'-0"	
217	MENS RESTROOM			●		●			●		●		9'-0"	
218	ELECTRIC CLOSET		●				●	●					NONE	
219	AHU CLOSET		●				●	●					NONE	
220	VENDING AREA	●			●			●			●		9'-0"	
221	HALL	●			●			●			●		9'-0"	
222	BRIDES ROOM	●			●			●			●		9'-0"	

GENERAL SHEET NOTES

1. INSULATION AND INSULATION ASSEMBLIES SHALL MEET THE REQUIREMENTS OF BC 2012 SECTION I 719.
   A. CONCEALED INSULATION SHALL HAVE A FLAME SPREAD OF 0-25 AND SMOKE DEVELOPED INDEX OF 0-450. EXCEPT THAT IN COMBUSTIBLE (WOOD FRAME) CONSTRUCTION.
   B. FACING SHALL COMPLY WITH IBC 2006.
2. PROVIDE 5'x5' LANDINGS, LEVEL WITH FINISHED FLOOR, OUTSIDE EXTERIOR DOORS ON WEST SIDE OF BUILDING. THRESHOLDS SHALL BE NOT MORE THAN 1/2" IN HEIGHT AND SHALL BE BEVELED IF MORE THAT 1/4".
3. CONTRACTOR TO VERIFY ALL SITE CONDITIONS, BUILDING LOCATIONS, AND DIMENSIONS PRIOR TO CONSTRUCTION.
4. MATERIALS SHALL BE NEW AND U.L. LISTED.
5. NO WORK SHALL BE CONCEALED UNTIL APPROVED BY LOCAL INSPECTORS.
6. CONSTRUCTION SHALL COMPLY WITH ALL PARISH, STATE, AND LOCAL CODES.
7. CONTRACTOR TO GUARANTEE WORK FOR ONE YEAR.
8. CONTRACTOR SHALL FURNISH WATER AND POWER FROM EXISTING SOURCES.
9. EXTERIOR CAULKING SHALL BE THIOKAL CAULK.
10. PAINT GRADE TO SHALL BE SHERWIN WILLIAMS OR EQUIVALENT. ALL WORK TO RECEIVE 3 COATS. COLOR SELECTION BY OWNER.
11. PROVIDE CLEANUP ON A REGULAR BASIS. NO TRASH STORED IN BUILDING.
12. ALL BLANKET INSULATION SHALL HAVE A CLASS "A" (0-25) FLAME SPREAD IN COMPLIANCE WITH APPLICABLE CODE.
13. USE 6" STUDS, OR 4" STAGGERED STUDS AT ALL PLUMBING WALLS.
14. PROVIDE GALVANIZED METAL PAN WITH DRAIN AT WATER HEATER LOCATION.
15. ALL CORNERS SHALL BE PROPERLY BRACED FOR WIND LOADS. A 48" SHEATHING SHALL BE PROVIDED EVERY 20 FEET OF WALL LENGTH.
16. FLOORING SHALL BE NON-SLIP.
17. INTERIOR LOCKS ON DOORS IN MEANS OF EGRESS SHALL NOT REQUIRE THE USE OF A KEY, SPECIAL KNOWLEDGE, OR SPECIAL DEVICE TO OPEN IN THE DIRECTION OF EGRESS. ALL DOORS SHALL HAVE LEVER TYPE HANDLES.
18. INTERIOR WALLS AND CEILINGS SHALL HAVE A FLAME SPREAD OF 0-200 AND A SMOKE DEVELOPMENT RATING OF 0-450.
18. ALL WORK SHALL COMPLY WITH THE LATEST EDITION OF ALL LOCAL, STATE, AND NATIONAL CODES COVERING THE TYPE OF WORK BEING PERFORMED.
19. PROVIDE PORTABLE FIRE EXTINGUISHERS IN ACCORDANCE WITH NFPA 101. SEE APPENDIX "E" OF NFPA 101 FOR DISTRIBUTION OF EXTINGUISHERS.
20. ALL FIRE WALLS SHALL EXTEND TIGHT TO ROOF DECK AND BE SEALED WITH AN APPROVED FIRE CAULK.
21. ALL ELECTRICAL, MECHANICAL, AND PLUMBING MATERIALS PENETRATING FIRE WALLS SHALL BE FIRE CAULKED. (PENETRATIONS THROUGH RATED CONSTRUCTION SHALL BE SEALED WITH A MATERIAL CAPABLE OF PREVENTING THE PASSAGE OF FLAMES AND HOT GASES WHEN TESTED IN ACCORDANCE WITH ASTM-E814.)
22. SERVICE COUNTER SHALL HAVE A HCP ACCESSIBLE WRITING SURFACE, MAX. 36" FROM F.F. (ADAAG MANUAL 1998, PG 135)
23. CONTRACTOR SHALL VERIFY AND COORDINATE THE CLEAR DIMENSIONS REQUIRED FOR ALL OWNER FURNISHED EQUIPMENT (OFE) WHICH IS LOCATED WITHIN, OR ADJACENT TO, ANY PIECE OF COUNTER TOP OR CABINETWORK/CASEWORK. SEE THE FLOOR PLANS FOR LOCATIONS OF OFE.

465406
REVIEWED FOR
STATE FIRE MARSHAL
AS PER REVIEW LETTER
BY: WILLIAM D. JONES, ARCHITECT, CBO

DAMMON ENGINEERING, INC.
Architects & Engineers
Chief Architect: Kevin J. Kinchen, NCARB
Chief Engineer: Brian Mistich, PE
554 Old Spanish Trail
Slidell, LA 70458
www.dammonengineering.com
info@dammonengineering.com
PH: 985.649.5832
F: 985.641.5950

REVISIONS

#	DESCRIPTION	DATE

SEAL: STATE OF LOUISIANA REGISTERED ARCHITECT
3/11/15

RECEPTION HALL RENOVATION FOR:
BEV, INCORPORATED
211 COUSIN STREET
SLIDELL, LOUISIANA 70458

JOB No: 2220	DATE: MARCH 03-2015
DRAWN BY: KJK	CHECKED BY: CKD

The above drawings and specifications, designs and arrangements represented thereby are and shall remain the property of Dammon Engineering, and no part thereof shall be copied, disclosed to others, or used in connection with any work or project other than the specific project for which the have been prepared and developed without written consent of Dammon Engineering. Visual contact with these drawings or specifications shall constitute conclusive evidence of acceptance of these restrictions.

SHEET TITLE:
SCHEDULES AND NOTES

DRAWING NUMBER:
A3