



1 POWER FLOOR PLAN  
SCALE: 1/8"=1'-0"

GENERAL ELECTRICAL NOTES:

- COORDINATE WITH OWNER, LOCATIONS OF ALL TELEPHONE AND ELECTRICAL SERVICE STUB-UPS INSIDE OF BUILDING.
- ALL CONDUIT SHALL BE MIN 1/2" DIAMETER UNLESS OTHERWISE NOTED.
- VERIFY EXACT LOCATION OF ALL OUTLETS AND FIELD COORDINATE PRIOR TO ANY WORK.
- PROVIDE JUNCTION BOX AND 3/4" CONDUIT WITH PULLWIRE STUBBED ABOVE ACCESSIBLE CEILING FOR ALL DATA AND COMMUNICATION DEVICE LOCATIONS. VERIFY EXACT LOCATIONS WITH SPECIFIC TENANTS PRIOR TO ROUGH-IN.
- LOW VOLTAGE WIRING FOR THERMOSTAT CONTROLS IS BY THE MECHANICAL CONTRACTOR. ELECTRICAL CONTRACTOR SHALL PROVIDE CONDUIT WITH PULL WIRES AND BACK BOXES AS NECESSARY FOR ROUGH-IN OF THERMOSTATS. COORDINATE LOCATIONS WITH MECHANICAL CONTRACTOR PRIOR TO ROUGH-IN.
- ADDITIONAL FIRE ALARM NOTIFICATION APPLIANCES WILL BE PROVIDED UNDER INDIVIDUAL TENANT FINISH CONTRACTS AS NECESSARY.
- DUCT SMOKE DETECTORS SHALL TRANSMIT A SUPERVISORY SIGNAL TO THE FIRE ALARM CONTROL PANEL AS REQUIRED BY LOCAL AHJ.

ELECTRICAL PLAN NOTES:

- LOW VOLTAGE DUCT SMOKE DETECTOR FURNISHED BY MECHANICAL CONTRACTOR. WIRE DUCT SMOKE DETECTOR FOR SHUT-DOWN OF RTU. PROVIDE SHUT-DOWN PER INDIVIDUAL TENANT CRITERIA. PROVIDE LOW VOLTAGE WIRING TO REMOTE INDICATOR LIGHTS, REMOTE TROUBLE LIGHTS, AND TEST/RE-SET STATIONS MOUNTED IN CEILING. IN UNFINISHED SPACES, TEMPORARILY MOUNT DEVICES AT ROOF JOISTS. LEAVE ENOUGH WIRE TO ALLOW PERMANENT MOUNTING IN CEILING BY TENANT.
- CEILING MOUNT RECEPTACLE NEAR WINDOWS FOR SHOW WINDOW LIGHTING/DISPLAY.
- PROVIDE FUSED DISCONNECT SWITCH, SIZE INDICATED ON PLANS.
- WIRE RECEPTACLE FURNISHED WITH UNIT.
- PROVIDE 2 POLE 20 AMP. TOGGLE SWITCH AND POWER CONNECTION FOR INSTANTANEOUS WATER HEATER. REFER TO PLUMBING SHEETS.
- PROVIDE 1-1/4" CONDUIT WITH PULL STRING FROM PHONE BOARD LOCATION IN TENANT SPACE, ABOVE CEILING AND TERMINATED AT THE MAIN DEMARK BOARD IN SPRINKLER ROOM.
- JUNCTION BOX FOR STORE FRONT SIGNAGE. VERIFY LOCATION. PROVIDE 3/4" CONDUIT STUBBED THRU WALL AS REQUIRED. PROVIDE LOCAL DISCONNECT SWITCH AS REQUIRED BY NEC IF NOT FURNISHED WITH SIGN.
- HOMERUN CIRCUIT(S) THROUGH CONTACTOR CONTROLLED BY PHOTOCELL AND/OR TIME SWITCH. REFER TO CONTACTOR SCHEDULE FOR CONTROL SEQUENCE.
- FUTURE JUNCTION BOX FOR STORE SIGNAGE.
- TENANT PROVIDED WASHER AND DRYER.
- TENANT PROVIDED NAIL AND PEDICURE STATIONS.

REVISION #1	REVISION #2	REVISION #3	DATE	DESCRIPTION	BY
1					
2					

**DDG DUPLANTIS DESIGN GROUP, PC**  
*Respect • Integrity • Client Satisfaction • Excellence*  
 HOUSTON, TEXAS  
 THIBODAUX, LOUISIANA  
 CIVIL ENGINEERING • SITE DEVELOPMENT • LAND PLANNING • PUBLIC WORKS • ARCHITECTURE  
 314 East Bayou Road  
 Thibodaux, Louisiana 70301  
 Phone: 985-471-0290  
 Fax: 985-471-1809

STATE OF LOUISIANA  
 REGISTERED PROFESSIONAL ENGINEER  
 CRAG R. LANSAM  
 REG. NO. 5564  
 ELECTRICAL ENGINEERING  
 SIGNATURE: \_\_\_\_\_ DATE: \_\_\_\_\_  
 STAMP: 3-5-08

PROPOSED RETAIL DEVELOPMENT  
 CITY OF BOULTE  
 ST. CHARLES PARISH, LOUISIANA  
 FOR THE SPECTRA GROUP, INC.  
 MEMPHIS, TENNESSEE

DRAWN: FLS  
 CHECKED: DWL  
 DATE: 8/18/07  
 SCALE: AS NOTED ON DWG  
 PROJECT NO.: 0750001106  
 FILE: 0650001106E4.DWG  
 SHEET: E4

**HENDERSON ENGINEERS**  
 8375 LENEVA DRIVE  
 LENOVA, KS 66214  
 TEL 913 742 5000 FAX 913 742 5001  
 www.hel-eng.com  
 0750001106

Program: p:\jpl\0750001106 Spectra Retail Center - Boule - LA\0650001106E4.dwg, PLOT: 3/20/08 2:04:13 PM, f:\mva\msh-jpl\mk, 11