



Ordering Information:

Cat. No.	Diameter	Extension	Finish	Voltage	Lamps (by others)	
6562BK	10 1/2"	5 1/4"	Black	120V	(1) 75W a19 Max.	
6561BZ	10 1/2"	5 1/4"	Bronze	120V	(1) 75W a19 Max.	
6560WH	10 1/2"	5 1/4"	White	120V	(1) 75W a19 Max.	
6568BK	10 1/2"	5 1/4"	Black	120V	(2) 9W Twin 2-pin (G23 base)	General Electric Osram/Sylvania Philips F9BX/SPX/* CF90S/* PLS9W/* *Manufactures color temperature designation.
6567BZ	10 1/2"	5 1/4"	Bronze	120V	(2) 9W Twin 2-pin (G23 base)	
6566WH	10 1/2"	5 1/4"	White	120V	(2) 9W Twin 2-pin (G23 base)	

Features

- 1. Diffuser:** Injection molder polycarbonate.
- 2. Screw:** Diffuser removal can be made tamper proof.
- 3. Lamp Shield:** Directs light efficiently through diffuser.
- 4. Lamp:** See Lamps.
- 5. Ballast:** See Electrical/Ballast.

Electrical/Ballast

	9W NPF 120V
Total Input Watts	20
Max. Line Current (amps)	.36
Ballast Factor	.90
THD	< 20%
Min. Starting Temperature	-4°C (-25°F)

Mounting

Wall Mount only to standard 4" octagonal outlet box.

Labels

UL Listed. Suitable for Wet Locations.

Job Information

Type:

Job Name:

Cat. No.:

Lamp(s):

Notes: