



1 POWER LAYOUT PLAN - THIRD FLOOR  
 A 203 SCALE: 1/8"=1'-0"

GENERAL NOTES:

- GENERAL CONTRACTOR TO COORDINATE A PRECONSTRUCTION SITE WALK THROUGH MEETING TO FIELD VERIFY OUTLET AND FIXTURE LOCATIONS AND TYPES WITH ARCHITECT, OWNER AND ELECTRICAL SUBCONTRACTOR PRIOR TO COMMENCING ELECTRICAL WORK AND PURCHASE OF FIXTURES.
- VERIFY POWER REQUIREMENTS OF ALL APPLIANCES WITH SELECTED APPLIANCE MANUFACTURER.
- RECESSED LIGHTING FIXTURES RECESSED INTO INSULATED CEILINGS MUST BE APPROVED FOR ZERO CLEARANCE INSULATION COVER (IC) BY UNDERWRITER LABORATORIES OR OTHER TESTING/RATING LABORATORIES RECOGNIZED BY THE INTERNATIONAL CONFERENCE OF BUILDING OFFICIALS (ICBO).
- EXHAUST FAN TO BE CAPABLE OF PROVIDING 5 FULL VOLUME AIR CHANGES PER HOUR.
- WIRING DEVICES: SWITCHES AND CONVENIENCE OUTLETS SHALL BE "LEVITON" SPEC. GRADE, COLOR: WHITE, NOT IVORY. INSTALL AT HEIGHTS REQUIRED BY CURRENT CODE, U.N.O.
- EXTENT: COMPLETE WIRING INSTALLATION FOR POWER, LIGHTING, SIGNAL SYSTEM AND TELEPHONE. CODES: ALL WIRING AND MATERIAL SHALL BE IN FULL ACCORDANCE WITH NATIONAL, STATE AND LOCAL ELECTRICAL CODES INCLUDING TITLE 24.
- OUTLET HEIGHTS INDICATED ON PLAN ARE TO CENTER OF FIXTURE AND HEIGHT ABOVE THE FINISHED FLOOR ELEVATION, VERIFY CODE COMPLIANCE WITH BUILDING INSPECTOR.
- OUTLETS AT ALL WADSWORTH DESIGN CUTTING STATIONS SHOULD BE GREY WITH BRUSHED ALUMINUM COVER PLATES.
- ALL COVER PLATES AT FLOOR BOX LOCATIONS SHALL HAVE STAINLESS STEEL COVER PLATES.

- ALL OUTLETS IN STAINLESS STEEL TO BE GREY WITH STAINLESS STEEL COVER PLATES.
- ALL OUTLETS/SWITCHES IN SLATE WALLS TO BE BLACK WITH BLACK COVER PLATES.

POWER LEGEND:

- WALL MOUNTED FLUSH J-BOX
- DUPLEX CONVENIENCE OUTLET
- GFI RECEPTACLE
- EXTERIOR WALL MOUNTED WATER RESISTANT CONVENIENCE OUTLET, PROVIDE GROUND FAULT INDICATOR (GFI), TYPICAL.
- HALF SWITCHED CONVENIENCE OUTLET
- FOURPLEX CONVENIENCE OUTLET
- FLOOR MOUNTED DUPLEX CONVENIENCE OUTLET
- FLOOR MOUNTED FOURPLEX CONVENIENCE OUTLET
- FLUSH MOUNTED RECESSED JUNCTION BOX
- CEILING MOUNTED OUTLET
- DATA CONNECTION, VERIFY WITH AV CONSULTANT AND COMPUTER, PHONE PROVIDER.

SPECIALTY NOTES:

- CEILING RECEPTACLE PROVIDED WITH AV PROJECTOR CEILING MOUNT PANEL.
- PROVIDE CABLE AND QUAD RECEPTACLE FOR FLATSREEN TELEVISION, COORDINATE MOUNTING HEIGHT WITH A.V. CONSULTANT
- AV RACK FOR EQUIPMENT LOCATED IN CLOSET, COORDINATE EXACT POWER REQUIREMENT AND LOCATION WITH AV CONSULTANT.
- OWNER PROVIDED WASHER AND DRYER, VERIFY EXACT POWER, GAS, AND PLUMBING REQUIREMENTS WITH MANUFACTURER OF SELECTED UNITS.
- VERIFY POWER AND DATA REQUIREMENTS FOR TIME CLOCK, COORDINATE LOCATION WITH OWNER.
- PROVIDE 4 DUPLEX OUTLETS, EACH WITH A DEDICATED CIRCUIT FOR 4 MICROWAVES. COORDINATE HEIGHTS WITH WALL SHELVES FOR MICROWAVES, REFERENCE 07/AS.2 FOR DETAILS.
- PROVIDE POWER AND NETWORK CONNECTION FOR OWNER PROVIDED COPIER/PRINTER, VERIFY EQUIPMENT WITH OWNER.
- PROVIDE 2 DUPLEX OUTLETS, EACH WITH A DEDICATED CIRCUIT FOR 2 MICROWAVES. COORDINATE HEIGHTS WITH WALL SHELVES FOR MICROWAVES.  
 (2) AT 63" AFF AND (2) AT 78" AFF VERIFY WITH WADSWORTH DESIGN.
- PROVIDE POWER AND NETWORK CONNECTION FOR OWNER PROVIDED COMPUTERS AND POINT OF SALE EQUIPMENT, VERIFY EQUIPMENT WITH OWNER. VERIFY EXACT LOCATION WITH WADSWORTH DESIGN. (RECEPTACLES INSTALLED BY O.C. INSIDE DESK)
- PROVIDE POWER FOR OWNER PROVIDED REFRIDGERATORS AND VENDING MACHINES; VERIFY EQUIPMENT WITH OWNER.
- POWER FOR EXTERIOR BACK-LIT SIGNAGE, REFER TO EXTERIOR ELEVATIONS FOR DETAILS.
- GAS HOT WATER HEATERS AND RECIRCULATING PUMP - REFER TO MEP DRAWINGS AND OUT SHEETS FOR REQUIREMENTS.
- ELECTRIC HAND DRYER, REFER TO SHEET A401 AND A402 FOR DETAILS.
- WATER WALL - VERIFY WATER SUPPLY, DRAIN & POWER REQUIREMENTS WITH MANUFACTURER.
- PERICURE STATIONS, PROVIDE GFI WALL OUTLET WITH DEDICATED CIRCUIT FOR EACH UNIT REFER TO OUT SHEETS FOR DETAILS.
- WALL MOUNTED TOOL BAR BY WADSWORTH DESIGN, 3 OUTLETS WITH DEDICATED CIRCUITS - REG.
- OWNER PROVIDED SKIN-BED AND MACHINES, VERIFY POWER REQ. WITH OUT SHEETS, PROVIDE DEDICATED CIRCUIT PER BED.
- PROVIDE POWER FOR OWNER PROVIDED BISHWASHER AS REQUIRED.
- PROVIDE POWER FOR MANNEQUIN DRYER CABINET; VERIFY EQUIPMENT WITH OWNER.
- PROVIDE POWER AND DATA FOR LAPTOP OVER RIDE, VERIFY EXACT REQUIREMENTS AND LOCATION WITH A/V CONSULTANT. (LOCATE DIRECTLY UNDER LCD SCREEN)

REVIEWED FOR STATE FIRE MARSHAL AS PER REVIEW LETTER BY JESU RAMIREZ  
 375133

PERMIT ISSUE SET: 12.30.09

ARCHITECTS OF RECORD:  
  
 BRADFORD J. DUDLEY  
 345 THIRD STREET  
 LAGUNA BEACH, CALIFORNIA 92651  
 T: 949.376.3076 F: 949.376.3078

**PAUL MITCHELL**  
 PARTNER SCHOOL  
  
 METAIRIE, LA  
  
 3321 HESSMER AVENUE  
 METAIRIE, LA 70002

CLIENT:  
  
 MARK AND LISA PALERMO

PROFESSIONAL SEAL:  
  
  
 SIGNATURE: [Signature] DATE: 12-24-2009

SUBMISSION	DATE
CONCEPT PLAN	12.01.09
CONSULTANT COORDINATION	12.14.09
PERMIT ISSUE SET	12.30.09

PROJECT NO: 0921  
  
 SCALE:

**POWER LAYOUT PLAN**  
**THIRD FLOOR**  
  
 A 203