



1 POWER LAYOUT PLAN - SECOND FLOOR
 A 202 SCALE: 1/8"=1'-0"

GENERAL NOTES:

1. GENERAL CONTRACTOR TO COORDINATE A PRECONSTRUCTION SITE WALK THROUGH MEETING TO FIELD VERIFY ALL POWER AND DATA REQUIREMENTS AND VERIFY ALL ELECTRICAL AND NETWORKING WORK AND PURCHASE OF FIXTURES.
2. VERIFY POWER REQUIREMENTS OF ALL APPLIANCES WITH SELECTED APPLIANCE MANUFACTURER.
3. RECESSED LIGHTING FIXTURES RECESSED INTO INSULATED CEILINGS MUST BE APPROVED FOR ZERO CLEARANCE INSULATION COVER (IC) BY UNDERWRITER LABORATORIES OR OTHER TESTING/RATING LABORATORIES OF BUILDING OFFICIALS (CBO).
4. EXHAUST FAN TO BE CAPABLE OF PROVIDING 5 FULL VOLUME AIR CHANGES PER HOUR.
5. WIRING DEVICES: SWITCHES, SPEC. GRADE, COLOR: WHITE, NOT ivory, INSTALL AT HEIGHTS REQUIRED BY CURRENT CODE, U.N.O.
6. EXTENT: COMPLETE WIRING INSTALLATION FOR ALL ROOMS, INCLUDING ALL WIRING AND TELEPHONE CODES. ALL WIRING AND MATERIAL SHALL BE IN FULL ACCORDANCE WITH NATIONAL, STATE AND LOCAL ELECTRICAL CODES INCLUDING TITLE 24.
7. OUTLET HEIGHTS INDICATED ON PLAN ARE TO CENTER OF FIXTURE AND HEIGHT ABOVE THE FINISHED FLOOR ELEVATION. VERIFY CODE COMPLIANCE WITH BUILDING INSPECTOR.
8. OUTLETS AT ALL WADSWORTH DESIGN CUTTING STATIONS SHOULD BE GREY WITH BRUSHED ALUMINUM COVER PLATES AT FLOOR BOX LOCATIONS.
9. ALL COVER PLATES AT FLOOR BOX LOCATIONS SHALL HAVE STAINLESS STEEL COVER PLATES.

POWER LEGEND:

- HJ WALL MOUNTED FLUSH J-BOX
- DUPLX CONVENIENCE OUTLET
- GROUND FAULT INDICATOR (GFI) RECEPTICAL EXTERIOR WALL MOUNTED WATER RESISTANT CONVENIENCE OUTLET, PROVIDE GROUND FAULT INDICATOR (GFI), TYPICAL.
- HALF SWITCHED CONVENIENCE OUTLET
- FOURPLEX CONVENIENCE OUTLET
- FLOOR MOUNTED DUPLX CONVENIENCE OUTLET
- FLOOR MOUNTED FOURPLEX CONVENIENCE OUTLET
- (4) CIRCUITS AT EACH STYLING STATION STUBBED THROUGH CONDUIT IN THE FLOOR, INSTALL FOURPLEX RECEPTICAL IN PRE-INSTALLED JUNCTION BOX IN STYLING STATION
- FLUSH MOUNTED RECESSED JUNCTION BOX
- CEILING MOUNTED OUTLET
- DATA CONNECTION, VERIFY WITH AV CONSULTANT AND COMPUTER, PHONE PROVIDER.

SPECIALTY NOTES:

1. CEILING RECEPTICAL PROVIDED WITH AV PROJECTOR, CEILING MOUNT PANEL.
2. PROVIDE CABLE AND QUAD RECEPTICAL FOR FLATS/SCREEN TELEVISION, COORDINATE MOUNTING HEIGHT WITH A.V. CONSULTANT
3. AV RACK FOR EQUIPMENT LOCATED IN CLOSET, COORDINATE EXACT POWER REQUIREMENT AND LOCATION WITH AV CONSULTANT.
4. OWNER PROVIDED WASHER AND DRYER, VERIFY EXACT POWER, GAS, AND PLUMBING REQUIREMENTS WITH MANUFACTURER OF SELECTED UNITS.
5. VERIFY POWER AND DATA REQUIREMENTS FOR TIME CLOCK, COORDINATE LOCATION WITH OWNER.
6. PROVIDE 4 DUPLEX OUTLETS, EACH WITH A DEDICATED CIRCUIT FOR 2 MICROWAVES, COORDINATE HEIGHTS WITH WALL SHELVES FOR MICROWAVES.
7. PROVIDE POWER AND NETWORK CONNECTION FOR OWNER PROVIDED COPIER/PRINTER, VERIFY EQUIPMENT WITH OWNER.
8. PROVIDE 2 DUPLEX OUTLETS, EACH WITH A DEDICATED CIRCUIT FOR 2 MICROWAVES, COORDINATE HEIGHTS WITH WALL SHELVES FOR MICROWAVES.
9. PROVIDE POWER AND NETWORK CONNECTION FOR ALL EQUIPMENT WITH OWNERS AND POINT OF SALE EQUIPMENT, VERIFY REQUIREMENTS WITH OWNER.
10. PROVIDE POWER FOR OWNER PROVIDED REFRIGERATORS AND VENDING MACHINES, VERIFY EQUIPMENT WITH OWNER.
11. PROVIDE POWER FOR EXTENSION CORDS, REFER TO EXTERIOR ELEVATIONS FOR DETAILS.
12. GAS HOT WATER HEATERS AND RECIRCULATING PUMP, REFER TO MEP DRAWINGS AND CUT SHEETS FOR REQUIREMENTS.
13. ELECTRIC HAND DRYER, REFER TO SHEET A401 AND A402 FOR DETAILS.
14. WATER HEATER, VERIFY WATER SUPPLY, DRAINAGE, AND VENTING REQUIREMENTS WITH MANUFACTURER.
15. REDUCE STATIONS, PROVIDE GFI WALL OUTLET WITH OUT SHEETS FOR EACH UNIT, REFER TO OUT SHEETS FOR DETAILS.
16. WALL MOUNTED TOOL BAR BY WADSWORTH DESIGN, 3 OUTLETS WITH DEDICATED CIRCUITS REQ.
17. OWNER PROVIDED SINK, BID, AND MACHINES, VERIFY POWER REQ. WITH CUT SHEETS, PROVIDE DEDICATED CIRCUIT PER REQ.
18. PROVIDE POWER FOR OWNER PROVIDED DISHWASHER AS REQUIRED.
19. PROVIDE POWER FOR MANNEQUIN, GREY CABLE, REFER TO EQUIPMENT WITH OWNER.
20. PROVIDE POWER AND DATA FOR LAPTOP OVER THE COUNTER, VERIFY REQUIREMENTS WITH A/V CONSULTANT, (COGNATE DIRECTLY UNDER LCD SCREEN)

NOT FOR CONSTRUCTION: 12.14.09

| | | | |
|--|---|---|---|
| BRADFORD J DUDLEY 365 THIRD STREET LIQUAN BEACH, CALIFORNIA 92661 T: 949.783.3078 F: 949.783.3078 | E:\Project\Graphic Design Files\VM PS.dwg METAIRIE, LA 3321 HESSNER AVENUE METAIRIE, LA 70002 | CLIENT: MARK AND USA PUERTO | PROFESSIONAL SEAL: |
| SUBMISSION DATE CONCEPT PLAN 12/01/09 CONSULTANT COORDINATION 12/14/09 | PROJECT NO: 0921 SCALE: 1/8" = 1' | SIGNATURE _____ DATE _____ | POWER LAYOUT PLAN SECOND FLOOR A 202 |